

# PRELIMINARY ASSESSMENT & SITE INVESTIGATION

## CAT SWAMP HILL DUMP SITE

BYRAM TOWNSHIP, SUSSEX COUNTY, NEW JERSEY

EPA ID NO. NJ0000200998

VOLUME I OF II



New Jersey Department of Environmental Protection and Energy  
Division of Publicly Funded Site Remediation  
Bureau of Environmental Measurements and Quality Assurance

CAT SWAMP HILL DUMP SITE  
AKA: SHAWS DUMP  
ROUTE 206  
BYRAM TOWNSHIP, SUSSEX COUNTY, NEW JERSEY

TABLE OF CONTENTS

NARRATIVE

MAPS

1. UNITED STATES GEOLOGIC SURVEY (USGS) TOPOGRAPHIC MAP - STANHOPE QUADRANGLE (1981)
2. LOCAL TAX MAP (1990)
- 3A. SITE MAP (1994)
- 3B. SAMPLE POINT SITE MAP (1995)
4. SUSSEX COUNTY ROAD MAP (1986)
5. WATER WITHDRAWAL POINTS MAP (1994)
6. NATIONAL WETLANDS INVENTORY MAP (1975)
7. FLOOD INSURANCE RATE MAPS (1984)

PHOTOGRAPHS

ATTACHMENTS

- A. NJDEP, DIVISION OF PUBLICLY FUNDED SITE REMEDIATION (DPFSR), SITE ASSESSMENT, LETTERS AND INCIDENT REPORT RE: CAT SWAMP HILL DUMP SITE; SEPTEMBER 1993
- B. UNITED STATES DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, SUSSEX COUNTY SOIL SURVEY
- C. BYRAM TOWNSHIP ENVIRONMENTAL COMMISSION, SURFICIAL GEOLOGY AND BEDROCK GEOLOGY MAPS FOR BYRAM TOWNSHIP
- D. BYRAM TOWNSHIP ENVIRONMENTAL COMMISSION, LETTER AND MAP RE: GROUND WATER USAGE IN BYRAM TOWNSHIP; JANUARY 14, 1994
- E. NJDEP, DIVISION OF WATER RESOURCES (DWR), PUBLIC COMMUNITY WATER SUPPLY SHEETS; VARIOUS DATES
- F. NJDEP, DPFSR, OFFICE OF SITE ASSESSMENT (OSA), PRIVATE POTABLE WELL DOCUMENTATION; APRIL 1994

- G. NJDEP, DPFSR, SITE ASSESSMENT, POPULATION CALCULATIONS WITHIN A 4-MILE RADIUS OF THE CAT SWAMP HILL DUMP SITE; APRIL 1994
- H. NJDEP, DIVISION OF COASTAL RESOURCES, 1961 AND 1974 AERIAL PHOTOGRAPHS OF THE CAT SWAMP HILL DUMP SITE
- I. NJDEP, DPFSR, OSA, PRE-SAMPLING ASSESSMENT REPORT; APRIL 8, 1994
- J. U.S. DEPARTMENT OF THE INTERIOR, NORTHWEST NEW JERSEY AN INVENTORY AND HISTORY OF HISTORIC ENGINEERING AND INDUSTRY, HISTORY OF U.S. MINERAL WOOL COMPANY, STANHOPE NEW JERSEY; 1979
- K. BYRAM TOWNSHIP ENVIRONMENTAL COMMISSION, LETTERS RE: PRIVATE POTABLE WELL RECORDS; JUNE 7, 1994
- L. U.S. GEOLOGICAL SURVEY, WATER RESOURCES DATA OF NEW JERSEY, WATER YEAR 1992
- M. NJDEP, ENVIRONMENTAL MEASUREMENTS AND QUALITY ASSURANCE (EMSA), NATIONAL WETLANDS INVENTORY MAPS, 15 MILE STREAM ROUTE MAP; 1975
- N. NEW JERSEY DIVISION OF FISH GAME AND WILDLIFE, 1995 SPRING TROUT STOCKING SCHEDULE; 1995
- O. NJDEP, BUREAU OF ENVIRONMENTAL MEASUREMENTS AND QUALITY ASSURANCE (BEMQA), ANALYTICAL DATA VALIDATION; SEPTEMBER 29, 1994, NOVEMBER 16, 1994
- P. NJDEP, BEMQA, SAMPLE DATA SHEETS FOR JUNE 16, 1994 SITE INSPECTION; JULY 28, 1994

NARRATIVE



# PRELIMINARY ASSESSMENT AND SITE INVESTIGATION REPORT

## PART I: GENERAL INFORMATION

Site Name: Cat Swamp Hill Dump Site  
Aka: Shaws Dump  
Address: Route 206  
Municipality: Byram Township State: New Jersey Zip Code: 07874  
County: Sussex  
EPA ID No.: NJ0000200998  
Block: 366 Lot(s): 10  
Block: 366 Lot(s): 3  
Latitude: 40° 55' 23" Longitude: 74° 43' 52"  
Acreage: Lot 10, 25.43 SIC Code: 4953  
Lot 3, 225.46  
Dump Site, Approx 10

Current Owner: 136717/136718 Canada Inc. (Block 366, Lot 10)  
c/o Larry Wainberg  
Mailing Address: 4645 Boulevard Def. Grandes PR  
City: St. Leonard State: Quebec Zip Code: HIR185

Current Owner: NJDEP (Block 366, Lot 3)  
Mailing Address: Labor and Industry Building  
City: Trenton State: New Jersey Zip Code:

Current Operator: None, site is an inactive dump.

### Owner/Operator History:

<u>NAME</u>	<u>OPERATOR/ OWNER</u>	<u>DATES</u> <u>FROM</u>	<u>TO</u>
136717 Canada Inc./ 136718 Canada Inc.	owner	11/30/86	present
NJDEP (Block 366, Lot 3)	owner	1982	present
11 Overbrook Corp.	owner	11/30/86	11/30/86
Subco. Inc.	owner	11/26/86	11/30/86
Kurt Erickson, Donald Bell, William Roche	owners	5/1/85	11/26/86
Michael & Madeline Hydash	owners	6/6/73	5/1/85
Robert & Madeline Shaw	owners	3/6/52	6/6/73

**Surrounding Land Use (zoning, adjacent properties):**

Land in the immediate area of the site is primarily wooded and undeveloped. Area land uses include residential and commercial properties.

**Distance to Nearest Residence or School:** 1,200 feet

**Direction:** North

**Population Density (residents per square mile):** 385

**PART II: SITE OPERATIONS**

**Discuss all current and past operations at the site. Identify all waste sources, the type and quantity of hazardous waste at each source and the type of containment for each source.**

The Cat Swamp Hill Dump is a 10-acre site located west of Route 206 in Byram Township, Sussex County on parcels owned by a Canadian developer, Larry Wainberg, and the NJDEP. The southern portion of the dump (approximately 3.5 to 4 acres) is located on NJDEP property which was obtained by eminent domain in 1982 to be added to the Allamuchy Mountain State Park (Block 366, Lot 3, 225.46 acres). The remainder of the site lies on the Wainberg property (Block 366, Lot 10, 25.43 acres). The original dump site was owned by Robert Shaw and was actively being landfilled during his ownership of the property from 1952 to 1973. It could not be determined at the time of the deed search if Mr. Shaw had owned that portion of the dump site currently on NJDEP property at the time of dumping or if he had expanded his dump onto this property. (Attachment A)

It has been reported by the Byram Township Environmental Commission that the site operated for about two decades until it was closed in the mid 1960s. The Byram Township Environmental Commission conducted preliminary investigations of the site using aerial photographs and interviews with local residents and past site workers. The Commission reports that several long trenches were dug at the site to receive household and industrial wastes as well as numerous large bails of insulating material. Interviews with a truck driver who brought materials to the site revealed that the bails of material, along with some furnace wastes, were from the Mineral Wool Company in Stanhope (now the U.S. Mineral Products Company). Many other residents familiar with the site used it for deposition of construction and household wastes. When the site was recently being considered for development, residents attending township meetings reported that industrial dumping had occurred at the site as well. (Attachments A, J)

Local residents reported regular dumping from the Mineral Wool Company as well as liquid industrial wastes and drums from unknown sources. A bulldozer operator who worked at the site for

approximately two years reported that most of the refuse disposed of at the site was household wastes interlayered with Mineral Wool wastes (insulating materials, fireproofing materials and furnace waste resulting from burning of slag to make rock wool); however, he did notice a number of drums including at least two or three flatbed trucks, stacked with 50-gallon drums, dumped into trenches and other excavations. He also stated that the trenches were dug to get cover soil to put over the garbage. It was reported in the Byram Township investigation that these trenches were dug to the bedrock, which would eliminate even the modest benefits of soil to confine any liquid wastes. (Attachment A)

An additional review of aerial photographs was conducted by NJDEP, Office of Site Assessment personnel to determine the history of the site. Early photographs from 1939 and 1951 indicated that the site was an open, unwooded hilltop which appeared to be covered with grasses and other low vegetation. The first signs of disturbance were noted in the subsequent set of photographs dated 1961. These photographs revealed a long trench in the northwest section of the site running from the northeast to the southwest approximately 500 feet long. The excavated soil was piled along the northwest side of the trench and numerous trucks were noted along the southeast side of the trench. It appeared that some objects were within the trenches; however, it was unclear as to what the objects were. In these same photographs a kidney shaped area approximately 300 by 75 feet was noted in the southeast corner of the dump site. It appeared to have large bails of material and other unknown solid wastes piled throughout its eastern side. In later photographs this area had been backfilled and did not show the previously identified bails and solid wastes. A third smaller dump area was also evident in the 1961 aerial photographs. This small dump area was located just to the northeast of the kidney shaped dump area and had solid wastes and refuse within its boundaries. The next set of aerial photographs, from 1974, revealed that the large trench, as well as the kidney shaped dump and smaller dump area to the northeast had apparently been backfilled as these no longer appeared on these plates. The 1974 photographs did reveal four trenches located centrally between the large trench and the kidney shaped dump area previously discussed. It has been reported by workers at the site that these trenches were dug to obtain soil for backfilling the other dump areas. No activity was expected in photographs later than 1974 as the dump was reportedly closed sometime in the mid 1960s. (Attachment H)

A Pre-Sampling Assessment was conducted on April 8, 1994 by NJDEP, Office of Site Assessment personnel and members of the Byram Township Environmental Commission. The inspection revealed several trenches and areas of solid waste disposal on the site. Solid wastes noted on site included drums, metal foils, unknown insulating materials, tires, slag wastes and various other household garbage. Soil gas surveys conducted in those areas where alleged liquid waste dumping occurred did not reveal significant

readings above background; however, it is possible that these alleged materials may have leached to the subsurface due to the elapsed time since deposition. Details of this inspection are provided in Attachment I.

Subsequently, a site investigation was conducted at the site to confirm allegations of dumping and landfilling at the site. A total of 24 soil and three potable well samples were collected on June 16, 1994 by NJDEP personnel during this inspection. Sample results are summarized in the appropriate pathway sections of this report and in Table I.

### PART III: PERMITS

#### A. NJPDES

<u>Number</u>	<u>Discharge Activity</u>	<u>Date Issued</u>	<u>Expiration Date</u>	<u>Formation or Body of Water Discharged To</u>
---------------	---------------------------	--------------------	------------------------	---

N/A

#### B. New Jersey Air Pollution Control Certificates

Plant ID No.: N/A

No. of Certificates: None issued

Equipment Permitted: N/A

#### C. BUST Registration

Registration No.: N/A

No. of Tanks:

<u>Tank No.</u>	<u>Capacity (gallons)</u>	<u>Contents of Tank</u>	<u>Integrity</u>
-----------------	---------------------------	-------------------------	------------------

No underground storage tanks exist at this site.

#### D. Other Permits

<u>Agency Issuing Permit</u>	<u>Type of Permit</u>	<u>Permit No.</u>	<u>Date Issued</u>	<u>Expiration Date</u>
------------------------------	-----------------------	-------------------	--------------------	------------------------

N/A

#### PART IV: SOIL EXPOSURE

Describe soil type. Include soil series, composition of the soil and permeability of the soil.

The United States Department of Agriculture, Soil Conservation Service lists the soils at the dump site as Rockaway Series and Rock Outcrop. The Rockaway Series consists of deep, well-drained, gently sloping to very steep soils on uplands. These soils are formed in coarse-textured or moderately coarse-textured glacial till. The lower portion of the soil profile is a fragipan of very firm, dark brown and yellowish-brown gravelly sandy loam approximately 14 inches thick. The Rockaway-Rock outcrops are 70 to 90 percent bedrock outcrops, rock rubble, or soil material less than 10 inches thick and 5 to 20 percent extremely stony Rockaway soils. Slopes range from 25 to 35 percent. (Attachment B)

Discuss contaminants identified in the soil. Include sampling date, sampling agency or company, sample locations, depth and contaminant level. Identify samples collected from a residential property, school, daycare center, workplace, terrestrial sensitive environment or resource. State whether Level 1 or Level 2 contamination is present.

A site investigation was conducted at this site on June 16, 1994 by the NJDEP, Office of Site Assessment to determine if dumping activities had caused any soil contamination. At this time 24 soil samples were collected in and around the alleged dump areas and near the adjacent wetland to the east. Sample results above current NJDEP Soil Cleanup Criteria (SCC) are listed below. For a complete list of contaminants detected see Table I.

Sample #	Depth/Description	Contaminants	ppm	SCC (ppm)
S-1	3-4 feet, Area #1	beryllium	1	1
S-2	0-6 inches, drum carcass area, north end of site	PCBs beryllium zinc	24 4.4 12,700	2 1 1,500
S-3	2.5-3 feet, north end of Area #2	beryllium	1.6	1
S-4	12-18 inches, middle of Area #2	none above standard	NA	NA
S-5	3 feet, between Area #1 and Area #2	none above standard	NA	NA
S-6	2 feet, between Area #1 and Area #2	none above standard	NA	NA

S-7	4-5 feet, between Area #1 and Area #2	beryllium	1.1	1
S-8	4 feet, trench #1, Area #3	PCBs beryllium	3.5 3.8	2 1
S-9	3.5 feet, middle of trench 1 in Area #3	PCBs beryllium	4.86 4.6	2 1
S-10	5 feet, trench #1, Area #3	PCBs beryllium	8.1 2.5	2 1
S-11	4 feet, trench #2, Area #3	none above standard	NA	NA
S-12	4 feet, trench #2, Area #3	PCBs beryllium lead zinc	2.2 2.5 5,400 2,270	2 1 600 1,500
S-13	3 feet, trench #3, Area #3	beryllium	2.5	1
S-14	3 feet, trench #3, Area #3	PCBs beryllium	430 7.3	2 1
S-15	5 feet, trench #4, Area #3	beryllium	1.2	1
S-16	4-4.5 feet, trench #4, Area #3	beryllium	2.9	1
S-18	4.5 feet, below drums east of trench #4, Area #3	beryllium	3.5	1
S-19	0-6 inches, below drums east of trench #4, Area #3	beryllium nickel	2.6 2,990	1 2,400
S-20	0-6 inches, near drums in Area #5	PCBs beryllium TPHC	8.3 1.2 11,000	2 1 10,000
S-22	2-3 feet, north end of landfilled area	beryllium	3	1
S-23	3.5-4 feet, in landfilled area	beryllium zinc	7 2,020	1 1,500
S-24	12 inches, in landfilled area	beryllium	8.8	1
S-26	0-12 inches, at swamp edge	none above standard	NA	NA

S-27	0-12 inches, at swamp edge	thallium	21.7	2
------	-------------------------------	----------	------	---

Total area of surficial contamination (square feet): Estimated at 50,000+ square feet.

If no soil sampling has been conducted, discuss areas of potentially contaminated soil, areas that are visibly contaminated or results from soil gas surveys.

Soil sampling has been conducted at this site.

Determine if any commercial agriculture, silviculture, livestock production or grazing are present on or within 200 feet of the site.

No commercial agriculture, silviculture, livestock production or grazing is conducted within 200 feet of this site.

Number of people that occupy residences or attend school or day care on or within 200 feet of the site: none

Number of workers on or within 200 feet of the site: none

Number of on-site employees: none

#### PART V: GROUND WATER ROUTE

##### A. HYDROGEOLOGY

Describe geologic formations and aquifer(s) of concern. Include interconnections, confining layers, discontinuities, composition, hydraulic conductivity and permeability.

Geologic maps provided by the Township of Byram indicate that the site geology consists of Quaternary glacial deposits underlain by shallow bedrock. Two formations of bedrock exist below the site which are divided by a northeast to southwest line. (see Attachment C) The northwestern portion of the dump site is underlain by hornblende syenite while the southeastern portion is underlain by a blend of hypersthene, quartz and andesine gneiss. Thickness of these formations below the site are unknown. (Attachment C)

Depth to aquifer of concern: unknown

Depth from lowest point of waste disposal/storage to highest seasonal level of the saturated zone of the aquifer of concern: unknown

Permeability of the least permeable layer between the ground

surface and the aquifer of concern:  $10^{-6}$  to  $10^{-8}$  cm/sec

Thickness of aquifer: unknown

Direction of ground water flow: variable over the area of the site.

Karst (Y/N): No; however, the Franklin Lime Formation is karst and is within the 4 mile target distance limit.

Wellhead Protection Area (Y/N): No Distance: N/A

#### B. MONITORING WELL INFORMATION

<u>Well No.</u>	<u>Screen Depth</u>	<u>Formation</u>	<u>Location</u>
-----------------	-------------------------	------------------	-----------------

No monitoring wells exist at this site.

Identify the upgradient well(s): N/A

Briefly discuss why the monitoring wells were installed and describe contaminants identified in the monitoring wells. Include Well No., sampling date, sampling agency or company, contaminant levels and remediation standards. Discuss any other groundwater sampling that has occurred.

No monitoring wells exist at this site.

#### C. POTABLE WELL INFORMATION

Distance to nearest potable well: 1,200 feet

Depth of nearest potable well: 124 feet

Identify all public supply wells within 4 miles of the site:

<u>Water Company</u>	<u>Distance from site (miles)</u>	<u>Depth (feet)</u>	<u>Formation</u>
Brookwood- Musconetcong River	0.3 (3)	66-350	Kittatinny & Gneiss
Willor Manor	0.75	unknown	Quaternary Dep.
Strawberry Point	0.75	unknown	Granite Bedrock
North Shore	1.0	unknown	Amphibolite
Colby	1.4	unknown	Gneiss Bedrock
East Brookwood Estates	1.4	unknown	Quaternary Dep.



<u>Water Company</u>	<u>Distance from site (miles)</u>	<u>Depth (feet)</u>	<u>Formation</u>
Stanhope Borough	1.4-1.9 (4)	97-225	Franklin Limes & Gneiss
Mount Olive Township	2.1-2.7 (5)	49-344	Terminal Moraine & Granite
Mount Olive Township	3.3-3.8 (7)	96-422	Granite Bedrock
Forest Lakes	3.8 (2)	65,102	Stratified Drift
Roxbury Township	3.0-3.9 (5)	75-365	Granite & Stratified Drift
Hopatcong Borough	3.0-3.7 (9)	74-500	Undifferentiated PreCambrian
Ard. Mt. Olive Assoc. (Map 5, Attachment E)	3.6 (2)	350,400	Undifferentiated PreCambrian

**Discuss private potable well use within 4 miles of the site. Include depth, formation and distance, if available.**

A number of private potable wells exist in the area of the site. These wells are generally screened less than 200 feet deep in Precambrian crystalline bedrock, with a majority in the 100-150 foot range. These private potable wells are intermixed in areas of Byram Township which are served by a number of smaller water companies. (Attachments D, F)

**Discuss the site's source of potable water.**

This site does not have a potable water source.

**Discuss for each aquifer the population utilizing that aquifer for drinking purposes within 4 miles of the site.**

<u>Distance from site (miles)</u>	<u>A</u>	<u>Population/Aquifer</u> <u>B</u>	<u>C</u>
0 - 1/4	3	0	0
1/4 - 1/2	1,060	0	0
1/2 - 1	345	55	0
1 - 2	4,075	615	925
2 - 3	1,000	0	0
3 - 4	18,035	1,265	0

- A - Bedrock Aquifers
- B - Glacial Deposits
- C - Franklin Limestone

Discuss information regarding potable well sampling related to the site. Also include any other evidence of contaminated drinking water or wells closed due to contamination. State whether Level 1 or Level 2 contamination is present.

Three private potable wells were sampled as part of the site inspection conducted at this site on June 16, 1994. Only one of the wells sampled, 2 Sutton Lane, exhibited contamination with 4 ppb of trichlorethene above current NJDEP, Ground Water Quality Standards. Attribution could not be established to link this site to the contamination found in the potable well, therefore, Level 1 or Level 2 cannot be established for this sample.

Identify industrial/irrigational wells within the vicinity of the site. Include depth, formation, distance and direction, if available.

The closest industrial/irrigational well is located 1.8 miles south of the site. This well is screened at 553 feet in the Leithsville Formation and is operated by N.J. Foreign Trade Zone. (Map 5)

#### D. POTENTIAL

Discuss the potential for ground water contamination, including any other information concerning the ground water contamination route.

It has been reported by local residents and previous workers at the site that liquid industrial wastes and numerous drums have been landfilled or directly dumped on the ground surface. However, sampling of local potable wells by NJDEP personnel did not reveal contamination attributable to the site. (Attachment A)

### PART VI: SURFACE WATER ROUTE

#### A. SURFACE WATER

Does a migration pathway to surface water exist? (Y/N):

Flood plain: >500 year (Map 7)      Slope: 3% - 40% (Map 1)

Does contaminated ground water discharge to surface water? (Y/N):  
No

Identify known or potentially contaminated surface water bodies. Follow the pathway of the surface water and indicate all adjoining

bodies of water along a route of 15 stream miles.

<u>Surface Water Body</u>	<u>Distance from site</u>	<u>Flow(cfs)</u>	<u>Usage(s)</u>
Unnamed tributary of Musconetcong River	0.5 miles	50 cfs	Recreation, Fishing
Musconetcong River	1.6 miles	100 cfs	Recreation, Fishing
Waterloo Lakes	2.6 miles	<10 cfs	Recreation, Fishing
Musconetcong River	3.1 miles	100 cfs	Recreation, Fishing
Saxton Lake	5.2 miles	<10 cfs	Recreation, Fishing
Musconetcong River	6.3 miles	100 cfs	Recreation, Fishing

Identify drinking water intakes and fisheries within 15 miles downstream (or upstream in tidal areas) of the site. For each intake or fishery identify the distance from the point of surface water entry, the name of the fishery and/or supplier and population served.

No drinking water intakes were identified for the 15 mile stream route; however, the Musconetcong River is stocked annually with trout and is utilized heavily for recreational fishing. Over 10,000 trout were stocked in the upper segment of the Musconetcong River in the spring of 1995.

Discuss surface water or sediment sampling conducted in relation to the site. Discuss visual observations if analytical data are not available (include date of observation). Include surface water body, sampling date, sampling agency or company, contaminant. State whether Level 1 or Level 2 contamination is present.

During the June 16, 1994 site inspection of the facility by NJDEP personnel, two soil samples were collected at the edge of the wetland which abuts the site to the east. One exceedence of current NJDEP Soil Cleanup Criteria for thallium was observed for these samples, however, attribution could not be established for this sample and it should not be considered an observed release.

Determine if surface water is used for irrigation of commercial

food or commercial forage crops, watering of commercial livestock or commercial food preparation.

No irrigational or commercial surface water intakes were identified within the 15 mile surface water route.

Discuss the potential for surface water contamination, include any additional information concerning the surface water route.

Surface water runoff from the eastern edge of the dump area, is received by a wetland area which abuts the dump on the eastern side. Thallium was detected at elevated levels in one sample collected at the edge of the wetland, however, attribution could not be established for this sample and it should not be considered an observed release. (Maps 1, 6)

## B. SENSITIVE ENVIRONMENTS

Identify all sensitive environments, including wetlands, along the 15 stream-mile pathway from the site:

<u>Environment</u> <u>Type</u>	<u>Surface Water</u> <u>Body</u>	<u>Flow</u> <u>(cfs)</u>	<u>Distance</u> <u>from site</u>	<u>Wetland</u> <u>Frontage</u>
PFO1	Wetland	<10	0.0 mile	0.4 mile
PFO/SS1	Unnamed tributary	50	0.5 mile	0.55 mile
PFO1	Unnamed tributary	50	0.75 mile	1.5 miles
PFO/SS1	Musconetcong River	100	1.8 miles	0.4 mile
PFO1	Musconetcong River	100	2.0 miles	0.55 mile
PSS1	Musconetcong River	100	2.3 miles	0.1 mile
PFO1	Musconetcong River	100	2.4 miles	0.1 mile
PSS1	Musconetcong River	100	2.5 miles	0.8 mile
PSS1	Musconetcong River	100	3.1 miles	0.3 mile
PFO1	Musconetcong River	100	4.5 miles	0.6 mile
PFO1	Musconetcong River	100	10.9 miles	0.5 mile
PFO/SS1	Musconetcong River	100	11.4 miles	1.1 miles
PFO1	Musconetcong River	100	12.5 miles	0.4 mile

PFO1 - Palustrine forested

PFO/SS1 - Palustrine forested/scrub shrub

PSS1 - Palustrine scrub/shrub

(Attachment M)

## PART VII: AIR ROUTE

Discuss observed or potential air release.

The primarily areas of concern at this site deal with buried solid wastes. The potential for air release at this site is very low.

Identify populations residing within 4 miles of the site.

<u>Distance (miles)</u>	<u>Population</u>
0 - 1/4	3
1/4 - 1/2	10
1/2 - 1	9,180
1 - 2	13,015
2 - 3	8,210
3 - 4	13,955

(Attachment G)

Identify sensitive environments and wetland acreage within 4 miles of the site.

<u>Distance</u>	<u>Type of environment</u>	<u>Wetland acreage</u>
-----------------	----------------------------	------------------------

Several small palustrine forested wetland areas exist within 0.5 mile of the site. The closest of these is located within the boundaries of the dump site. (Map 6)

Identify all land resources (commercial agriculture, silviculture or recreation) within 4 miles of the site.

This site abuts the Allamuchy Mountain State Park and is within 4 miles of several lakes and ponds that are used for recreational purposes; however, an air release from this site is unlikely.

Determine if a contaminant on site displays bioaccumulative properties. Identify all bioaccumulative substances that may impact the food chain.

PCBs, which are known to be bioaccumulative, have been detected in on-site soils at elevated levels.

#### PART VIII: REMOVAL ACTION AND/OR IEC CONDITION

Discuss conditions which constitute an IEC or warrant EPA Removal Action consideration (improper storage of incompatible/reactive materials, leaking or unsound containers, inadequate site security, subsurface gas threat).

Conditions at this site do not constitute an immediate environmental concern (IEC) nor do they warrant an EPA removal action.

#### **PART IX: PREVIOUS OR ONGOING REMEDIAL ACTIONS**

Discuss for each medium or area of concern all previous and ongoing remedial activities at the site. Include why initiated, type of action, date and present status.

No remedial activities were discovered for the site.

#### **PART X: ENFORCEMENT ACTIONS**

No enforcement actions were discovered for the dump site during the file search.

#### **PART XI: CONCLUSIONS AND RECOMMENDATIONS**

List each area of concern and state whether further remediation is required.

The following areas of concern have been identified at this site due to elevated levels of contaminants detected in on-site soils:

- The northern area of the site, which contains several drum carcasses displayed elevated levels of PCBs, beryllium and zinc. (S-2)
- Area #1 has displayed elevated levels of beryllium. (S-1)
- Area #2 has displayed elevated levels of beryllium. (S-3)
- One sample collected between Area #1 and Area #2 has displayed elevated levels of Beryllium. (S-7)
- Samples collected from Area #3, trenches #1 through #4, have displayed elevated levels of PCBs, beryllium, lead and zinc. (S-8 through S-16)
- Samples collected adjacent to drum carcasses to the southeast of Area #3 have displayed elevated levels of nickel and beryllium. (S-18, S-19)
- A sample collected adjacent to drum carcasses in Area #5 displayed elevated levels of PCBs, beryllium and TPHC. (S-20)
- Samples collected within the areas of landfilled debris and slag along the eastern border of the site displayed elevated levels of beryllium and zinc. (S-22, S-23, S-24)
- One sample collected at the edge of the wetland on the eastern edge of the dump site displayed elevated levels of thallium (S-27), however, attribution could not be established for this

sample and it should not be considered an observed release.

No further action is warranted under CERCLA. It is recommended that additional investigations be conducted to characterize the contaminated soils at this site and the potential for ground water and surface water contamination. It should also be noted that the levels of beryllium above the current NJDEP, Soil Cleanup Criteria of 1 ppm, may be attributable to the unique lithology indicative of this area of Sussex County.

**Submitted by:** David Dibblee

**Title:** HSMS 4

NJDEP, Division of Publicly Funded Site Remediation,  
Bureau of Environmental Measurements and Quality Assurance  
Environmental Measurements and Site Assessment Section

**Date:** June 1995

PART XII: POTENTIALLY RESPONSIBLE PARTIES

<u>NAME</u>	<u>OWNER/OPERATOR/ KNOWN DISCHARGER</u>	<u>CURRENT ADDRESS</u>
136717/136718 Canada Inc.	owner	4645 Boulevard Def. Grandes PR St. Leonard, Quebec, Canada HIR185
Robert and Madeline Shaw	owner/operator	unknown



### SUMMARY OF SAMPLING DATA VOLATILES

SAMPLE ID NO:

S-1	S-2	S-3	S-4	S-5	S-6	S-7	S-8	S-9	S-10	S-11	S-12	S-13	S-14	S-15
459	460	461	462	463	464	465	466	467	468	469	470	471	472	473

[illegible]

Byram Township, Sussex County

### SUMMARY OF SAMPLING DATA VOLATILES

UNITS: ppm

[illegible]

### SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 3 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: ppm

SAMPLE ID NO:

[illegible]

LOCATION: Route 206

Byram Township, Sussex County

### SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 4 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: ppm

[illegible]

Byram Township, Sussex County

## SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 5 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: ppm

[illegible]

Byram Township, Sussex County

### SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 6 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: ppm

SAMPLE ID NO:

[illegible]

SUMMARY OF SAMPLING DATA  
PESTICIDE ORGANICS, PCBs

PAGE 7 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: gpm

[illegible]

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: 2000

SAMPLE ID NO:

[illegible]



SITE NAME: Cat Swamp Hill Dump

LOCATION: Route 206

Byram Township, Sussex County

SUMMARY OF SAMPLING DATA  
METALS, CYANIDE

PAGE 9 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: ppm

SAMPLE ID NO:	S-1 459	S-2 460	S-3 461	S-4 462	S-5 463	S-6 464	S-7 465	S-8 466	S-9 467	S-10 468	S-11 469	S-12 470	S-13 471	S-14 472	S-15 473
ALUMINUM	1,800	1,800	17,500	14,000	40,400	15,200	16,800	31,600	36,400	31,400	18,200	23,300	25,600	50,700	24,900
ANTIMONY			7.0uJ	7.1uJ	7.3uJ	7.0uJ	6.8uJ			8.7uJ	8.6uJ	43.8JB	32.5JB	9.1uJ	
ARSENIC	7.7	2.7J	3.0	1.9J	2.4uJ	2.2J	1.4J	1.5uJ	14.9		6.5	9.3	8.3		8.7
BARIUM	93.2	348	80.9	109	110	64.8	76.6	336	488	273	122	342	986	387	137
BERYLLIUM	1.0J	4.4	1.6				1.1	3.8	4.6	2.5		2.5	2.5	7.3	1.2J
CADMIUM	0.45uJ	3.3J	1.1J	0.46uJ	0.47uJ	0.45uJ	0.44uJ	0.58uJ	0.53uJ	3.9J	1.1J	13.4J	2.5J	0.59uJ	0.59uJ
CALCIUM	4,570	102,000	2,940	3,490J	14,500J	1,850J	3,200J	111,000J	136,000J	46,900J	9,860J	63,200J	74,300J	202,000J	10,800J
CHROMIUM	36.4	35.3	17.2	13.3J	52.9	16.5J	23.5	39.5	43.9	51.9	30.0	68.9	90.7	28.7	34.1
COBALT	18.1	12.0	16.1	11.0J	23.8	12.5	11.8	11.7J	14.9	15.5	14.1	23.5	20.2		16.0
COPPER	22.7J	1,930	28.9	10.8J	2.4uJ	11.4J	13.3J	81.8J	139J	123J	40.0J	212J	246J	35.9J	40.7J
IRON	36900	43,200	31,000	27,500	33,900	29,600	31,400	49,600	72,900	64,000	38,000	148,000	104,000	8,820	40,500
LEAD	25.9	359J	7.6	4.0	2.9J	10.3J	7.2J	262J	190J	359J	55.3J	5,400J	703J	91.3J	84.0J
MAGNESIUM	5,170	15,500	3,050	3,470	8,810	2,800	3,600	25,600	28,300	9,940	4,900	13,300	14,300	62,700	5,960
MANGANESE	741	1,680	654	672J	713J	519J	617J	1,960J	1,890J	1,440J	2,010J	1,790J	1,710J	1,800J	1,590J
MERCURY	0.21							0.81	0.42	1.1	0.22	1.3	1.8	0.24	0.28
NICKEL	56.0	56.0	9.9J	10.9J	36.1	14.3J	16.7J	23.9J	30.5J	38.5J	20.6J	52.9J	37.2J	37.8J	30.5J
POTASSIUM	870	5,040	1,340	1,340	1,950	1,230	1,460	5,870	5,870	2,420	1,020	3,390	3,400	9,530	1,430

## SUMMARY OF SAMPLING DATA METALS, CYANIDE

PAGE 10 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil

UNITS: ppm

SAMPLE ID NO:

[illegible]

SITE NAME: Cat Swamp Hill Dump

LOCATION: Route 206

Byram Township, Sussex County

### SUMMARY OF SAMPLING DATA VOLATILES

PAGE 11 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil, Ground water

UNITS: Soil (ppm), water (ppb)

[illegible]

Byram Township, Sussex County

PAGE 12 OF 20

UNITS: Soil (ppm), Water (ppb)

[illegible]

Byram Township, Sussex County

PAGE 13 OF 20

UNITS: Soil (ppm), Water (ppb)

[illegible]

SITE NAME: Cat Swamp Mill Dump  
LOCATION: Route 206  
Byram Township, Sussex County

## SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 14 OF 20

DATE SAMPLED: June 16, 1994  
MATRIX: Soil, Ground Water  
UNITS: Soil (ppm), water (ppb)

[illegible]

LOCATION: Route 206

Byram Township, Sussex County.

### SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 15 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil, Ground Water

UNITS: Soil (ppm), Water (ppb)

[illegible]

LOCATION: Route 206

Byram Township, Sussex County

### SUMMARY OF SAMPLING DATA SEMIVOLATILES

PAGE 16 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil, Ground water

UNITS: Soil (ppm), water (ppb)

SAMPLE ID NO:

S-16  
474

S-18  
416

S-19  
477

S-20  
478

5-22  
480

S-23  
481

5-27  
482

S-26  
484

S-27  
195

PW-1  
488

PW-2  
489

HW-3  
490

P41-  
491

[illegible]



LOCATION: Route 206

Byram Township, Sussex County

SUMMARY OF SAMPLING DATA  
PESTICIDE ORGANICS, PCBs

PAGE 17 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil, Ground water

UNITS: Soil (ppm), Water (ppb)

SAMPLE ID NO:

5-10

5-18

3-19

5-20

5-22

5.73

5-24

52

Σ. 21.

2.1

100

1

•

474

476

4'1'1

478

480

431

487

5-26  
431

5-21  
495

FW-1

PW-2  
100

PW-3

PW-1

[illegible]

Byram Township, Sussex County

PESTICIDE ORGANICS, PCBs

PAGE 18 OF 20

DATE SAMPLED: June 16, 1999

MATRIX: Soil, Ground water

UNITS: Soil (ppm), Water (ppb)

SAMPLE ID NO:

S-16  
474

S-18  
476

5-19  
471

5-20  
478

5-22  
480

S-23  
481

S-24  
497

S-26  
AGA

S-271  
495

PW-1  
418

PW-2  
100

PW-3

RW-7

[illegible]

SITE NAME: Cat Swamp Hill Dump

LOCATION: Route 206

Byram Township, Sussex County

SUMMARY OF SAMPLING DATA  
METALS, CYANIDE

PAGE 19 OF 20

DATE SAMPLED: June 16, 1994

MATRIX: Soil, Ground Water

UNITS: Soil (ppm), Water (ppb)

SAMPLE ID NO:	S-16 474	S-18 476	S-19 477	S-20 478	S-22 480	S-23 481	S-24 482	S-26 484	S-27 485	PW-1 488	PW-2 489	PW-3 490	PW-4 491
ALUMINUM	31,700	25,900	19,200	5,130	15,700	43,600	50,400	16,000	34,700				
ANTIMONY			8.0uJ	6.8uJ		8.3uJ							
ARSENIC	6.3	7.7	1.5J	1.8J	32.2	4.3J	3.3J	5.6uJ	5.4J				
BARIUM	196	274	97.8	15.8J	512	409	493	124J	276	55uJ	55uJ	55uJ	55uJ
BERYLLIUM	2.9	3.5	2.6	1.2	3.0	7.0	8.8						
CADMIUM	2.0J	0.55uJ	0.52uJ	0.44uJ	0.46uJ	3.4J	4.3J	9.6J	5.3J				
CALCIUM	58,500J	79,400J	11,500J	3,420J	51,200J	170,000J	18,400J	17,600	18,700J	22,500J	5,300J	30,100J	21,900J
CHROMIUM	121	105	26.4	47.4	19.1J	24.5	89.8	25.0	44.6				
COBALT	17.5	15.5	25.3J	7.1J	31.4	9.1J	11.8						
COPPER	41.1J	290J	42.8J	235J	539J	48.9J	139J	19.4J	27.3J		795J		159J
IRON	44,800	54,600	38,700	17,300	28,700	31,400	14,600	11,800	18,100	90.4J			
LEAD	95.7J	526J	60.8J	55.2J	172J	85.8J	391J	76.9	97.1	3.0uJ	3.0uJ	3.0uJ	5.2J
MAGNESIUM	12,900	16,800	5,770	1,780	22,800	32,700	4,270	3,315J	3,970J	7,850		9,590	7,210
MANGANESE	1,360J	1,020J	453J	77.7J	797J	3,540J	2,430J	1,550J	1,820J				8.0J
MERCURY	0.6	0.57	0.21			0.3	0.18		0.52				
NICKEL	35.4J	1,180J	2,990J	22.4J	60.8J	23.3J	48.6J						
POTASSIUM	1.1uJ	3,660	4,100J	767J	5,110	7,120	9,880					1,890J	

SITE NAME: Cat Swamp Hill Dump  
 LOCATION: Route 206  
 Byram Township, Sussex County

PAGE 20 OF 20

SUMMARY OF SAMPLING DATA  
 METALS, CYANIDE

DATE SAMPLED: June 16, 1994  
 MATRIX: Soil, Ground Water  
 UNITS: Soil (ppm), Water (ppb)


SAMPLE ID NO:	S-16 474	S-18 476	S-19 477	S-20 478	S-22 480	S-23 481	S-24 482	S-26 484	S-27 485	Pw-1 488	Pw-2 489	Pw-3 490	Pw-4 491
SELENIUM		1.4UJ	1.3UJ	1.1UJ	2.3J	3.6J	3.2J	12.7J	8.1J				
SILVER							44.9						
SODIUM					1,360	1,780	1,690			3,690J			21,900
THALLIUM							1.1UJ		21.7				
VANADIUM	53.8	28.3	68.5	41.6	29.8	21.8	40.2	31.2J	51.1				
ZINC	825J	404J	191J	62.9J	586J	2,020J	393J	607J	985J			29.2J	
CYANIDE							1.3						
TOTAL PHCs	920	1,100	5,400	11,000	31	280	630	490	330	-	-	-	-

- ☐ - Analyte above current NJDEP Soil Cleanup Criteria or Ground Water Quality Standard  
 J - Estimated concentration  
 B - Analyte also detected in associated blank(s)

MAPS




SCALE 1:24000



CONTOUR INTERVAL 20. FEET  
DATUM IS MEAN SEA LEVEL

CAT SWAMP HILL DUMP SITE  
WEST OF RT. 206  
BYRAM TOWNSHIP, SUSSEX COUNTY  
LAT. 40 55' 23"  
LON. 74 43' 52"  
USGS TOPOGRAPHIC MAP  
MAP #1





BLOCK 366, LOT 10

 - AREAS OF LANDFILLED DEBRIS AND  
BALES OF INSULATING MATERIALS

 - TRENCHED AREAS

APPROXIMATE LANDFILL  
DIMENSIONS


BLOCK 366, LOT 3




ROUTE 206

CAT SWAMP HILL DUMP SITE  
WEST OF ROUTE 206  
BYRAM TOWNSHIP, SUSSEX COUNTY  
SITE MAP  
NOT TO SCALE





Cat Swamp Hill Dump Site  
West of Route 206  
Byram Township, Sussex County  
Site Map 3B, Sample Points



07821

- 1 OVERVIEW
- 2 WAM-PAN TR
- 3 H-TO-GA TR
- 4 LA-BO-GA TR
- 5 WA-TO-GA PASS
- 6 WO-MA-GA TR
- 7 PANTHER PASS
- 8 OPA PASS
- 9 SHON-GA PASS
- 10 PAW-TU PASS
- 11 HILL CREST TR
- 12 SPRING LA
- 13 WEAVER HOUSE RD
- 14 BROOK TR
- 15 HICKORY TR
- 16 RAUNGE TR
- 17 IVY LA
- 18 MUGGO TR
- 19 LANDONE TR
- 20 OLAN PASS
- 21 LAKE VIEW PASS
- 22 LONG VIEW TR
- 23 BALD ROCK TR
- 24 WHITE OAK TR
- 25 SOUTH LAKE TR
- 26 ROCK ISLAND PASS
- 27 STRAWBERRY POINT DR

- 1 HART TR
- 2 CEDAR TR
- 3 OAK TR
- 4 SPRUCE TR
- 5 COLES TR
- 6 MAPLE TR
- 7 CRANBERRY LEDGE RD

CAT SWAMP HILL DUMP SITE  
WEST OF RT. 206  
BYRAM TOWNSHIP, SUSSEX COUNTY  
COUNTY ROAD MAP  
MAP #4

SUBJECT TO REVISION

WATER WITHDRAWAL  
POINTS WITHIN  
5.0 MILES OF:

LATITUDE 405523  
LONGITUDE 744352

DRAFT


SCALE: 1:63,360  
(1.5 Inch = 1 Mile)

x 100,000 GPD WATER WITHDRAWAL POINTS ONLY

1 MILE AND 5 MILE RADII INDICATED

PLOT PRODUCED BY:  
NJDEPE  
WATER SUPPLY ELEMENT  
BUREAU OF WATER ALLOCATION  
CN-426  
TRENTON, NJ 08625  
DATE: 01/03/94

SUBJECT TO REVISION



NUMBER	NAME	SOURCEID	LOCID	LAT	LON	LLACC	DISTANCE	COUNTY	MUN	DEPTH	GEO1	GEO2	CAPACITY
10031W	HOUSE OF THE GOOD SHEPHERD	2405582	#1	405202	744825	T	5.5	41	08	173	GOKA		230
	HOUSE OF THE GOOD SHEPHERD		#2	405202	744825	U	5.5	41	08				
10077W	FLANDERS ASPHALT DIV. OF DELL	2515896	WELL #1	405310	744242	T	2.7	27	27	152	GFCGR		150
10265W	BYRAM HOMEOWNERS ASSOC. WATER	2218673	WELL 1	405920	744005	U	5.6	37	04	350	GFCGN		100
	BYRAM HOMEOWNERS ASSOC. WATER	2241336	WELL 2	405920	744005	U	5.6	37	04	275	GFCGN		100
10287W	U.S. MINERAL PRODUCTS/CANCELED	MUSCONETOONG	RIVER	405405	744240	U	1.8	37	19		SDMUS		100
10387W	MT. ARLINGTON SERVICE	2509929	WELL 1	405515	743820	U	4.8	27	26	97	GFC		
	MT. ARLINGTON SERVICE	2511292	WELL 2	405540	743840	U	4.6	27	26	200	GFC		
	MT. ARLINGTON SERVICE	2511821	WELL 5	405510	743820	U	4.8	27	26	273	GFC		
1173D	MT. ARLINGTON BOROUGH	WELL POINTS		405520	743840		4.6	27	26		GCGU		417
1174D	MUSCONETOONG S.A.	TRENCHES		405540	743830		4.7	27	26	20	GCGU		60
1175D	MT. OLIVE TOWNSHIP	WELLS	FSH2	405140	744513	F	4.4	27	27	30	GFCGR		
	MT. OLIVE TOWNSHIP	WELLS	FSH3	405231	744528	F	3.6	27	27	250	GFCGR		
	MT. OLIVE TOWNSHIP	TRENCHES		405310	744413	F	2.6	27	27	22	GFCGR		
1176D	BERTRAND ISLAND DEV. INC.	POINT TRENCHES		405535	743905	U	4.2	27	26	25	GCGU		150
2321P	SAXTON FALLS SAND & GRAVEL CO.	POND	1	405341	744708	F	3.5	27	27	90	GCGU		4500
	SAXTON FALLS SAND & GRAVEL CO.	POND	2	405325	744729	F	3.9	27	27	40	GCGU		1500
	SAXTON FALLS SAND & GRAVEL CO.	DEWATERING PIT		405334	744722	F	3.7	27	27	45	GCGU		6000
2439P	NJ FOREIGN TRADE ZONE	2523865	BR-3	405349	744330	T	1.8	27	27	553	GCKL		100
	NJ FOREIGN TRADE ZONE	2537536	BR-4	405346	744318	T	1.9	27	27	290	GCKL		800
5061	NETCOING BOROUGH	4500272	1	405318	744200	F	2.9	27	28	88	GCGU		205
	NETCOING BOROUGH	4500273	2	405318	744200	U	2.9	27	28	113	GCGU		265
	NETCOING BOROUGH	2526342	5	405347	744252	F	2.0	27	28	350	GFCGN		245
	NETCOING BOROUGH	2522910	6	405347	744252	F	2.0	27	28	240	GCGU		260
5098	FOREST LAKES WATER COMPANY	2200591	1	405839	744408	F	3.8	37	02	102	GOSD		100
	FOREST LAKES WATER COMPANY	2213368	3	405839	744408	F	3.8	37	02	65	GOSD		165
5101	ROXBURY WATER COMPANY	2201338	1	405108	743834	F	6.7	27	36	52	GOSD		150
	ROXBURY WATER COMPANY	2529720	7	405110	744120	T	5.3	27	36	175	GCKL		350
	ROXBURY WATER COMPANY	4500315	4	405111	743842	F	6.6	27	36	40	GOSD		300
	ROXBURY WATER COMPANY	2525540	6	405235	743817	F	5.8	27	36	57	GOSD		290
	ROXBURY WATER COMPANY	2505279	2	405114	743848	F	6.5	27	36	160	GTRCG		150
	ROXBURY WATER COMPANY	2534457	1A	405108	743834	F	6.7	27	36	700	GCKL		200
	ROXBURY WATER COMPANY	2544470	7A	405110	744113	F	5.4	27	36	182	GCKL		350
5103	MOUNT OLIVE TOWNSHIP	2519568	STONEHEDG1	405245	744520	T	3.3	27	27	172	GFCGR		75
	MOUNT OLIVE TOWNSHIP	2519567	STONEHEDG2	405245	744520	T	3.3	27	27	173	GFCGR		75
	MOUNT OLIVE TOWNSHIP	25147838	STONEHEDG3	405245	744520	T	3.3	27	27	96	GFCGR		120
	MOUNT OLIVE TOWNSHIP	2514561A	STONEHEDG4	405245	744520	T	3.3	27	27	266	GFCGR		72
	MOUNT OLIVE TOWNSHIP	4500028	HIGHRIDGE1	405208	744342	F	3.7	27	27	210	GFCGR		20
	MOUNT OLIVE TOWNSHIP	4500029	JUCKETT 1	405135	744430	F	4.4	27	27		GFCGR		20
	MOUNT OLIVE TOWNSHIP	2515906	VILLAGEGR1	405304	744342	T	2.7	27	27	344	GFCGR		45
	MOUNT OLIVE TOWNSHIP	2516087	VILLAGEGR2	405306	744340	T	2.6	27	27	81	GOTM		95
	MOUNT OLIVE TOWNSHIP	2517318	VILLAGEGR3	405332	744347	F	2.1	27	27	49.5	GOTM		105
	MOUNT OLIVE TOWNSHIP	2518054	VILLAGEGR4	405328	744355	F	2.2	27	27	88	GOTM		180
	MOUNT OLIVE TOWNSHIP	PROPOSED	VILLAGEGR5	405332	744345	T	2.1	27	27		GOTM		
	MOUNT OLIVE TOWNSHIP	2518429	GOLDMINE 1	405205	744330	F	3.8	27	27	422	GFCGR		30
	MOUNT OLIVE TOWNSHIP	2518506	GOLDMINE 2	405205	744330	F	3.8	27	27	248	GFCGR		34
	MOUNT OLIVE TOWNSHIP	2404095	INDIAN SP1	405210	744558	F	4.1	27	27	97	GOTM		85
	MOUNT OLIVE TOWNSHIP	2405720	INDIAN SP2	405210	744558	F	4.1	27	27	92	GOTM		300
	MOUNT OLIVE TOWNSHIP	4500346	PINECREST1	405150	744415	T	4.1	27	27		GOTM		80
	MOUNT OLIVE TOWNSHIP	4500347	PINECREST2	405150	744415	T	4.1	27	27		GOTM		80
	MOUNT OLIVE TOWNSHIP	2526556	HOFER 1	405140	744228	F	4.4	27	27	485	GFCGR		100
	MOUNT OLIVE TOWNSHIP	2526567	HOFER 2	405140	744228	F	4.4	27	27	647	GFCGR		60
	MOUNT OLIVE TOWNSHIP	2517885	LYNNWOOD 1	405147	744345	T	4.1	27	27		GFCGR		32
	MOUNT OLIVE TOWNSHIP	2518201	LYNNWOOD 2	405147	744345	T	4.1	27	27	148	GFCGR		15
5145	HACKETTSTOWN M.U.A.	2405556	4 (SEBER)	405113	744846	F	6.4	41	08	37	GOSD		300

NUMBER	NAME	SOURCEID	LOCID	LAT	LON	LLACC	DISTANCE	COUNTY	MUN	DEPTH	GEO1	GEO2	CAPACITY
	HACKETTSTOWN M.U.A.	2407212	5 (SEBER)	405105	744849	F	6.6	41	08	143	GDOK		1000
5146	HACKETTSTOWN M.U.A.	LOW MINE HILL	RESERVOIR	405138	744720	F	5.3	27	27		SDMUS		
5165	STANHOPE BOROUGH	4500030	2	405435	744216	F	1.7	39	19	97	GPCGN		125
	STANHOPE BOROUGH	4500031	3	405421	744300	F	1.4	27	27	117	GPCGN		350
	STANHOPE BOROUGH	2511618	4	405421	744300	F	1.4	27	27	103	GPCGN		225
	STANHOPE BOROUGH	2521153	5	405412	744224	F	1.9	37	19	225	GPCFL		500
5263	ANDOVER BOROUGH WATER DEPT.	4200001	1	405925	744425	F	4.7	37	01	44	GDSD		40
	ANDOVER BOROUGH WATER DEPT.	4200002	2	405925	744425	F	4.7	37	01	42	GDSD		75
5277	BROOKWOOD-MUSCONETCONG RIVER	2521375	3	405510	744357	F	0.3	37	04	350	GPCGN		120
	BROOKWOOD-MUSCONETCONG RIVER	2513822	2	405510	744355	U	0.3	37	04	200	GPCGN		75
	BROOKWOOD-MUSCONETCONG RIVER	2504732	1	405510	744355		0.3	37	04	66	GDOK		75
5287	HOPATCONG BOROUGH	2507325	8	405540	743956	F	3.5	37	12	93	GPC		60
	HOPATCONG BOROUGH	2509585	12	405548	743955	F	3.5	37	12	165	GPC		60
	HOPATCONG BOROUGH	2521763	SQUIRE	405549	743959	F	3.4	37	12	148	GPC		75
	HOPATCONG BOROUGH	2221308	RIVER STYX	405634	743927	F	4.1	37	12	475	GPC		70
	HOPATCONG BOROUGH	4200007	1	405631	743955	F	3.7	37	12	79	GPC		40
	HOPATCONG BOROUGH	2200020	2	405626	743950	F	3.7	37	12	147	GPC		40
	HOPATCONG BOROUGH	2200096	3	405622	743947	F	3.7	37	12	74	GPC		75
	HOPATCONG BOROUGH	4200008	4	405624	744043	F	3.0	37	12	150	GPC		40
	HOPATCONG BOROUGH	2201097	5	405700	743919	F	4.4	37	12	120	GPC		60
	HOPATCONG BOROUGH	4500283	MARINER V	405535	743936	F	3.7	37	12		GPC		35
	HOPATCONG BOROUGH	2228355	3A	405622	743947	F	3.7	37	12	500	GPC		68
5289	MT. OLIVE VILLAGES WATER CO.,	2516478	2	405130	744430	F	4.5	27	27	130	GPC		150
	MT. OLIVE VILLAGES WATER CO.,	2517783	3	405122	744528		4.8	27	27	200	GPC		150
	MT. OLIVE VILLAGES WATER CO.,	2523162	4	405140	744439	F	4.3	27	27	200	GPC		150
5295	ROXBURY TOWNSHIP WATER DEPT.	2501042	2	405430	743920		4.1	27	36	88	GDSD		250
	ROXBURY TOWNSHIP WATER DEPT.	2512596	3	405206	744127		4.3	27	36	135	GPCGR		150
	ROXBURY TOWNSHIP WATER DEPT.	4500288	4	405430	744010		3.4	27	36	75	GPCGR		300
	ROXBURY TOWNSHIP WATER DEPT.	2513067	5 Inactive	405246	744100		3.9	27	36	100	GPCGR		50
	ROXBURY TOWNSHIP WATER DEPT.	4500289	6 Inactive	405246	744100		3.9	27	36	90	GPCGR		50
	ROXBURY TOWNSHIP WATER DEPT.	2524169	9 Inactive	405300	744130		3.4	27	36	365	GPCGR		80
	ROXBURY TOWNSHIP WATER DEPT.	2526025	10	405225	743955		4.9	27	36	170	GPCGR		65
	ROXBURY TOWNSHIP WATER DEPT.	2524717	11	405225	743955		4.9	27	36	550	GPCGR		17
	ROXBURY TOWNSHIP WATER DEPT.	2529414	12	405450	744029	T	3.0	27	36	82	GDSD		300
5338	ARLINGTON HILLS WATER CO., INC.	2533916	1A	405419	743833	F	4.8	27	26	99	GGTM		300
	ARLINGTON HILLS WATER CO., INC.	2536115	2	405421	743833	F	4.8	27	26	91	GGTM		300
5353	ARD MT. OLIVE ASSOCIATES, L.P.	2527269	WELL NO. 1	405215	744328	T	3.6	27	27	350	GPC		100
	ARD MT. OLIVE ASSOCIATES, L.P.	2527268	WELL NO. 2	405215	744378	T	3.6	27	27	400	GPC		100
MR0010	FARM SOLD	POND	1	405135	743930	F	5.8	27	36	8	GDGP		

Number of Observations: 94

## DESCRIPTION OF WATER WITHDRAWAL POINTS

The Water Withdrawal Points listing contains the following fields:

CAPACITY: the pump capacity in gallons per minute  
COUNTY: county the withdrawal point is in  
DEPTH: depth of the well or pond  
DISTANCE: distance in miles from center of circle  
GEO1: the ground or surface water source  
GEO2: a secondary source of the water  
LAT: latitude of the withdrawal point  
LLACC: accuracy of the latitude and longitude estimates  
LOCID: the local identification of the withdrawal point,  
or a continuation of the SOURCEID field for surface water  
LON: longitude of the withdrawal point  
MUN: the municipality the withdrawal point is in  
NAME: name of the permit, certificate, or registration holder  
NUMBER: Water Allocation permit, Agricultural Certification, or  
Registration number  
SOURCEID: the well permit number or other identifier for  
the water withdrawal

The listing that you have requested includes most wells and surface intakes that are in the Water Allocation Permits, and representative sources from most of the Agricultural Certificates. Recognizing the fact that the list will contain errors and omissions, it is advisable to use this resource as a guide and to verify all data. We try to maintain an accurate database; however, we can not yet guarantee reliability. If you spot any errors we would be very grateful to hear about them. Please call or write to us in reference to the "Radius Program" at:

NJDEP  
Division of Water Resources  
Bureau of Water Allocation  
CN-029  
Trenton, NJ 08625

(609) 292-2957

Thank you.

Please see the attached sheets for definitions of the codes used in the Water Withdrawal Points listing.

# CODES USED IN THE WATER WITHDRAWAL POINTS LISTING

This packet contains information on the database codes that the Bureau of Water Allocation uses in the Water Withdrawal Points Listing.

COUNTY:	01 - Atlantic	15 - Gloucester	29 - Ocean
	03 - Bergen	17 - Hudson	31 - Passaic
	05 - Burlington	19 - Hunterdon	33 - Salem
	07 - Camden	21 - Mercer	35 - Somerset
	09 - Cape May	23 - Middlesex	37 - Sussex
	11 - Cumberland	25 - Monmouth	39 - Union
	13 - Essex	27 - Morris	41 - Warren

## GEO: RECENT

Surficial Deposits

GRS

## PLEISTOCENE

Glacial Undifferentiated

GQGU

Stratified Drift

GQSD

Terminal Moraine

GQTM

Bridgeton

GQBS

Cape May

GQCM

Holly Beach Mbr.

GQCHB

Estuarine Sand

GQES

Pennsauken

GQPS

## TERTIARY

Beacon Hill

GTBH

Cohansey

GTCH

Cohansey & Kirkwood

GTCK

Kirkwood

GTKW

Upper

GTKWU

Rio Grande

GTKRG

Lower

GTKWL

Piney Point Mbr.

GTKPP

Shark River Marl

GTSR

Manasquan Marl

GTMO

Vincentown Sand

GTVT

Hornerstown Marl

GTHT

## CRETACEOUS

Red Bank

GKRB

Navesink

GKNS

Mount Laurel

GKML

Wenonah

GKWE

Mount Laurel & Wenonah

GKMW

Marshalltown

GKMT

Englishtown

GKET

Woodbury

GKWB

Merchantville

GKMV

Magothy

GKM

Old Bridge	GKROB
Raritan	GKR
Sayreville Sand	GKRSS
Farrington	GKRF
Raritan/Magothy	GKMR
Potomac	GKP
TRIASSIC	
Brunswick Formation	GTRB
Lockatong Formation	GTRL
Stockton Formation	GTRS
Basalt	GTRBS
Diabase	GTRDB
Conglomerate	GTRCG
DEVONIAN	
Undifferentiated	GD
SILURIAN	
Bossardville Limestone	GSBD
Decker Formation	GSDK
Longwood Shale	GSLs
Poxono Island Fm	GSPI
Greenpond Conglomerate	GSGP
High Falls	GSHF
Shawangunk Fm	GSSG
ORDOVICIAN	
Martinsburg Fm	GOMB
Jacksonburg Fm	GOJB
Kittatinny Group	GOK
Outleaunee Fm	GOKO
Harmonyvale Mbr	GOKOH
Beaver Run Mbr	GOKOB
Epler	GOKE
Rickenbach	GOKR
CAMBRO ORDOVICIAN	
Kittatinny Fm	GCOK
CAMBRIAN	
Hardyston Quartzite	GCH
Allentown Fm	GCKA
Upper Mbr	GCKU
Limeport Mbr	GCKLP
Leithsville Fm	GCKL
Walkill Mbr	GCKLW
Hamburg Mbr	GCKLH
Califon Mbr	GCKLC
PRECAMBRIAN	
Granite	GPCGR
Gneiss	GPCGN
Undifferentiated	GPC



# Franklin Lms

GPCFL

## DELAWARE RIVER BASIN

Unknown or Non-Specific

Alloways Creek

Alexsocken Creek

Assiscunk Creek

Assunpink Creek

Big Timber Creek

Blacks Creek

Cooper's Creek

Crafts Creek

Crosswicks Creek

Delaware River

Flat Brook

Hakihokake Creek

Harihokake Creek

Jacob's Creek

Lockatong Creek

Lopatcong Creek

Mantua Creek

Musconetcong River

Nichisakawick Creek

Old Man's Creek

Paulins Kill

Pennsauken Creek

Pequest River

Pohatcong Creek

Raccoon Creek

Rancocas Creek

Salem River

Wickecheoke Creek

SD

SDALL

SDALE

SDASC

SDASP

SDBIG

SDbLA

SDCOO

SDCRA

SDCRO

SDDel

SDFLA

SDHAK

SDHAR

SDJAC

SDLOC

SDLOP

SDMNT

SDMUS

SDNIC

SDOLD

SDPAU

SDPEN

SDPST

SDPOH

SDRAC

SDRAN

SDSAL

SDWIC

## RARITAN RIVER BASIN

Unknown or Non-Specific

Lawrence Brook

Lower Raritan

Millstone River

North Branch Raritan

South Branch Raritan

South River

SR

SRLAW

SRLOW

SRMIL

SRNBR

SRSBR

SRSRV

## PASSAIC RIVER BASIN

Unknown or Non-Specific

Canoe Brook

Lower Mid-Passaic River

Lower Passaic

Passaic River

Peckman River

Pequannock River

Pompton River

Ramapo River

Rockaway River

Saddle River

SP

SPCAN

SPLMP

SPLOW

SPPAS

SPPEC

SPPNK

SPPOM

SPRAM

SPROC

SPSAD

Upper Mid-Passaic River	SPUMP
Upper Passaic River	SPUPP
Wanaque River	SPWAN
Whippany River	SPWHI

#### ATLANTIC COASTAL BASIN

Unknown or Non-Specific	SC
Atlantic County Coastal	SCATL
Cape May County Coastal	SCCAP
Cedar Creek	SCCED
Great Egg Harbor River	SCGRE
Manasquan River	SCMSQ
Metedeconk River	SCMET
Monmouth County Coastal	SCMON
Mullica River	SCMUL
Navesink River	SCNAV
Ocean County Coastal	SCOCE
Raritan Bay	SCRAR
Shark River	SCSHA
Shrewsbury River	SCSHR
Toms River	SCTOM
Tuckahoe River	SCTUC

#### HUDSON RIVER BASIN

Unknown or Non-Specific	SH
Hudson River	SHHUD
Papakating Creek	SHPOP
Pochuck Creek	SHPOC
Wallkill River	SHWAL

#### HACKENSACK RIVER BASIN

Unknown or Non-Specific	SK
Hackensack River	SKHAC

#### RAHWAY RIVER BASIN

Unknown or Non-Specific	SY
Rahway River	SYRAH

#### ELIZABETH RIVER BASIN

Unknown or Non-Specific	SE
Elizabeth River	SEELI

#### DELAWARE BAY BASIN

Unknown or Non-Specific	SB
Cohansey River	SBCOH
Maurice River	SBMAU
Stow Creek	SBSTO

#### LLACC:


S	- accurate to +- 1 second
F	- accurate to +- 5 seconds
T	- accurate to +- 10 seconds
M	- accurate to +- 1 minute
U	- accuracy unknown




# WETLAND LEGEND

U - Primarily represents upland areas, but may include unclassified wetlands less than 1 acre in area, non photo-identifiable areas and/or unintentional omissions.


## ECOLOGICAL SYSTEM



## ECOLOGICAL SYSTEM



## ECOLOGICAL SYSTEM



**SYSTEM**  
**Ecological**  
**Subsystem**

**CLASS**  
**Subclass**

1 - Limnetic				2 - Littoral							
RB - ROCK BOTTOM	UB - UNCONSOLIDATED BOTTOM	AD - AQUATIC BED	OW - OPEN WATER Unknown Bottom	RB - ROCK BOTTOM	UB - UNCONSOLIDATED BOTTOM	AD - AQUATIC BED	FL - FLAT ROCK	RS - ROCKY SHORE	DB - BEACH BAR	EM - EMERGENT	OP - OPEN WATER Unknown Bottom
1. Bedrock 2. Boulder	1. Cobble / Gravel 2. Sand 3. Mud 4. Organic	1. Submergent Algal 2. Submergent Vascular 3. Submergent Moss 4. Floating leaved 5. Floating 6. Unknown Submergent 7. Unknown Surface		1. Bedrock 2. Boulder	1. Cobble/Gravel 2. Sand 3. Mud 4. Organic	1. Submergent Algal 2. Submergent Vascular 3. Submergent Moss 4. Floating leaved 5. Floating 6. Unknown Submergent 7. Unknown Surface	1. Cobble/Gravel 2. Sand 3. Mud 4. Organic 5. Vegetated Pioneer 6. Vegetated Non-pioneer	1. Bedrock 2. Boulder	1. Cobble/Gravel 2. Sand	2. Nonpersistent 3. Narrow leaved Nonpersistent 4. Broad leaved Nonpersistent	

**R - RIVERINE**

**Ecological**  
**Subsystem**

**CLASS**  
**Subclass**

1. Tidal		2 - Lower Perennial		3 - Upper Perennial		4 - Intermittent		5 - Unknown Perennial	
EM - EMERGENT(*)	RB - ROCK BOTTOM	UB - UNCONSOLIDATED BOTTOM	AD - AQUATIC BED	FL - FLAT	SH - STREAMBED	RS - ROCKY SHORE	DB - BEACH/DAR	OW - OPEN WATER Unknown Bottom	
1. Nonpersistent 2. Narrow-leaved Nonpersistent 3. Broad-leaved Nonpersistent	1. Bedrock 2. Boulder	1. Cobble/Gravel 2. Sand 3. Mud 4. Organic	1. Submergent Algal 2. Submergent Vascular 3. Submergent Moss 4. Floating-Leaved 5. Floating 6. Unknown Submergent 7. Unknown Surface	1. Cobble / Gravel 2. Sand 3. Mud 4. Organic 5. Vegetated Pioneer 6. Vegetated Non-pioneer	1. Cobble/Gravel 2. Sand 3. Mud 4. Organic	1. Bedrock 2. Boulder	1. Cobble/Gravel 2. Sand		

(\*) EM - EMERGENTS are only found in the Riverine Tidal and Riverine Lower Perennial Ecological Subsystem. All other classes are found in all Riverine Ecological Subsystems


## MODIFYING TERMS

In order to more adequately describe wetland and aquatic habitats one or more of the water regime, water chemistry, soil, or special modifiers may be applied at the class or lower level in the hierarchy. The farmed modifier may also be applied to the ecological system.

WATER REGIME(1)				WATER CHEMISTRY			SOIL	SPECIAL MODIFIERS	
Non-Tidal		Tidal		Coastal Salinity	Inland Salinity	pH Modifiers for all Fresh Water	g Organic n Mineral	b Beaver d Partially Drained/Ditched f Farmed	b Diked/Impounded r Artificial s Spoil x Excavated
A Temporary B Saturated C Seasonal D Seasonal Well-drained E Seasonal Saturated F Semipermanent O Intermittently Exposed	H Permanent J Intermittently Flooded K Artificial Z Intermittently Exposed/Permanent W Intermittently Flooded/Temporary Y Saturated/Semipermanent/Seasonal U Unknown	K Artificial L Subtidal M Irregularly Exposed N Regular P Irregular	R Seasonal Tidal S Temporary Tidal T Semipermanent Tidal V Permanent Tidal U Unknown	1 Hypersaline 2 Eubaline 3 Microhaline (Brackish) 4 Polyhaline 5 Mesohaline 6 Oligohaline 0 Fresh	7 Hypersaline 8 Eubaline 9 Microhaline 0 Fresh	a Acid c Circumneutral l Alkaline			
								MOOL Lawns, Stormwater Management Areas (areas not normally inundated) MOOR Right-of-Ways (weeds maintained by mowing) MODAG Agricultural Lands, Turf Farms (both row crop and turf cultivation) MOOD Disturbed Areas (succession/regeneration disturbed. Nature of activity not readily apparent)	

(1) Information on the water regime modifiers found on this legend, but not found in the classification system, may be obtained from the above listed source.

## KEY TO MAP



\*\*Referenced to the National Geodetic Vertical Datum of 1929

### \*EXPLANATION OF ZONE DESIGNATIONS

ZONE	EXPLANATION
A	Areas of 100-year flood; base flood elevations and flood hazard factors not determined.
A0	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; average depths of inundation are shown, but no flood hazard factors are determined.
AH	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; base flood elevations are shown, but no flood hazard factors are determined.
A1-A30	Areas of 100-year flood; base flood elevations and flood hazard factors determined.
A99	Areas of 100-year flood to be protected by flood protection system under construction; base flood elevations and flood hazard factors not determined.
B	Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood. (Medium shading)
C	Areas of minimal flooding. (No shading)
D	Areas of undetermined, but possible, flood hazards.
V	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors not determined.
V1-V30	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors determined.

### NOTES TO USER

Certain areas not in the special flood hazard areas (zones A and V) may be protected by flood control structures.

This map is for flood insurance purposes only; it does not necessarily show all areas subject to flooding in the community or all planimetric features outside special flood hazard areas.

For adjoining map panels, see separately printed Index To Map Panels.

INITIAL IDENTIFICATION:

FEBRUARY 28, 1975

FLOOD HAZARD BOUNDARY MAP REVISIONS:

NONE

## NATIONAL FLOOD INSURANCE PROGRAM

# FIRM FLOOD INSURANCE RATE MAP

TOWNSHIP OF  
BYRAM,  
NEW JERSEY.  
SUSSEX COUNTY

PANEL 5 OF 20


(SEE MAP INDEX FOR PANELS NOT PRINTED)

COMMUNITY-PANEL NUMBER  
340557 0005 A

EFFECTIVE DATE:  
JANUARY 5, 1984



Federal Emergency Management Agency




PHOTOGRAPHS



CAT SWAMP HILL DUMP SITE  
AKA: SHAWS DUMP  
WEST OF ROUTE 206  
BYRAM TOWNSHIP, SUSSEX COUNTY, NEW JERSEY


PHOTOGRAPH LOG


1. AREA #1, LOCATION OF SAMPLE S-1
2. AREA #2, LOCATION OF SAMPLES S-3 & S-4
- 3 - 6. AREA #3, TRENCHES #1 THROUGH #4
- 7 - 8. DRUM CARCASSES AND DEBRIS IN THE VICINITY OF S-18 & S-19
- 9 - 14. PHOTOGRAPHS OF VARIOUS TYPES OF SOLID WASTES AND DEBRIS  
LANDFILLS THROUGHOUT THE SITE.
15. WETLAND AREA EAST OF THE DUMP SITE.












ATTACHMENT A

# TOWNSHIP OF BYRAM

NEW JERSEY

MAILING ADDRESS:  
10, MANSFIELD DRIVE  
STANHOPE, N.J. 07874  
Phone: 201-347-2500



SEP 24 1993

IN ANSWERING  
PLEASE REPLY TO

{ NJDEPE case #

{ 93-9-15-1015-15

September 22, 1993

Gregory Marshall, Director  
Division of Parks and Forestry  
NJ DEPE  
CN 404  
501 East State Street, Floor 4  
Trenton, NJ 08625-0404

Dear Mr. Marshall:

The Byram Township Council and the Byram Township Environmental Commission are seeking NJDEPE assistance in investigating a dumpsite that operated for about two decades, closing in the mid 1960's, and that reportedly received hazardous industrial waste as well as household waste.

This approximately 10-acre site was located west of Route 206 on Cat Swamp Hill on parcels now owned by a Canadian developer and by your Parks and Forestry Division of the NJDEPE. The Parks and Forestry parcel, which was taken by eminent domain in 1982 to be added to Allamuchy Mountain State Park, is Block 366, Lot 3, 225.46 acres.

As the enclosed maps show, the southernmost fringe of the dump (perhaps 3.5 to 4 acres) lies on this NJDEPE parcel. Based on a 1973 aerial photo and tax maps, several long trenches that were dug to receive both household and industrial waste are partly located on the NJDEPE parcel, as are numerous large bales of insulating material that may contain asbestos. These bales are scattered over the surface of the entire site and were reportedly also dumped in the trenches and then covered with household refuse and soil.

Our information about the dump comes from several sources. In addition to the 1973 aerial photo, there are photos available from 1959 and 1963 showing the gradual enlargement of the site from about 5-6 acres in 1959 to the full 10 acres in 1963. All three aerial photos are available at Robinson Aerial Survey in Newton. The township had Robinson make two ten-fold enlargements of the 1973 photo; one is on file with the Environmental Commission; the other has been sent to the NJDEPE Division of Parks and Forestry. The two earlier photos are less fine but could be enlarged perhaps five-fold.

The 1973 enlargement clearly shows many of the trenches and bales, as well as old automobiles and also bull-dozer marks where waste was pushed in a southerly and easterly direction into the swamp that borders the site.

Another swamp lies to the north; and much of the area is underlain by glacial deposits, some of it sand and gravel and very susceptible to contamination. Several of Byram's small water companies to the northwest, northeast and south of the site have, in the past decade or two, shown contamination by volatile organics such as trichloroethane.

Members of the township Council and the Environmental Commission have walked the site at least three times in the past year, taking along a hunter who belonged to a hunting club that used the area in the 1970's and a former truck driver who brought in insulating and furnace waste from the Mineral Wool company in Stanhope (now called the United States Mineral Products Company). The Commission has also interviewed a bull-dozer driver who worked at the dump part-time for two years in 1958 and 1959.

Many other residents are familiar with the site and used it themselves for household or construction waste. When the site was recently being considered for townhouse and industrial-commercial development, these people came to township meetings to describe the industrial dumping.

Most of these people believed the site posed no problems as long as it wasn't disturbed, but the Council and the Environmental Commission are worried about possible groundwater contamination as well as surface disturbance of any asbestos.

These residents all tell similar stories--regular dumping from the Mineral Wool company; tanker trucks pouring liquid industrial waste into the trenches, sometimes lined up along Route 206 waiting to enter the site. The bull-dozer driver said most of the refuse was household waste interlayed with Mineral Wool waste (insulating materials, fireproofing materials, and furnace waste resulting from burning slag to make rock wool). But during his two-year part-time job, he also saw "an awful lot of drums" dumped there, including at least two or three flatbed trucks stacked with 50-gallon drums which were dumped into the trenches and other excavations. This man said the trenches were dug to get cover soil to put over the garbage. Because this is an area of thin soils, the trenches were dug all the way down to bedrock (eliminating even the modest benefits of soil to confine any liquid industrial wastes).

We know the name of the man who owned the dump and are trying to find his current address and phone number in Florida, where he is said to reside.

The hunter who walked the site with us tells also of sinking into an area where the dump meets the swamp and pulling his leg out to find it "covered with silver".




The Environmental Commission, the Council and Planning Board are on good terms with the Canadian developer, who is not obstructing our attempts to determine what may be in this dump and whether any groundwater contamination has occurred. However, he is anxious to proceed with development. The Environmental Commission and Council would like to have the site investigated and groundwater quality thoroughly monitored before any specific plans are discussed before the Planning Board.


Copies of this letter and the maps have also been sent to NJDEPE Acting Commissioner Jeanne Fox, Assistant Commissioner for Natural and Historic Resources James Hall, Assistant Commissioner of Site Remediation Lance Miller, Director of Publicly Funded Site Remediation Anthony Farro, Chief Joseph Mikulka at the Northern Bureau of Regional Enforcement in Parsippany, Sussex County Planning Director Fred Suljic, Parks Superintendent Bart Wallin and to all pertinent Byram Township officials and the Canadian developer, Larry Wainberg.

We look forward to your reply.

Yours truly,



Margaret McGarrity, Chairwoman  
Byram Township Environmental Commission



Ronald F. Gatti, Manager  
Township of Byram

STATE OF NEW JERSEY  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF RESPONSIBLE PARTY SITE REMEDIATION  
DISCHARGE RESPONSE ELEMENT  
BUREAU OF FIELD OPERATIONS - NORTHERN FIELD OFFICE  
1259 RTE. 46, BLDG. 2, PARSIPPANY, NJ 07054  
TELEPHONE (201) 299-7570 TELEFAX (201) 299-7575

M E M O R A N D U M

TO: Bob Van Fossen, Acting Assistant Director DATE: 10/28/93

FROM: John Zisa, NFO

THROUGH: Yacoub E. Yacoub, Section Chief

THROUGH: Vince Krisak, Acting Bureau Chief

SUBJECT: Cat Swamp Hill Dumpsite - Route 206  
Byram Township, Sussex County  
DRPSR Case No. 93-9-15-1015-25N

On September 22, 1993 a letter (see attached) was sent to the Division of Parks and Forestry outlining potential environmental concerns discovered in Byram Township. The letter was sent to a number of different bureaus within the Department. An official incident report to the "hotline" was made by the Byram Township Environmental Commission. That incident was assigned to NFO.

An initial site investigation was conducted on 10/27/93, in conjunction with Margaret McGarrity of the Byram Environmental Commission and Councilman Charles Vitale. The site was found to be an abandoned dump site. Several exposed and partially exposed 55 gallon drums were noted. It is unknown if these drums contained anything. Other debris was observed at the site. It is alleged that large quantities of asbestos have been dumped at the site. This could not be verified. Potential environmental and health related concerns were clearly evident at the site.

Approximately 2/3 of the site is currently owned by a Canadian Developer, who plans to construct townhouses at the site. The remainder of the property is State owned parkland (Allamuchy State Park). Dumping was ceased at the site approximately 20 years ago. A viable RP may no longer be available. An MOA was, however, offered to the Canadian Developer. This was done by Site Assessment, who also received a copy of the report. A response to the MOA has not yet been received.

The State owned portion of the dump site must be addressed as well, and could not be covered under the developer MOA. It is recommended that DRPSR management discuss this matter with Parks and Forestry. At a minimum this is a solid waste issue and possibly involves hazardous materials.

Due to a lack of information regarding the site, an accurate RPS score may not be possible at this time. Local residents are extremely concerned that this site may be contributing to groundwater contamination that has been identified in several nearby municipal wells. Should the developer fail to respond favorably to the MOA, the NFO recommends that this case be transferred through Site Assessment to DPFSR so that a preliminary assessment can be performed by Ken Kloo's group. The information learned will aid in properly scoring the site, and will allow for public funds to be utilized in the event they are needed. Due to public and local governmental involvement in this issue, the referral/assessment process should be expedited.

New Jersey Department of Environmental Protection  
COMMUNICATIONS CENTER NOTIFICATION REPORT

BFO-N

Received: 9/15/93

Operator: JIMH

TD Log #

15729

Case # 93-9-15-1015-25

Reported By

MARGRET MCCAFFERTY

Street Address

Notification Type: Citizen

Affiliation  
ENVIRONMENTAL COMMI  
MunicipalityPhone  
201-347-2358  
State

Incident Location: Other

Site BLOCK 366 LOT 3

Street Address

WEST OF RT 205

Location Type Rural

Municipality  
BYRAM TWP

Phone

County  
SUSSEXState  
NJ

Incident Date

Time

Substance Released SOIL CONTAMINATED W/ UNKNOWN MATERIAL

Amount Released (

) UNK

ID: Known

State Solid CAS#

Release Is Terminated

Additional Substances

Substance Contained? U

COMU CODE: 1904

Hazardous Material? Y

TCPA? U

A310 Letter? Y

REF CODE: 001

Incident Description HISTORICAL SPILLS

Injuries? N

Public Evac? N

Facility Evac? N

Public Exposure? U

Police On Scene? N

Firemen On Scene? N

DEP Requested? Y

Wind Sp/Dir

Contamination Of Land/Water

Receiving Water UNK

Status At Scene PROPERTY CONTAMINATED IN 60'S PART OF LAND OWNED BY  
DEVELOPER LARRY WAINBERG, AND PART BY DEPE

Responsible Party Unknown

Party

Contact

Street Address

Municipality

Phone

Title

County

State

## OFFICIALS NOTIFIED

NAME

TITLE

PHONE

DATE TIME

NJSP: NJSP/OEM

FAXED

9/15

MUNIC: BYRAM TWP

SECY TUNA

201-347-4008 9/15 1027

OTHER:

Name

Affiliation

Method

Date

Time

T/M

1.

DRPSR

ERI

Faxed, Mailed

9/15

B

2.

3.

COMMENTS:

CAT SWAMP ROAD

U040A100

ATTACHMENT

A5

ATTACHMENT B


R. 12

38  
J

SOIL SURVEY OF


# Sussex County, New Jersey

---



United States Department of Agriculture  
Soil Conservation Service

in cooperation with  
New Jersey Agricultural Experiment Station  
and Cook College  
Rutgers University



SUSSEX COUNTY, NEW JERSEY NO. 44

ATTACHMENT B2

Representative profile of Riverhead sandy loam, 3 to 8 percent slopes, at the intersection of Route 206 and Lake Lackawanna Road, in a field:

Ap—0 to 7 inches, very dark grayish-brown (10YR 3/2) sandy loam; weak, fine, granular structure; very friable; 10 percent fine to medium gravel; strongly acid; clear, wavy boundary.

B—7 to 30 inches, strong-brown (7.5YR 5/6) sandy loam; weak, medium, subangular blocky structure; friable; 10 percent gravel; strongly acid; gradual, irregular boundary.

C—30 to 60 inches, light yellowish-brown (2.5Y 6/4), stratified loamy sand; single grain; loose; 10 percent gravel; strongly acid.

The solum is 22 to 36 inches thick over sand containing some gravel. Depth to bedrock is more than 6 feet. The gravel content ranges from 0 to 15 percent in the solum and from 5 to 35 percent in the C horizon. Unless limed, these soils are strongly acid.

The Ap horizon is 10YR in hue, 3 or 4 in value, and 2 in chroma. The B horizon is 7.5YR to 10YR in hue, 4 or 5 in value, and 4 to 6 in chroma. The B horizon is dominantly sandy loam but ranges to loamy sand in the lower part of some profiles. The C horizon is 10YR to 2.5Y in hue, 5 or 6 in value, and 4 to 6 in chroma. The C horizon is stratified loamy sand, sand, or gravelly sand.

Riverhead soils are associated with Pompton, Otisville, Preakness, and Rockaway soils. They do not have the mottles that are common in Pompton soils and the grayish-brown B horizon that is common in Preakness soils. They contain more clay and less gravel and sand than Otisville soils. They do not have the fragipan that is common in Rockaway soils.

**Riverhead sandy loam, 3 to 8 percent slopes (RhB).**—The profile of this soil is the one described as representative of the series. Included in mapping are small areas where the surface layer is loam, many areas where the content of gravel ranges to 25 percent, and areas of nearly level soils.

This soil is used for alfalfa, corn, vegetables, and fruit. Capability unit IIe-7; woodland group 301.

**Riverhead sandy loam, 8 to 25 percent slopes (RhC).**—The profile of this soil is similar to the one described as representative of the series, but the depth to the substratum is 20 to 24 inches. Included in mapping are areas of Otisville gravelly loamy sand and areas where the content of gravel ranges to 25 percent.

This soil is used for hay, silage crops, and fruit. Runoff is medium or rapid. The hazard of erosion is moderately severe. Erosion control is needed in cultivated areas. Capability unit IVE-15; woodland group 3r1.

## Rockaway Series

The Rockaway series consists of deep, well-drained, gently sloping to very steep soils that have a fragipan in the lower part of the subsoil. These soils formed in coarse-textured or moderately coarse textured glacial till. They are on uplands.

In a representative profile the plow layer is dark grayish-brown gravelly loam 7 inches thick. The upper 3 inches of the subsoil is yellowish-brown, strong-brown, dark-brown gravelly loam. The lower part is a fragi- of very firm, dark-brown and yellowish-brown gravelly sandy loam 14 inches thick. The substratum to depth of 65 inches is very firm, light yellowish-brown gravelly sandy loam.

Available water capacity is moderate above the very firm, brittle fragipan. Permeability is moderately rapid

above the fragipan and slow in the pan. Natural fertility is moderate. Root penetration is restricted in the fragipan.

Most of the acreage is wooded or idle. The less sloping nonstony soils are suited to corn, fruit trees, hay, and pasture.

Representative profile of Rockaway gravelly loam, 3 to 8 percent slopes, in Sparta Township, 1/4 mile south of Saint Mary's Episcopal Church, 100 feet west of Conestoga Trail, in a hayfield:

Ap—0 to 7 inches, dark grayish-brown (10YR 4/2) gravelly loam; weak, medium, granular structure; friable; many fine and medium roots; many medium and coarse pores; 20 percent gravel; medium acid; clear, smooth boundary.

B1—7 to 11 inches, yellowish-brown (10YR 5/6) gravelly loam; weak, medium, subangular blocky structure; friable; many fine and medium roots; many medium pores; 20 percent gravel; strongly acid; gradual, wavy boundary.

B21t—11 to 18 inches, strong-brown (7.5YR 5/6) gravelly loam; moderate, medium, subangular blocky structure; friable, slightly sticky when wet; weak clay bridging and thin patchy clay films on ped faces; many roots; many fine and medium pores; 15 percent gravel; strongly acid; gradual, wavy boundary.

B22t—18 to 30 inches, dark-brown (7.5YR 4/4) gravelly loam; moderate, coarse, subangular blocky structure; moderately firm; bridging and pore filling common; thin discontinuous clay films on many ped faces and on pebbles; few large and many fibrous roots; few large pores; 20 percent gravel; strongly acid; gradual, wavy boundary.

Bx—30 to 44 inches, dark-brown (7.5YR 4/4) and yellowish-brown (10YR 5/4) gravelly sandy loam; massive; very firm and brittle; most pores filled; patchy thin to thick clay films on ped faces; few roots; 25 percent gravel and cobblestones; strongly acid; diffuse, irregular boundary.

Cx—44 to 65 inches, light yellowish-brown (10YR 6/4) gravelly sandy loam; few, coarse, faint, light brownish-gray (2.5Y 6/2) and yellowish-brown (10YR 5/6) mottles; massive; very firm and brittle; 35 percent gravel and cobblestones; strongly acid.

The solum ranges from 30 to 50 inches in thickness. Depth to the fragipan ranges from 20 to 30 inches. Depth to gneissic bedrock is generally 48 inches or more and in places ranges to 10 feet or more. Unless limed, these soils are dominantly strongly acid. The content of coarse fragments ranges from 10 to 35 percent in the solum and to as much as 50 percent in the C horizon.

The A1 horizon, where present, has a hue of 10YR or 7.5YR, a value of 3, and a chroma of 2 or 3. It ranges from 1 to 3 inches in thickness. The Ap horizon has a hue of 10YR or 7.5YR, a value of 4, and a chroma of 2 or 3. The B1 and B2t horizons have a hue of 10YR or 7.5YR, a value of 4 or 5, and a chroma of 4 to 6. These horizons range from gravelly loam to gravelly sandy loam. The Bx horizon matrix has a hue of 7.5YR or 10YR, a value of 4 or 5, and a chroma of 4 to 6. It is sandy loam or loam and in places is gravelly. The Bx and Cx horizons are firm to very firm and brittle.

Rockaway soils are associated with Hibernia, Whitman, and Riverhead soils. They do not have the grayish mottles in the upper part of the B horizon that are common in Hibernia soils. They do not have the gray colors that are common in Whitman soils. They have a fragipan and Riverhead soils do not. They do not have the loose, stratified gravelly and sandy C horizon that Riverhead soils have.

**Rockaway gravelly loam, 3 to 8 percent slopes (RoB).**—The profile of this soil is the one described as representative of the series. Included in mapping are two similar soils. One of these soils has a medium acid subsoil, and the other lacks a fragipan. Both are inextensive and are

ar to this Rockaway soil in limitations and management. Also included are areas of Hibernia soils and of Rockaway very stony loam. The Hibernia soils occur at the base of steeper slopes and make up 15 percent of the area.

This soil is used for row crops, hay, pasture, and woodland. Many areas are now idle and are reverting to woodland or are used for community development purposes. Hazard of erosion is moderate. Erosion control is needed in cultivated areas. Capability unit IIe-3; woodland group 3o1.

**Rockaway gravelly loam, 8 to 15 percent slopes**  
—Included with this soil in mapping in some areas two similar soils. One of these soils has a medium subsoil, and the other does not have a fragipan. Both are inextensive and are similar to this Rockaway soil in limitations and management. Also included are spots of Rockaway very stony loam. Small seep areas occur where slope changes.

This soil is used for row crops, hay, pasture, and woodland. Many areas are reverting to woodland. Runoff is medium. The hazard of erosion is moderate. Erosion control is needed in cultivated areas. Capability unit IIe-3; woodland group 3o1.

**Rockaway gravelly loam, 15 to 25 percent slopes**  
—The profile of this soil is similar to the one designated as representative of the series, but the depth to fragipan is slightly less. Included in mapping are areas of Rockaway very stony loam and Rock outcrop. Also included in some areas are two similar soils; one has a medium acid subsoil, and the other does not have a fragipan. Both are inextensive and are similar to Rockaway soil in limitations and management. Conspicuous pockets and places where the slope changes tend to be seepy.

This soil is used for hay, pasture, woodland, and infrequent row crops. Many areas are idle. Runoff is rapid. Hazard of erosion is severe in cultivated areas. Erosion control is needed. Capability unit IVe-3; woodland group 3r1.

**Rockaway very stony loam, 5 to 25 percent slopes**  
—The profile of this soil is similar to the one designated as representative of the series, but the content of stones, 5 to 30 feet apart, is about 3 percent in the top layer and subsoil. Included in mapping are small seep pockets that collect water and areas of Rockaway loam. Also included in some areas are two similar soils; one has a medium acid subsoil, and the other does not have a fragipan. Both are inextensive and are similar to this Rockaway soil in limitations and management. This soil is used for woodland and pasture and as equal home sites. In the less sloping areas, the stone content is the primary limitation for intensive use. Capability unit VIe-19; woodland group 3r1.

**Rockaway very stony loam, 25 to 40 percent slopes**  
The profile of this soil is similar to the one designated as representative of the series, but it contains 5 to 30 feet apart, and about 3 percent of the surface area is covered with stones. Included in mapping are two similar soils; one has a medium acid subsoil, and the other does not have a fragipan. Both are inextensive and are similar to this Rockaway soil in limitations

and management. Small areas of Rock outcrop are also included.

This soil is used for woodland. Steep slopes and the high stone content severely limit the use of this soil for most other uses. Capability unit VIIe-21; woodland group 3r1.

**Rockaway-Rock outcrop association, sloping and moderately steep (RrD).**—This association is 25 to 40 percent bedrock outcrop or soil material less than 10 inches thick over bedrock and 30 to 45 percent stony to extremely stony Rockaway soils. Slopes range from 8 to 25 percent. Included in mapping are small areas of similar soils where bedrock is at a depth of 10 to 40 inches and elongated, narrow areas of gently sloping soils along the ridge crests. Also included in depressions and seep areas are spots of Whitman and Hibernia soils and muck.

Most of this association is wooded. Some areas are used for pasture. The Rock outcrop and shallow soils, the content of stones, and the steep slopes make this association unsuitable for cultivation. Capability unit VIIe-21; woodland group 3x1.

## Rock Outcrop

Rock outcrop is extensive in areas of steep Oquaga soils and very steep Nassau soils. Three mapping units that are predominantly Rock outcrop are described in the paragraphs that follow.

**Rock outcrop-Nassau association, very steep (RsF).**—This association is 30 to 60 percent Rock outcrop, rubble, or soil material less than 10 inches thick and 30 to 60 percent Nassau soils. Slopes range from 25 to 45 percent. In some areas, the Rock outcrop is a 6- to 12-inch ledge at the top of steep Nassau soils. In 10 percent of the areas, Rock outcrop forms almost vertical cliffs, many feet above the surface. The outcrops are separated only by very narrow areas.

This association is used for pasture, woodland, and watershed protection. Woodland and pasture production are severely restricted by Rock outcrop. Capability unit VIIIe-23; woodland group 5x1.

**Rock outcrop-Oquaga association, steep (RrE).**—This association is 40 to 60 percent bedrock outcrop, rock rubble, or soil material less than 10 inches thick and 20 to 35 percent extremely stony Oquaga soils. Slopes range from 25 to 35 percent. Bedrock is generally aligned in a northeast to southwest direction. The bedrock faces have cracks and crevices that are filled or partly filled with soil material, in which trees and shrubs grow. The Oquaga soils are on the lower slopes. Included in mapping are small areas of extremely stony Lackawanna and Swartswood soils in narrow areas, like steps, between bedrock outcrop. Also included are small areas of very steep or moderately steep Rock outcrop or soils.

Most of this association is in State forests, camps, recreation areas, and private woodland. Capability unit VIIIe-23; woodland group 3x1.

**Rock outcrop-Rockaway association, steep (RvE).**—This association is 70 to 90 percent bedrock outcrop, rock rubble, or soil material less than 10 inches thick and 5 to 20 percent extremely stony Rockaway soils. Slopes range from 25 to 35 percent. The Rockaway soils occupy



steep areas at the base of slopes and elongated ridge crests. The bedrock faces have cracks that are filled or partly filled with soil material, in which trees and shrubs grow. Included in mapping are areas of soils where the depth to bedrock is 10 to 40 inches and some wet spots.

This association is used for watershed protection and recreation, such as hiking and skiing, where the Rock outcrop is not too numerous. Woodland production is severely limited because stands are of low density and harvesting is difficult. Residential sites are seriously restricted because the abundant rock outcrop and the steep slopes make the area inaccessible and severely limit septic tank systems. Capability unit VIIIc-23; woodland group

## Sloan Series

The Sloan series consists of deep, level and nearly level, very poorly drained soils. These soils formed in alluvium washed from nearby uplands. They are on flood plains along the Wallkill, Paulins Kill, and Pequest Rivers and along some of the major streams in the county. These flood plains are subject to frequent, generally annual, flooding. In a representative profile the surface layer is black loam 10 inches thick. The subsoil is distinctly mottled gray silty clay loam 30 inches thick. The substratum to a depth of 60 inches is mottled, gray gravelly sandy

loam. Available water capacity is high. Permeability is moderate. Natural fertility is high. Typically, the water table is at or near the surface most of the year.

Most of the acreage is wooded. Most of the cleared acreage is pastured because flooding is a hazard. Corn is grown in the few areas that are not flooded every year. Improving drainage is difficult.

Representative profile of Sloan silt loam, in an area of Sloan and Wayland silt loams, 1/2 mile east of intersection of County Routes No. 94 and 15, at Lafayette, 100 feet south of bridge on State Route No. 94 over Paulins Kill, between old railroad bed and river:

11-0 to 10 inches, black (10YR 2/1) silt loam; moderate, medium, granular structure; friable; very sticky; slightly acid; abrupt, smooth boundary.

12-10 to 15 inches, very dark gray (10YR 3/1) silt loam; moderate, medium, subangular blocky structure; friable; sticky to very sticky; slightly acid; gradual, wavy boundary.

B2g-15 to 32 inches, gray (10YR 5/1) silty clay loam; common, fine, distinct, dark yellowish-brown (10YR 4/4) and yellowish-brown (10YR 5/6) mottles; moderate, medium, angular blocky structure; slightly firm; sticky and plastic; neutral; gradual, wavy boundary.

B3g-32 to 45 inches, gray (5Y 5/1) silty clay loam; many, distinct, dark yellowish-brown (10YR 4/4) and brownish-yellow (10YR 6/6) mottles; weak, medium, angular blocky structure; friable and sticky; neutral; gradual, wavy boundary.

11Cg-45 to 60 inches, gray (5Y 5/1) gravelly sandy loam; many, coarse, distinct, yellowish-brown (10YR 5/6) and brownish-yellow (10YR 6/6) mottles; massive; friable; mildly alkaline.

The solum is 30 inches or more thick. The alluvial deposits are more than 40 inches thick over stratified material. Small amounts of gravel are present in the lower part of some profiles. Reaction ranges from slightly acid in the A horizon to mildly alkaline in the C horizon.

The A1 horizon has a hue of 10YR, a value of 2 or 3, and a chroma of 1 or 2. The B horizon is dominantly gray; hue ranges from 5Y to 10YR, value is 4 or 5, and chroma is 1 or 2. It contains mottles that have a hue of 10YR, a value of 4 to 6, and a chroma of 4 or 6. The B horizon is dominantly silty clay loam, but is silt loam in places. It has weak to moderate, medium to coarse, subangular and angular blocky structure and moderate, medium, prismatic structure. The 11C horizon is stratified with varying textures. It is gleyed and mottled.

Sloan soils are associated with Wayland and Carlisle soils. In contrast with Wayland soils, they have a gray B horizon. They have a thicker A horizon than Wayland soils. They have more mineral and less organic material than Carlisle soils.

**Sloan and Wayland silt loams (Sm).**—Most areas are nearly equal parts of Sloan and Wayland soils. Some are dominantly one or the other. These soils are in low positions on the landscape. Included in mapping are small areas of loamy, sandy, gravelly, and other better drained soils. Also included are a few small isolated areas of Carlisle soils or other shallow organic soils.

Most of the acreage is used for summer pasture, woodland, and wetland wildlife. Wild grasses, sedges, and reeds and red maple, elm, ash, and white oak trees are most abundant in undrained areas. Outlets for improved drainage systems are generally not available. Capability unit VIw-46; woodland group 4w1.

## Swamp

Swamp (Sp) is low land where the water table is at the surface at least 10 months of the year. It is along sluggish streams and drainageways, in low areas that have poor surface outlets and a very high water table, and in areas around natural ponds. The surface layer is very dark gray or gray. The texture of the surface layer and content of organic matter are highly variable. The subsurface layer ranges from coarse to fine. The subsurface layer and underlying material contain a layer that is firm, but not necessarily brittle. Some areas are stony, but rarely very stony or extremely stony.


Swamp maple is a dominant natural species; some areas have many dead or dying trees. This mapping unit has potential for wetland wildlife habitat development. Most areas are natural water retention and storage areas. Capability unit VIIIw-37; woodland group 5w1.


## Swartswood Series

The Swartswood series consists of deep, well-drained, gently sloping to very steep soils that have a fragipan in the lower part of the subsoil. These soils formed in glacial till derived chiefly from gray and brown quartzite, conglomerate, and sandstone.

In a representative profile in a wooded area, a 2-inch layer of partly decomposed leaf litter and black or dark-brown organic material overlies the mineral soil. The next layer is 2 inches of grayish-brown very stony sandy loam. The upper 28 inches of the subsoil is yellowish-brown very stony gravelly loam or very stony gravelly sandy loam. The lower part to a depth of 60 inches is a fragipan of very firm, brittle, dark-brown gravelly sandy loam.

ATTACHMENT C





ATTACHMENT D

January 14, 1994

Margaret M. Garrity  
Chairwoman, Byram Township Environmental Comm.  
201-347-2358 (home)

Dave Dibblee  
Office of Site Assessment  
300 Horizon Center  
CN 407  
Trenton, N.J. 08625

Dear Dave Dibblee:

Here are general block + lot maps of the areas of Byram Township that lie within a one-mile radius of the Cat Swamp Hill dumpsite.

Specific well information (depth + screening) is filed here by block + lot or by the several small water companies that service certain residential areas.

If you indicate how many wells + where you need specific information, I could then return to you a list of block, lot, owner, address, depth of well, depth of casing (anything else?).

To my knowledge, there are four small water companies within the one-mile radius; the rest are private residential or commercial wells.

Also, as far as I know, most wells are less than 180-200' in depth; probably the majority are more in the 100-120' range. Our geology is mostly pre-Cambrian crystalline bedrock, although a few wells are drilled in a stratified-drift glacial deposit at the east end of Cranberry Lake which lies roughly along Route 206 + extends probably almost to the dumpsite.

Just to the north + southeast of the dumpsite

ATTACHMENT DL

are wetlands, which I've marked on the map.

I have a call into the Sussex County Health Department, who serve as Bryan's sanitarians, asking for any information they might have on wells + well depths here. I've also asked if they have a map showing all well locations.

Thanks for your help.

Margaret McGarity

November 10, 1993

McGarrity, Chairwoman  
Byram Township Environmental Commission  
10 Mansfield Drive  
Stanhope, N.J. 07874  
201-347-2358 (home phone)

John Zisa  
Bureau of Northern Enforcement  
N.J.D.E.P.E.  
1259 Route 46  
Parsippany, N.J. 07054

NOV 17 1993

Dear Mr. Zisa:

Here is some more information about the Cat Swamp Hill dumpsite in Byram, which we hope will help persuade the N.J.D.E.P.E. to include some basic groundwater testing within its initial investigation of this site.

The maps show well companies that have experienced some contamination in the past decade or so (I sent you a previous map like this, but that one contained one error--company #1 had no episodes of contamination) and also a map showing the nearest existing wells, which perhaps could be tested to help determine whether groundwater contamination exists.

I've circled the nearest wells immediately downslope of the dumpsite and here is a list of owners:

A. Jefferson Lakes Camp and Travel Corp., (block 366 lot 3.A, 38 Jefferson Lake Road), 46 Kenwood Road, Tenafly, N.J. 07670.

B. The Stone House (76rs Restaurant), (block 70, lot 9), c/o G. Mazzei, 54 Richmond Rd., Stanhope, N.J. 07874.

C. [REDACTED], (block 226 lot 10), 116 Route 206, Stanhope, N.J. 07874.

D. Mountainside Restaurant, (block 226 lot 3), 198 Route 206, Andover, N.J. 07821.

E. two homes (or one home, one business): [REDACTED] Ex. 6  
(block 366 lot 12), 1 Sutton Lane, P.O. Box 785, Andover, N.J. 07821.

[REDACTED] Ex. 6 (block 366 lot 13), 2 Sutton's Lane, Andover, N.J. 07821.

The redacted information consists of names of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

ATTACHMENT


D3



Thank you again for your help. If you need any other information from us, please call me. Let us know what kind of testing the department decides upon.

Yours truly,

*Margaret McGarrity*  
Margaret McGarrity



ATTACHMENT E

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES

5-4

COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE 8-2-89

## GENERAL INFORMATION

PURVEYOR/  
FACILITY: BROOKWOOD - MUSCONETCONG RIVER PROPERTY OWNERS ASSOCIATIONFILE LOCATION BYRAM TWP, SUSSEX COUNTY PW-ID # 1904001MAILING ADDRESS P.O. BOX 787, STANHOPE, NEW JERSEY 07874ADMIN. STEVE DOEBLER, SECY.REQUIRED T-1  
LICENSES W.

BUSINESS:

TELEPHONE # Admin.: 201-691-1431Licensed Operators: T-1WILLIAM HORTON  
W-4

## FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): THREE (3) WELLS:WELL #1 LOCATED ON RIVER ROAD USED AS STANDBY 0.100MGD CAP.WELL #2 LOCATED ON CHESTNUT STREET ALSO STANDBY 0.110MGD CAP.WELL #3 LOCATED ON RIVER ROAD, MAIN WELL Est Tot Eff Cap: 0.426MGD  
0.216MGD

TREATMENT: source, type, capacities(mgd):

WALLACE & TIERNAN HYPOCHLORINATION AT ALL WELLS.Est Tot Eff Cap: 0.426MGDFINISHED WATER STORAGE: descriptions, locations, capacities(mg): GROUND TANK AT WELL #20.100MG. ALSO A HYDRO-PNEUMATIC TANK WITH COMPRESSOR0.006MG.Est Tot Cap: 0.106MGEMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail:

AUXILIARY POWER: location, type, capabilities: DIESEL GENERATOR PORTABLE CAN1400KUP TO ALL WELLS, 50KW.ATTACHMENT E1



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max <u>SEPT 88 0.156 mgd</u> Min <u>MAY 88 0.081 mgd</u> Annual Average <u>0.118 mgd</u>	
BULK PURCHASES (provider, mgd) <u>NONE</u>	
BULK SALES (customer, mgd) <u>NONE</u>	
NUMBER OF SERVICES <u>400</u>	% METERED <u>---</u>
MUNICIPALITIES SERVED (est. services in each) <u>BYRAM TWP.</u>	
TOTAL ESTIMATED POPULATION SERVICED <u>1056</u>	
CURRENT/RECENT WATER RESTRICTIONS <u>NONE</u>	
NEW CONSTRUCTION (Project Numbers) <u>NONE</u>	
DISTRIBUTION MAINS: Sizing <u>4"</u> (min) to <u>12"</u> (max) Pressures <u>50 psi</u> (min) to <u>90 psi</u> (max) Hydrants/Flushing Program <u>10 - ONCE PER YR</u>	

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
A-280	1X YR 3/12/87 REAG	4/88 - 6/89
Coliform	2 PER MONTH	OK then 7/89
Inorganics	3 yrs	DONE 4/88
Nitrate	"	" "
Trihalomethanes		
Organics		
Turbidity		
Radiochemical	4 yrs	87
SECONDARY	3 yrs	DONE 4/88
Cl <sub>2</sub>	DAILY	DAILY

NAME OF LABORATORY GARDEN STATE LABS CERTIFICATION # 07044  
ADDRESS IRVINGTON, N.J. 07111

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES



COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE 11-8-90

GENERAL INFORMATION

PURVEYOR/  
FACILITY COLBY WATER COMPANY

FILE LOCATION BYRAM TWP, SUSSEX COUNTY PW-ID # 1904007

MAILING ADDRESS P.O. BOX 814, ANDOVER, NEW JERSEY 07821

ADMIN. JOHN SEABERG REQUIRED T  
LICENSES W N/A

BUSINESS (201) 691-8174 Licensed Operators: T W N/A

TELEPHONE # Admin. 691-8174

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): ONE (1) WELL AT 70 TAMARACK  
RD. WELL HEAD PROJECTS THROUGH POOL DECK, WELL  
PIT ON SIDE OF BACK YARD.

Est Tot Eff Cap: EST 0.003 MG

TREATMENT: source, type, capacities(mgd): NONE

Est Tot Eff Cap: \_\_\_\_\_

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): THREE (3) CON-AIRE (425 gal)  
HYDRO-PNEUMATIC TANKS IN WELL PIT.

Est Tot Cap: 0.000375 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

RECEIVED

DEC 19 1990

Est Tot Avail: \_\_\_\_\_

AUXILIARY POWER: location, type, capabilities: NONE

N.J. STATE DEPT. OF  
ENVIRONMENTAL PROTECTION  
BUREAU OF SAFE DRINKING WATER

ATTACHMENT E3



DELIVERY INFORMATION		1904007
PLANT DELIVERED WATER (mgd, month, year) Max <u>JULY 88 0.003 MGD</u> Min <u>FEB 88 0.003 MGD</u> Annual Average <u>0.003 MGD</u>		
BULK PURCHASES (provider, mgd) <u>NONE</u>		
BULK SALES (customer, mgd) <u>NONE</u>		
NUMBER OF SERVICES <u>19</u>		% METERED <u>100%</u>
MUNICIPALITIES SERVED (est. services in each) <u>PRIVATE RESIDENCES ON AND AROUND COLBY DRIVE</u>		
		TOTAL ESTIMATED POPULATION SERVICED <u>85</u>
CURRENT/RECENT WATER RESTRICTIONS <u>NONE</u>		
NEW CONSTRUCTION (Project Numbers) <u>NONE</u>		
DISTRIBUTION MAINS: Sizing <u>3"</u> (min) to <u>4"</u> (max) Pressures <u>—</u> (min) to <u>70 PSI</u> (max) Hydrants/Flushing Program <u>NONE</u>		

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	2-MONTH	OK THRU 88
Inorganics	1/3 YEARS	NONE 88
Nitrate	11	11
Trihalomethanes		
Organics		
Turbidity		
RADIOLOGICAL	1/4 YEARS	DUE 90 DONE 86
A-280	2 TIMES PER YEAR	DONE 86, 87, 88, 89 TWICE PER YEAR
SECONDARY REQS	1/3 YEARS	DONE 86 DUE 89
COARSENMENT	ONCE	DONE 86

NAME OF LABORATORY I.C.M. LABS - RANDOLPH, N.J. ALL EXCEPT COLIFORM CERTIFICATION # 14116  
ADDRESS BURHAM LABS RD#2 - SLEEPY HOLLOW RD, SUSSER, NJ # 19103 GLG

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES



COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE 8-2-89

GENERAL INFORMATION

PURVEYOR/  
FACILITY FOREST LAKES WATER COMPANY

FILE LOCATION BYRAM TOWNSHIP, SUSSEX COUNTY

PW-ID # 1904003

MAILING ADDRESS P.O. BOX 264, ANDOVER, N.J. 07821

ADMIN. KENNETH HANSEN - SECY. TREASURER

REQUIRED T-1  
LICENSES W-1

BUSINESS  
TELEPHONE # Admin.: 201-786-5692

Licensed Operators: T-4

WILLIAM 201-264-1133  
HORTON W-4

ROBERT MOONEY - ASST. OPERATOR  
201-786-5692

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): TWO WELLS: BOTH LOCATED OFF

FOREST LAKES DRIVE, WELL NO. 1 0.166MGD

WELL NO. 2 0.460MGD WELL NO. 2 USED

ONLY WHEN NEEDED.

BOOSTER STATION ON FOREST LAKES DR.

TWO PUMPS #1-125HP #2-125HP Est Tot Eff Cap: 0.625MGD

TREATMENT: source, type, capacities(mgd): WALLACE + TIERNAN HYPOCHLORINATION

AT BOTH WELLS.

Est Tot Eff Cap: 0.625MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): ONE (1) STANDPIPE OFF CROW'S

NEST RD. 0.166MG, 1 HYDRO-PNEUMATIC TANK AT WELL #1 0.006MG

1 UNDERGROUND HOLDING TANK AT WELL NO. 2 0.005MG.

Est Tot Cap: 0.105MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

AUXILIARY POWER: location, type, capabilities: NONE





NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max JUNE 1989 0.136 mgd Min FEB 1989 - 0.094 mgd Annual Average 0.115 mgd

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 380

% METERED 6140

MUNICIPALITIES SERVED

(est. services in each) 350 SERVICES IN BYRAM TWP.

30 SERVICES IN ANDOVER TWP.

TOTAL ESTIMATED POPULATION SERVED 6140

CURRENT/RECENT WATER RESTRICTIONS LAWNS + CARS JULY - AUGUST

NEW CONSTRUCTION

(Project Numbers) NONE

DISTRIBUTION MAINS: Sizing 4" (min) to 6" (max)  
Pressures 35 PSI (min) to 110 PSI (max)  
Hydrants/Flushing Program 37 / 2 x 4R

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
CHLORIDE RESIDUAL	DAILY	DAILY
Coliform	2 PER MONTH	OK THRU 7/89
Inorganics	3 yrs	DONE 4/88
Nitrate	3 yrs	" "
Trihalomethanes		
Organics		
Turbidity		
A-280	2 x 4R	4/88 / 5/88 5/89
SECONDARY DEGS	3 yrs	DONE 4/88
RADIOLOGICAL	4 yrs	DONE 87

NAME OF LABORATORY DURHAM LABS / GARDEN STATE LABS CERTIFICATION # 19103 / 07044

ADDRESS RD 2, Box 20, SLEEPY HOLLOW RD, SUSSEX, N.J. 07461 - COLIFORM  
GARDEN STATE ALL EXCEPT COLIFORM STUYVESANT AVE, IRVINGTON NJ. 07111  
COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES

3-4

COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE 8-22-89GENERAL INFORMATION

PURVEYOR/ FACILITY <u>NORTH SHORE WATER ASSOCIATION</u>	
FILE LOCATION <u>BYRAM TOWNSHIP, SUSSEX COUNTY</u>	PW-ID # <u>1904004</u>
MAILING ADDRESS <u>1 HITOGA TRAIL, ANDOVER, NEW JERSEY 07821</u>	
ADMIN. <u>TIM LOWERY</u>	REQUIRED T-1 LICENSES W
BUSINESS TELEPHONE # Admin.: <u>201 691-5623</u>	Licensed Operators: <u>T-2</u> ER. HOME. W <u>201 657-5344</u>

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): ONE WELL ON CATANA TRAIL, 0.025MGD  
SECOND WELL USED APRIL THRU OCTOBER ONLY. FOUR(4) SERVICES

Est Tot Eff Cap: 0.025MGD

RF TMENT: source, type, capacities(mgd): CHEM-TECH HYPOCHLORINATION 20gpd cap

Est Tot Eff Cap: 0.025MGD

ISHED WATER STORAGE: descriptions, locations, capacities(mgd): HYDRO PNEUMATIC TANK LOCATED  
N WELL HOUSE.

Est Tot Cap: 0.00052MGD

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail: \_\_\_\_\_

UXILIARY POWER: location, type, capabilities: PORTABLE PROPANE GENERATOR AVAILABLE  
20M ASSOCIATION MEMBER

ATTACHMENT E7



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page

DELIVERY INFORMATION

PLANT DELIVERED WATER  
(mgd, month, year) Max MARCH 0.0087 MGD Min JULY 89 0.0034 MGD Annual Average 0.0061 MGD

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 22 yr ROUND, 40 SUMMER % METERED 100%

MUNICIPALITIES SERVED  
(est. services in each) NORTH SHORE SECTION OF CRANBERRY LAKE

TOTAL ESTIMATED  
POPULATION SERVICED 60-100

CURRENT/RECENT  
WATER RESTRICTIONS NONE

NEW CONSTRUCTION  
(Project Numbers) NONE

DISTRIBUTION MAINS: Sizing 1" (min) to 1 1/2" (max)  
Pressures 20 PSI (min) to 60 PSI (max)  
Hydrants/Flushing Program NONE

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
pH-280	2X YR	6/88 - 11/88 - 5/89
Coliform	1 PER MONTH	OK THRU 7/89
Inorganics	3 YRS	DONE 3/86
Nitrate	3 YRS	DONE 3/86
Trihalomethanes		
Organics		
Turbidity		
CL <sub>2</sub> RESIDUAL	Daily	Daily
RADIOLOGICAL	4 YRS	DOS
SECONDARY EGGS	3 YRS	6/88
CORROSIVITY	ONCE	1983

NAME OF LABORATORY ENVIRONMENTAL PROFILE LABORATORIES CERTIFICATION # 15526

ADDRESS RT 37 BUSINESS PARK, SUITE 13, TOMS RIVER, N.J. 08755  
201 244-6278

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE

ATTACHMENT E8



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES



COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE 10-4-90

GENERAL INFORMATION

PURVEYOR/ FACILITY	STRAWBERRY POINT PROPERTY OWNERS ASSOCIATION		
FILE LOCATION	BYRAM TWP, SUSSEX COUNTY	PW-ID #	190 4006
MAILING ADDRESS	200 NORTH SHORE ROAD, ANDOVER, NEW JERSEY 07821		
ADMIN.	GAIL BIERMAN	REQUIRED LICENSES	T-1 W-1
BUSINESS TELEPHONE #	Admin.: (201) 547-7237	Licensed Operators	T-3 W-3
			WILLIAM GRABER

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): ONE WELL AT STRAWBERRY POINT DRIVE AND NORTH SHORE DRIVE. NEW SECOND WELL IS DRILLED BUT NOT YET ON LINE.

Est Tot Eff Cap: #1 0.042MGD

TREATMENT: source, type, capacities(mgd): CHEM-TECH. INTERNATIONAL HYPOCHLORINATOR. 5 GALLON CONTAINER

2 Est Tot Eff Cap: 0.042MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mgd): ONE HYDROPNEUMATIC TANK AT WELL HOUSE.

Est Tot Cap: 0.001MG

EMERGENCY-INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail:

AUXILIARY POWER: location, type, capabilities: GAS GENERATOR AVAILABLE FROM LOCAL FIRE DEPARTMENT.



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max JAN 0.010MGD Min MAY 0.0022MGD Annual Average 0.052MGD

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 30 YEAR ROUND / 5 SUMMER % METERED 100%

MUNICIPALITIES SERVED (est. services in each) STRAWBERRY POINT SECTION OF CRANBERRY LAKE

TOTAL ESTIMATED POPULATION SERVICED 90-110

CURRENT/RECENT WATER RESTRICTIONS NONE

NEW CONSTRUCTION (Project Numbers) NONE

DISTRIBUTION MAINS: Sizing 24 (min) to 41 (max)  
Pressures 20 PSI (min) to 40 PSI (max)  
Hydrants/Flushing Program NONE

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	MONTHLY	OK thru 9/90
Inorganics	3 yrs	7/87, 88 due 7/91
Nitrate	11	7/87, 88 7/91
Trihalomethanes	—	—
Organics	—	—
Turbidity	—	—
SECONDARY	3 yrs	87 due 90
A-LBG	2 yrs	6/88, 9/88, 7/89, 10/89 due 90
RADIOLOGICAL	4 yrs	87 due 90

NAME OF LABORATORY I.C.M. CERTIFICATION # 14116

ADDRESS 1152 ROUTE 10, RANDOLPH, NJ 07869

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

WATER TREATMENT DEFICIENCIES NONE

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES

111

COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE June 17, 1988

## GENERAL INFORMATION

PURVEYOR/  
FACILITYWillor Manor Water Company

FILE LOCATION

Byram Twp. Sussex CountyPW-ID # 1904008

MAILING ADDRESS

RD #2 6 Birch Rd., Andover, N.J. 07821

ADMIN.

Jane VanderbiltREQUIRED  
LICENSEST  
WN/A

BUSINESS

TELEPHONE #

Admin.: (201) 347-2804Licensed Operators: TW

## FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd):

1 well - Rt 206 + Willor Dr. 20gpmEst Tot Eff Cap: 0.028 mgdTREATMENT: source, type, capacities(mgd): None

Est Tot Eff Cap: \_\_\_\_\_

FINISHED WATER STORAGE: descriptions, locations, capacities(mg):

1 - 5,000 gal. hydro pneumatic tank  
near well.Est Tot Cap: 0.005 mgd

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):

None

Est Tot Avail: \_\_\_\_\_

AUXILIARY POWER: location, type, capabilities: NoneATTACHMENT E11



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page 2

DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max unknown Min unknown Annual estimated Average 0.005

BULK PURCHASES (provider, mgd) None

BULK SALES (customer, mgd) None

NUMBER OF SERVICES 16 % METERED 0

MUNICIPALITIES SERVED (est. services in each) Willor Manor Development

TOTAL ESTIMATED POPULATION SERVICED 55

CURRENT/RECENT WATER RESTRICTIONS None

NEW CONSTRUCTION (Project Numbers) None

DISTRIBUTION MAINS: Sizing 1 1/2" (min) to 6" (max)  
Pressures 40 psi (min) to 60 psi (max)  
Hydrants/Flushing Program NONE

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	<u>2 / Month</u>	
Inorganics	<u>1 / 3 years</u>	<u>Oct 1984, due 87</u>
Nitrate	<u>1 / 3 years</u>	<u>Oct 1984, due 87</u>
Trihalomethanes		
Organics		
Turbidity		
Radiological	<u>1 / 4 years</u>	<u>1983, due 87</u>
A-280	<u>2 per year</u>	<u>Done Feb 1985, July 85,</u>
Secondary Regs	<u>1 / 3 years</u>	
Corrosivity	<u>once</u>	

NAME OF LABORATORY Durham Labs / I.C.M. - (A-280) CERTIFICATION # 19103/14116

ADDRESS RD 2 Sleepy Hollow Rd, Sussex, N.J. 07461 / Rt 10 Randolph, N.J. 07869

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES No water level indicator, no flow meter, no casing vent

TREATMENT DEFICIENCIES None

ATTACHMENT E12

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICESCOMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE 10-4-89GENERAL INFORMATION

PURVEYOR/  
FACILITY BOROUGH OF STANHOPE WATER DEPARTMENT

FILE LOCATION STANHOPE BOROUGH, SUSSEX COUNTY PW-ID # 1919001

MAILING ADDRESS 77 MAIN STREET, STANHOPE, NEW JERSEY 07874

ADMIN. JOHN ARNTZ REQUIRED T-2 JIM FLOYD  
LICENSES W-1

BUSINESS 201-347-6348 T-2 JIM FLOYD  
TELEPHONE # Admin. (201) 347-0159 Licensed Operators: T-2 GARAGE W-3 GARAGE

GO TO GARAGE SMITH

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd):

3-4 WELL #2 - MUSCONETCONG AVE 0.115MGD

WELLS #3 + 4 - DYNAPAC PROPERTY #3 0.238MGD #4 0.158MGD

WELL #5 - PLANE LANE 0.504MGD Est Tot Eff Cap: 1.015MGD

TREATMENT: source, type, capacities(mgd):

WELLS # 3 + 4 REGAL CYLINDER MOUNT 1.5lbs CAP

WELLS # 2 + 5 FISHER PORTER 3lbs CAP.

Est Tot Eff Cap: 1.015MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg):

TWO (2) CONCRETE GROUND TANKS 0.250MG EACH

1 ELEVATED TANK 0.050MG

Est Tot Cap: 0.550MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):

1 8" MAIN WITH NETCONG BOROUGH WATER DEPT.  
(METERED)

Est Tot Avail: -

AUXILIARY POWER: location, type, capabilities:

75KW DIESEL GENERATOR ATWELL #5 CAN PUMP 300 GAL/MIN.

EST TOT





DELIVERY INFORMATION	
PLANT DELIVERED WATER (mgd, month, year) Max DEC 88 0.456 MGD Min NOV 88 0.377 MGD Average 0.407 MGD	Annual
BULK PURCHASES (provider, mgd) NONE	
BULK SALES (customer, mgd) NONE	
NUMBER OF SERVICES 1045	% METERED 100%
MUNICIPALITIES SERVED (est. services in each) STANHOPE BOROUGH	
TOTAL ESTIMATED POPULATION SERVED 3700 5000	
CURRENT/RECENT WATER RESTRICTIONS NONE	
NEW CONSTRUCTION (Project Numbers) NONE (REGULAR MAIN REPLACEMENTS)	
DISTRIBUTION MAINS: Sizing 4" (min) to 8" (max) Pressures 40 PSI (min) to 120 PSI (max) Hydrants/Flushing Program 60/2X46	

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
A-280	2X4R	12/88-6/89-8/89
Coliforms	5 PER MONTH	OK THRU 9/89
Inorganics	3 YRS	4/88
Nitrate	"	"
Trihalomethanes		
Organics		
Turbidity		
RADIOLOGICAL	4 YRS	DUE 88
SECONDARY REGS	3 YRS	4/88
SODIUM	3 YRS	9/87 DUE 90
CORROSIVITY	ONCE	DONE

NAME OF LABORATORY INDUSTRIAL CORROSION MGMT CERTIFICATION # 14047-  
ADDRESS RANDOLPH, N.J. 07869

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES ALL CHLORINATION ROOMS, LACK PANIC  
BAR HARDWARE ON THE INSIDE OF THE DOORS.  
N.J.A.C. 7:10-11.13(F)1

ATTACHMENT E14

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES

2-3

COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE 9-26-89

## GENERAL INFORMATION

PURVEYOR/  
FACILITY HOPATCONG BOROUGH WATER DEPARTMENT

FILE LOCATION HOPATCONG BOROUGH, SUSSEX COUNTY PW-ID # 1912001

MAILING ADDRESS RIVER STYX ROAD, HOPATCONG BOROUGH, 07843

ADMIN. JOHN ESKILSON REQUIRED T-1  
LICENSES W-2

BUSINESS  
TELEPHONE # Admin. (201) 770-1200 EXT 13  
Licensed Operators: T-2 WENDALL INHOFFER W-2 RICHARD MEYER  
340-4300 W-2 LIC. OP.  
(201) 770-1150  
(201) 770-0277

## FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): 8 WELLS #1 MADISON TRAIL 0.122MGD.  
#2 HUDSON AVE 0.057MGD. #3 CRESCENT RD 0.106MGD. RIVER STYX WELL 0.122MGD.  
SQUIRE FIELD WELL 0.106MGD. #5 HUDSON AVE 0.057MGD. #8 DARTAN AVE  
0.064MGD. MARINER WELL 0.072MGD. Est Tot Eff Cap: 0.698MGD

TREATMENT: source, type, capacities(mgd):

HYPOCHLORINATION AT EACH WELL (WALLACE + TIERNAN),  
5 GPD.

Est Tot Eff Cap: 0.698MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): STAND PIPE BEHIND COMMUNITY CENTER  
RT. 607 0.500MG. MUSCONETCONG AVE STAND PIPE 0.168MG. MUSCONETCONG  
AVE HYDROPNUMATIC TANK 0.002MG. SIX (6) STANDPIPES ON BROOKLYN  
MOUNTAIN RD 0.152MG TOTAL. Est Tot Cap: 0.820MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail:

AUXILIARY POWER: location, type, capabilities: ONAN PORTABLE GAS GENERATOR  
AVAILABLE, 90AMP = 30KW, STORED IN WATER DEPARTMENT GARAGE.  
GENERATOR, ELECTRICAL HOOKUP PROVIDED AT EACH WELL HOUSE.



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max MAY 89 0.466 MGD Min DEC 88 0.360 MGD Annual Average 0.413 MGD

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 1580

% METERED 100%

MUNICIPALITIES SERVED

(est. services in each) HOPATCONG BOROUGH

TOTAL ESTIMATED  
POPULATION SERVED 5,240

CURRENT/RECENT  
WATER RESTRICTIONS NONE

NEW CONSTRUCTION

(Project Numbers) NONE

DISTRIBUTION MAINS:

Sizing 1 1/2" (min) to 12" (max)

Pressures 40 PSI (min) to 140 PSI (max)

Hydrants/Flushing Program 147 / 1x yr

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	7 per month	OK thru 8/89
Inorganics	3 yrs	DUE 5/90
Nitrate	3 yrs	
Trihalomethanes		
Organics		
Turbidity		
Radiological	4 yrs	DUE 91
SECONDARY RES.	3 yrs	DUE 5/90
A-280	2x yr	DONE 5/88 - 12/88 - 6/89
CHLORINE RES.	Daily	DAILY

NAME OF LABORATORY PASSAIC VALLEY WATER COMMISSION CERTIFICATION # 16047

ADDRESS P.O. Box 198, LITTLE FALLS, N.J. 07424

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICESCOMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE July 23, 1990

## GENERAL INFORMATION

PURVEYOR/  
FACILITYRoxbury Township Water DepartmentFILE LOCATION Roxbury Township, Morris CountyPW-ID # 1436003MAILING ADDRESS 72 Eyland Ave, Succasunna, N.J. 07876

ADMIN.

J. ZouvelekisREQUIRED T-1  
LICENSES W-2

BUSINESS

TELEPHONE # Admin.: 201-398-2818 Licensed Operators: T-2 D. Sutton W-3 D. Sutton

## FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): Well #1 (0.576 mgd) - temporarily out of service. Well #2 (0.360 mgd) - located on Ford Road. Well #4 (0.432 mgd) - located on Center Street. Well #12 (0.432 mgd) - located on Center Street. All wells are interconnected.

Est Tot Eff Cap: 1.224 mgd

TREATMENT: source, type, capacities(mgd): Well #2 is temporarily on WBT hypochlorinator (24 GPD-Cap.) - well will soon be returned to gas chlorination (Fisher & Porter - 1016/d-cap.). Well #4 has gas chlorination (Fisher & Porter - 1016/d cap.). Well #1 has WBT hypochlorinator (24 GPD-Cap.). Well #12 has WBT hypochlorinator (25 GPD-Cap.).

Est Tot Eff Cap: 1.224 mgd

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): There are two standpipes on Benzel (0.1 and 0.215 mg). A ground tank on 2<sup>nd</sup> Str. (1.0 mg). High and low level alarms to police station and office. There is a booster station for Well #2 on Ford Road.

Est Tot Cap: 1.315 mg

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):

None

Est Tot Avail:

AUXILIARY POWER: location, type, capabilities: Well #2 has an Onan Diesel Generator. Well #4 has an Wankesha Diesel Generator. Well #12 has an Onan Diesel Generator that is presently being installed.



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page 2

DELIVERY INFORMATION

PLANT DELIVERED WATER (med, month, year) Max 0.4117 mgd	June 1990	Feb. 1990 Min 0.327 mgd	Annual July 1989 - June 1990 Average 0.3767 mgd
BULK PURCHASES (provider, mgd)	None		
BULK SALES (customer, mgd)	None		
NUMBER OF SERVICES	1597	% METERED	100
MUNICIPALITIES SERVED (est. services in each)	Roxbury Twp (1321); Mt. Arlington (276)		
		TOTAL ESTIMATED POPULATION SERVED 6316	
CURRENT/RECENT WATER RESTRICTIONS	None		
NEW CONSTRUCTION (Project Numbers)	None		
DISTRIBUTION MAINS:	Sizing 3' (min) to 16" (max) Pressures 20 psi (min) to 150 psi (max) Hydrants/Flushing Program 63 hydrants / 2 times / year		

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	7 / month	10 / month
Inorganics	1 / 3 years	Done 10/89; Due 10/92
Nitrate	"	" ; "
Trihalomethanes		
Organics		
Turbidity		
Radon/Inclides	1 / 4 years	Done 6/88; Due 6/92
Secondary	1 / 3 years	Done 10/89; Due 10/92
A-280	2 per year	Done 12/89; 5/90; Due 12/90

NAME OF LABORATORY Garden State Lab Inc / R.H. Cummings CERTIFICATION # 07044/14004  
ADDRESS 399 Stuyvesant Ave, Irvington, N.J. / 29 Woodland Dr, Bonton, N.J.

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES

None

TREATMENT DEFICIENCIES

None

ATTACHMENT EP

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICESCOU-15 BOW  
10/27/92  
JMRCOMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE 9-17-92GENERAL INFORMATION

PURVEYOR/  
FACILITY MOUNT OLIVE TOWNSHIP WATER DEPARTMENT - VILLAGE GREEN

FILE LOCATION MOUNT OLIVE TWP WATER & SEWER DEPT  
AT PLANT RT 206 N. & MUNIC HALL PW-ID # 1427007

MAILING ADDRESS P.O. Box A, Route 46, Budd Lake, NJ 07827

ADMIN. LOU COREA JR REQUIRED T-1  
LICENSES W-2

BUSINESS 201 JOHN RAKOWSKI 584-7086

TELEPHONE # Admin.: 691-0900 Licensed Operators: T-4 W-4

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): FOUR WELLS

#1 LOCATED AT MALL 0.073 MGD #2 LOCATED BEHIND MALL 0.060 MGD

#3 (ARTESIAN) BEHIND MALL 0.055 MGD #4 LOCATED IN COMPLEX 0.194 MGD

Est Tot Eff Cap: 0.382 MGD

TREATMENT: source, type, capacities(mgd): GAS CHLORINATION AT ALL FOUR WELLS

WALLACE & TIERMAN w/ CAPITAL CONTROLS

Est Tot Eff Cap: 0.382 MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): ONE TANK LOCATED AT

BUFF EDGE CIRCLE

Est Tot Cap: 1.0 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail: —

AUXILIARY POWER: location, type, capabilities: PORTABLE GENERATOR, FOUR WELLS

ARE ALL RUN ON SEPARATE POWER GRIDS (T.C.P.C.)



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page 2

DELIVERY INFORMATION			
PLANT DELIVERED WATER (mgd, month, year) Max	5/92 / 0.642 MGD	2/92 / 0.1912 MGD	Annual Average 8/91 - 8/92 0.2484 MGD
BULK PURCHASES (provider, mgd) NONE			
BULK SALES (customer, mgd) NONE			
NUMBER OF SERVICES	1202	% METERED	100%
MUNICIPALITIES SERVED (est. services in each) AREA NORTH OF BUDD LAKE, VILLAGE WAY & FAIRWAY DRIVE AREA, VILLAGE GREEN APARTMENTS & MALL			
			TOTAL ESTIMATED POPULATION SERVED
CURRENT/RECENT WATER RESTRICTIONS NONE			
NEW CONSTRUCTION (Project Numbers) W-07-92-4655 POLYPHOSPHATE FEED TO SEQUESTER IRON, MANGANES. HARDNESS AT WALLS 1-4			
DISTRIBUTION MAINS: Sizing 6" (min) to 10" (max) Pressures 40 PSI (min) to 70 PSI (max) Hydrants/Flushing Program 21 / TWICE PER YEAR			

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	4 PER MONTH	O.K. THRU 8/92
Inorganics	EVERY 3 YEARS	6/91
Nitrate	" "	" "
Trihalomethanes	-	-
Organics	-	-
Turbidity	-	-
A-280	TWICE PER YEAR	6/91, 11/91, 5/92
SECONDARY	EVERY 3 YEARS	6/91
RADIOLOGICAL	EVERY 4 YEARS	1992

NAME OF LABORATORY CFM ENVIRONMENTAL SERVICES CERTIFICATION # 18367  
ADDRESS 3434 ROUTE 22 WEST, SOMERVILLE, NJ 08876

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES ① ALL FOUR CHLORINE GAS ROOMS LACK A MINIMUM OF 2 CHLORINE

GAS CYLINDERS INTERCONNECTED. AS REQUIRED BY N.J.A.C. 7:10-11.13(f)3

② GAS ROOMS LACK GAS MASKS & AIR PACKS IN VIOLATION OF N.J.A.C. 7:10-11.13(f)8

③ WELL 1 CHLORINE ROOM FAN NOT OPERATING IN VIOL. OF N.J.A.C. 7:10-11.13(f)1.

ATTACHMENT E20



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
 DIVISION OF WATER RESOURCES  
 ENFORCEMENT & REGULATORY SERVICES



2/2/82  
 my

COMPLIANCE EVALUATION INSPECTION  
 PUBLIC COMMUNITY WATER SUPPLY

DATE 10-20-92/10-22-92

GENERAL INFORMATION

PURVEYOR/  
 FACILITY MOUNT OLIVE TOWNSHIP WATER DEPARTMENT - SAND SHORE SUPPLY  
WATER & SEWER DEPT. RT 206 N. MT OLIVE.  
 FILE LOCATION AND MUNICIPAL BUILDING, BUDD LAKE PW-ID # 1427006  
 MAILING ADDRESS P.O. BOX A, BUDD LAKE, NJ 07828  
 ADMIN. LOU CORREA, JR. REQUIRED T-1  
 LICENSES W-1  
 BUSINESS JOHN RAKOWSKI 584-7086 HOME (908) 723-0690  
 TELEPHONE # Admin.: (201) 691-0900 Licensed Operators: T-4 W-4

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): FOUR WELLS. #1 0.144 MGD LOCATED  
NEXT TO 224 SAND SHORE RD. #2 0.072 MGD LOCATED NEXT TO #19  
ALCREST DR. - THIS WELL OUT OF SERVICE. #3 0.072 MGD LOCATED  
AT END OF CAMELOT DR. #4 0.093 - CAMELOT - OUT OF SERVICE Est Tot Eff Cap: 0.216 MGD  
 TREATMENT: source, type, capacities(mgd): HYPOCHLORINATION AT WELL #1 & #3.  
MEC-O-MATIC FEEDER PUMP AT WELL 1, AND A CHEM-  
TREC FEEDER AT WELL 3.  
 Est Tot Eff Cap: 0.216 MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): ONE STANDPIPE LOCATED  
ON CAMELOT DR. - 0.420 MG, ONE STORAGE TANK  
AT WELL #3 (STONEHEDGE) - 0.002 MG  
 Est Tot Cap: 0.422 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE  
 Est Tot Avail: —

AUXILIARY POWER: location, type, capabilities: TOWNSHIP CAN CONNECT A 4000 WATT  
PORTABLE GENERATOR TO WELL #1 IF NECESSARY.





NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page 2

DELIVERY INFORMATION

PLANT DELIVERED WATER 5/91 1/92 Annual 1/91 - 9/92  
(mgd month year) Max 0.0619 MGD Min 0.033 MGD Average 0.044 MGD

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 150 % METERED 100%

MUNICIPALITIES SERVED  
(est. services in each) ALCREST AVE, OVERHILL RD., BIRKESIDE DR.,  
GLENSIDE DR., LOCUST DR., KENNEDY DR., CAMELOT DR.,  
CISA DR. & ANDREA CT.

TOTAL ESTIMATED  
POPULATION SERVED 500

CURRENT/RECENT  
WATER RESTRICTIONS NONE

NEW CONSTRUCTION  
(Project Numbers) NONE

DISTRIBUTION MAINS: Sizing 6" (min) to 8" (max)  
Pressures 40 PSI (min) to 130 PSI (max)  
Hydrants/Flushing Program 18 / 1 X YEAR

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	<u>ONCE PER MONTH</u>	<u>O.K. THRU 9/92</u>
Inorganics	<u>EVERY 3 YEARS</u>	<u>DONE 6/91</u>
Nitrate	<u>" " "</u>	<u>DONE 6/91</u>
Trihalomethanes	<u>—</u>	<u>—</u>
Organics	<u>—</u>	<u>—</u>
Turbidity	<u>—</u>	<u>—</u>
<u>A-280</u>	<u>TWICE A YEAR</u>	<u>5/90, 11/91, 5/92</u>
<u>SECONDARIES</u>	<u>ONCE EVERY 3 YEARS</u>	<u>6/91</u>
<u>RADIOLOGICAL</u>	<u>EVERY 4 YEARS</u>	<u>6/91</u>

NAME OF LABORATORY CFM ENVIRONMENTAL SERVICES CERTIFICATION # 148367  
140 BUSINESS QUARTERS  
ADDRESS 3434 ROUTE 22 W. SOMERVILLE, NJ 08876

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICESCOMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE 1-6-93GENERAL INFORMATION

PURVEYOR/ FACILITY <u>MOUNT OLIVE TOWNSHIP WATER DEPT. - HIGH RIDGE / GILDMINE SUPPLY</u>	
FILE LOCATION <u>MOUNT OLIVE WATER &amp; SEWER RT 206 N.</u>	PW-ID # <u>1427002</u>
MAILING ADDRESS <u>PO BOX A, ROUTE 46 BUDD LAKE NJ 07828</u>	
ADMIN. <u>LUCIANO COREA - BUSINESS ADMIN.</u>	REQUIRED T-2 LICENSES W-1
BUSINESS TELEPHONE # Admin. <u>(201) 691-0900</u>	HOME <u>(908) 723-0690</u> → JOHN RAKOWSKI 584-7086 Licensed Operators: T-4 W-4

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): TWO (2) WELLS LOCATED OFF  
STOKES RD. WELL 1 = @ 0.0432 MGD  
WELL 2 = @ 0.0489 MGD

Est Tot Eff Cap: 0.0921

TREATMENT: source, type, capacities(mgd): ① HYPOCHLORINATION (PRE CHLORINATION) W/ T @  
1 DAY  
PUMP FROM 55 GAL SOLUTION TANK ② POTASSIUM PERMANGANATE  
FOR IRON & MANGANESE REMOVAL - 2 FILTERS

Est Tot Eff Cap: 0.0921

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): HYDRO-PNEUMATIC TANKS,  
UNDERGROUND ADJACENT TO TREATMENT PLANT ON STOKES  
TANK 1 = 20,000 GAL

Est Tot Cap: 0.02 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail: —

AUXILIARY POWER: location, type, capabilities: NONE AVAILABLE FOR CONNECTION



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Pa

DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max	12/91 0.017 MGD	8/92 0.012 MGD	Annual Average	12/91 - 11/92 0.0131
BULK PURCHASES (provider, mgd)	NONE			
BULK SALES (customer, mgd)	NONE			
NUMBER OF SERVICES	89	% METERED		C
MUNICIPALITIES SERVED (est. services in each)	FLANDERS RD., MORLYN TER., MADISON AVE, WYNWOOD AVE, CLINTON AVE, STOKES RD., WOODBINE RD.			
	TOTAL ESTIMATED POPULATION SERVED		210	
CURRENT/RECENT WATER RESTRICTIONS	NONE			
NEW CONSTRUCTION (Project Numbers)	NONE			
DISTRIBUTION MAINS:	Sizing 8" (min) to 24" (max) Pressures 30 PSI (min) to 80 PSI (max) Hydrants/Flushing Program 015 / YEARLY			

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	ONCE PER MONTH	O.K. THRU 11/92
Inorganics	EVERY 3 YEARS	DONE 6/91 DONE 6/94
Nitrate	EVERY 3 YEARS	DONE 6/91 DONE 6/94
Trihalomethanes	NA	-
Organics	NA	-
Turbidity	NA	-
A-280	TWICE A YEAR	11/91, 5/92, 11/92
SECONDARY	EVERY 3 YEARS	DONE 6/91 DONE 6/94
RADIOLOGICAL	ONCE EVERY 4 YRS	DONE 6/91

NAME OF LABORATORY CARDEN STATE LABS CERTIFICATION # 20044  
ADDRESS 410 HILLSIDE AVE, HILLSIDE, N.J. 07205

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES WELL BLOWOFF PIPE INSIDE TREATMENT  
BUILDING NOT SCREENED.

TREATMENT DEFICIENCIES THIS WATER SYSTEM IS NOT POST-CHLORINATING  
IN VIOLATION OF N.J.A.C. 7:10-11.13(a)3.



DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES



COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE August 25, 1993

GENERAL INFORMATION

SURVEYOR/ FACILITY <u>East Brookwood Estates Property Owners Association, Incorporated</u>	
FILE LOCATION <u>Byram Township, Sussex County</u>	PW-ID # <u>1904002</u>
MAILING ADDRESS <u>P.O. Box 575, Stanhope, New Jersey, 07874</u>	
ADMIN. <u>Richard Stupa</u>	REQUIRED T-1 LICENSES W-1
BUSINESS TELEPHONE * Admin.: <u>(201) 347-9004</u>	Licensed Operators: <u>Robert Gradusko. (201) 347-1525</u> T-4 W-4

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): Three (3) wells:

Well #1 located off of Brookwood Rd. in basketball court; 0.0864 MGD

Well #2 located off of Trout Brook Rd near Trout Brook; 0.0547 MGD

Well #3 located off of Mountain Rd.; 0.0288 MGD Est Tot Eff Cap: 0.17 MGD

TREATMENT: source, type, capacities(mgd): 12-13 % solution of Sodium Hypochlorite  
added to Well #'s 2 + 3. Well #1 fed directly into system.

FINISHED WATER STORAGE: descriptions, locations, capacities(mgd): one (1) stand pipe w/ booster  
pump above Well #3 - Mountain Rd.; 0.07 MG. Well #'s 1 + 2 fed  
directly into system.

Est Tot Eff Cap: 0.0835 MGD

Est Tot Cap: 0.07 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): NONE

Est Tot Avail: —

AUXILIARY POWER: location, type, capabilities: NONE - Gravity feed



## PUBLIC COMMUNITY WATER SUPPLY INSPECTION



## DELIVERY INFORMATION

PLANT DELIVERED WATER 7/93 11/93 Annual 7/92-7/93  
(mgd, month, year) Max 0.0562 MGD Min 0.0339 MGD Average 0.0386 MGD

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 178 % METERED 0

MUNICIPALITIES SERVED  
(est. services in each) East Brookwood Estates section of  
Byram Township

TOTAL ESTIMATED  
POPULATION SERVICED est. 612

CURRENT/RECENT  
WATER RESTRICTIONS lawn watering allowed on odd/even date basis

NEW CONSTRUCTION  
(Project Numbers) NONE

DISTRIBUTION MAINS: Sizing 4" (min) to 6" (max)  
Pressures 20 psi (min) to 60 psi (max)  
Hydrants/Flushing Program 4/1 x per year

## MONITORING &amp; REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
A-280's	2 / year	11/91, 4/92, 11/92, 5/93
Coliform	1 / month	OK thru 7/93
Inorganics	1 / 3 years	DONE 4/91, DUE 4/94
Nitrate	1 / year	1 / month, OK thru 7/93
Trihalomethanes	NA	NA
Organics	4 / year: every 2nd year	DUE by 1995
Turbidity	NA	NA
Secundaries	1 / 3 years	DONE 4/91, DUE 4/94
Radiologicals	1 / 4 years	DONE 1986, DUE ???
Lead + Copper	Start 7/1/93	1st Round DUE 12/31/93

NAME OF LABORATORY ICM, Inc. / Q.C., Inc. CERTIFICATION # 14116/77166

ADDRESS 1152 Rte. 10, Randolph, NJ / P.O. Box 514, Southampton, PA

## COMPLIANCE EVALUATION

SOURCE DEFICIENCIES The blowoff pipe for Well # 2 is not adequately protected  
against the entry of pollution (N.J.A.C. 7:10-11.4(g)2.).

TREATMENT DEFICIENCIES NONE

ATTACHMENT F



State of New Jersey  
Department of Environmental Protection and Energy

Robert C. Shinn, Jr.  
Commissioner

TO: Cat Swamp Hill Dump Site File

FROM: David Dibblee, HSMS IV, Office of Site Assessment

RE: Private Potable Wells Within 4-Miles

The number of private potable wells in the vicinity of the site was calculated by counting the number of homes outside of areas served by smaller water companies in the area. These calculations should be considered estimated due to the fact that distinctive service boundaries could not be accurately assessed for the smaller water companies. However, it should be noted that potable water in Byram Township is acquired entirely by private potable wells and a number of smaller water companies.

ATTACHMENT G





**State of New Jersey  
Department of Environmental Protection and Energy**

Robert C. Shinn, Jr.  
Commissioner

TO: Cat Swamp Hill Dump Site File

FROM: David Dibblee, HSMS IV

RE: 4-mile Population Calculations

The populations that reside within 4 miles of the Cat Swamp Hill Dump Site were calculated using a combination of the known number of houses counted from topographic and local maps in the vicinity of the site as well as the 1990 GEMS population database.

ATTACHMENT H

4-20-61


1116 31 1053

5 AG 4  
1111  
52 22

ATTACHMENT H1

4-3 -74

803 25 5387



ATTACHMENT I





State of New Jersey  
Department of Environmental Protection and Energy  
Division of Publicly Funded Site Remediation

CN 413  
Trenton, NJ 08625-0413  
Tel. # 609-984-2902  
Fax. # 609-633-2360

Anthony J. Farro  
Director

TO: Cat Swamp Hill Dump Site File  
FROM: David Dibblee, HSMS IV, Office of Site Assessment  
RE: April 8, 1994 Pre-Sampling Assessment

At approximately 1040 on April 8, 1994 David Dibblee and David Triggs of the NJDEPE, Office of Site Assessment met with Margaret McGarrity and Mark Smith of the Byram Township Environmental Commission at the Above listed site.

The inspection began at Area #1 which was a trench located on the north side of the dump site. (see site map) The dimensions of the trench appeared to be approximately 80 feet in length by 10 feet wide. Soil gas surveys conducted within the middle of the trench at several locations did not reveal readings above background. A photograph was taken of the trench facing the north.

Area #2 was then inspected which lies to the west of Area #1. Area #2 was also a trench approximately 60 X 15 feet. This area contained ponded water within the trench as well as various debris including tires, metal and other household garbage. Soil gas surveys were conducted on the ends of the trench where dry soil could be found. No readings above background were noted in this area and a photograph was taken of the trench facing south.

From Area #2 the inspectors traveled south-easterly across the site to a series of trenches on the southern boundary of the dump area. Here four distinct trenches were noted running in an east-west direction. This location was labeled as Area #3 on the site map and each trench was identified as Trench #1-4 from north to south. The trenches and surrounding area was littered with drum carcasses containing a hardened resin or putty like substance as well as rock-like slag waste, foil backed insulating material, tires, a type of metal foil and other debris. Soil gas surveys were conducted throughout the trenches and around some of the drum

carcasses. No readings above background were noted in any of these trenches. Photographs were taken of each of trenches as well as the drums and other debris which littered the area.

From this location the inspectors traveled west towards Areas#4 and #5. These areas did not have definitive boundaries as the other areas did, however; similar debris was noted here including rolls of the fiberglass-type insulating material and drums of the hardened resin-like material. In some instances the entire drum had decayed away leaving only the hardened resin material formed in the shape of the drum. Photographs were taken of the materials littering this area.

The next area inspected was along the eastern edge of the dump site where the topography quickly dips towards a swamp between the dump and Route 206. Traveling along the bottom of the hillside various bails and rolls of the unknown insulating material were noted partially buried or on the ground surface on the hillside. Soil gas surveys conducted at the base of the hill near the swamp revealed reading of up to 20 units on the photoionization detector (Hnu) and 4 units on the organic vapor analyzer (OVA). It is unknown if these readings were attributable to decaying matter or common "swamp gases". Photographs were taken of the materials in this area as well as the swamp from the higher elevations of the dump.

It was noted during the inspection that no fences exist at the site and access to the dump area is easy for the outside population. No stressed flora or fauna was noted at the site. The inspectors left the site at 1225.

ATTACHMENT J



NORTHWEST NEW JERSEY  
AN INVENTORY AND HISTORY  
OF HISTORIC ENGINEERING AND INDUSTRY

BY

H. LEEDOM LEFFERTS, JR., DIRECTOR

AND

DAVID R. PEIFER, ASSOCIATE DIRECTOR

WARREN AND SUSSEX COUNTIES INVENTORY

DREW UNIVERSITY

MADISON, NEW JERSEY

U.S. DEPARTMENT OF THE INTERIOR  
HERITAGE CONSERVATION AND RECREATION SERVICE  
OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION

1979

5673  
L-45  
repro  
REPRODUCED BY  
NATIONAL TECHNICAL  
INFORMATION SERVICE  
U.S. DEPARTMENT OF COMMERCE  
SPRINGFIELD, VA. 22161

ATTACHMENT

J1

## STONE ARCH BRIDGE (1874)


Stanhope  
18.524440.4527450/  
Stanhope

Single span keystone arch bridge. Roadway width approximately 30 feet. Keystone bears date 1874. Random coursed limestone construction, arch span about 15 feet. This bridge once carried a rail spur to the Stanhope Furnace. It now serves as an industrial road for Compac Corporation.

U.S. MINERAL WOOL COMPANY  
STANHOPE PLANT (1875)

Stanhope  
18.524290.4527380/  
Stanhope

Today, the United States Mineral Products Corporation occupies the site of the early United States Mineral Wool Company plant at Stanhope, New Jersey. Little remains of the original plant; however, its history is documentable. Mineral wool is a specialized insulating product made by heating rock and blowing jets of compressed air or steam through it. The result is a fibrous fireproof mass which has excellent insulating properties. Such a product was produced naturally during an eruption of Mt. Kilauea in Hawaii in 1836. The first man-made slag fibers were produced in 1864 by G. Perry in Wales and used in making mortar. In 1870, Siemens and Dieterle began producing slag wool for insulation at Neusattel, Germany, and an American patent was issued to J. Player. In 1869, the first commercial scale production of mineral wool was carried out by the Parrott family, makers of Parrott guns, and Alexander D. Elbers at Stanhope, New Jersey. In 1875, the United States Mineral Wool Company was formed and operated on the slag produced by the Stanhope furnace, then operated by the Musconetcong Iron Works. In 1876, improvements were made to the process under patent #180,470: "Improvement in the Process of Disintegrating Molten Scoriaceous Substances." This involved the addition of other siliceous material to the slag and remelting it. Feldspar was obtained from Lockwood, about 3 miles away, and added to the mix. On November 17, 1885, a new cupola was added to the Stanhope plant which allowed for the production of two grades of mineral wool with different proportions of rock and slag. Grade 1 with more rock was marketed at \$5 per 100 pounds, while Grade 2, with a higher slag content, sold for \$1 per 100 pounds. In 1881, the New York Steam Company purchased the plant and used mineral wool to insulate its steam pipes in New York City. In addition, mineral wool was used to insulate railroad passenger cars and "reefers" as well as cold storage houses



New York Steam Company used this system in the 1880's to insulate underground steam pipes. Boxes were packed with mineral wool.

Illustration of Product Application, U.S. Mineral Wool Company  
(courtesy U.S. Mineral Products Corporation)

and as insulation and sound deadening in construction, especially after the 1880's. By February 23, 1886, the Stanhope plant was producing 2,500 pounds of rock wool and 6,000 pounds of slag wool per day. (U.S. Mineral Products Co., 100 Years of Producing Energy Conserving Materials, 1975; The Daily Advance, "Insulation Industry Started Here," Dover, N.J., November 18, 1975; The Stanhope Eagle 8/11/1885, 9/22/1885, 9/29/1885, 2/20/1885, 10/27/1885, 11/17/1885, 2/23/1886; National Car Builder, Ap. 1882, "Mineral Wool" p. 47, R. M. van Arsdale, pub., N.Y., N.Y., 1882; Scientific American, Architects and Builders Addition, p. 73, "Mineral Wool as a Filling," Ap. 1887; Mr. Frank Stumph, V. P., U.S. Mineral Products Co., Stanhope, N.J.)

BRIDGE-U.S. MINERAL PRODUCTS COMPANY  
(ca. 1875)

Stanhope  
18.524240.4527380/  
Stanhope

This stone arch bridge, about 30 feet long, 10 feet wide with an arch span of 12 feet, provided rail access by the Delaware, Lackawanna, and Western, and later the Erie-Lackawanna to the U.S. Mineral Wool Plant and the Stanhope Furnace. It is in generally fair condition and today carries an industrial road inside the U.S. Mineral Products plant. (Deed map in the possession of U.S. Mineral Products Co., 41 Furnace Street, Stanhope-Survey, April 3, 1928.)

CONRAIL BRIDGE #63.07  
(1870, ca. 1890)

Mansfield  
18.507210.4514940/  
Washington

This stone arch bridge, constructed by the Delaware, Lackawanna, and Western Railroad in 1870, spanned a dirt road. It has been widened probably ca. 1890 to carry a double track mainline and a siding. The original portion on the south side measures 11½ feet in height and 16 feet in width. The length of the old section is 45 feet. The new (1890) section is 15½ feet high, 17 feet 1/8 inch wide and 18 feet, 6 inches long. The arches are keystone type with the finer dressing being found on the older arch. The road has been abandoned, the structure now serving as a drainage tunnel.

ATTACHMENT K

Dave = well is 124'  
casing 106'  
more information attached

copy

June 7, 1994

Byram Township Environmental Commission  
10 Mansfield Drive  
Stanhope, N.J. 07874

The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

Ex. 6

Ex. 6

2 Sutton Lane  
P.O. Box 785  
Andover, N.J. 07821

Dear Ex. 6

This is to remind you that David Dibblee and David Triggs of the New Jersey Department of Environmental Protection and Energy (NJDEPE) will come to your home on June 16 to gather water samples for testing.

They will be working in the area all day and so may be at your place any-time from about 9 a.m. to 4 p.m. I've asked them to try to get there first thing in the morning and that seems likely.

Thank you again for agreeing to participate and help Byram Township find out whether the old dumpsite on Cat Swamp Hill presents a hazard. If you have any questions, please call me at 347-2358.

Yours truly,

Margaret McGarrity, Chairwoman  
Byram Township Environmental Commission

ATTACHMENT K1

Dave Dibblee — This man knows of an old well that was in use when the dump was operating + is on the site itself. He'll take you there if you like. He's lived right there all his life.  
Margaret McGarrity

BOARD OF HEALTH  
TOWNSHIP OF BYRAM

PERMIT TO LOCATE AND CONSTRUCT OR ALTER  
A WATER SUPPLY

Permission is hereby granted..... Ex. 6

Name of Owner or Contractor

..... 2 Sutton Lane  
Address

☒ Locate and Construct or to ☐ Alter

A WATER SUPPLY

Location: Block No ...366....Lot No ...13.....Street....Sutton.Lane  
as shown on Application for Permit to Locate and Construct or  
Alter a Water Supply.

Water Supply Number ...22-28398.....

IN ACCORDANCE WITH Ordinances of the Board of Health of the  
Township of Byram.

"An Ordinance establishing a code regulating the location, con-  
struction, alteration, use and supervision of individual and semi-  
public water supplies, requiring certain permits, providing for the  
inspection of such supplies, the fixing of fees and prescribing  
penalties for violations."

BOARD OF HEALTH OF BYRAM TOWNSHIP

Date .December. 8., 1988

Fee \$125.....

*Judith Hancox/mrc*  
For the Board of Health

PERMIT EXPIRES ONE YEAR  
FROM DATE OF ISSUE

The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

(To be filed in Duplicate)

DATE 12-8-88

Location - Address. 2 Sutton Lane Block 366 Lot 13  
NO. & STREET

Size of Lot.....3.70 Acres.....Area Sq. Ft. ....

Owner (print) . . . . . Ex. 6 . . . . . Telephone . . . . . Ex. 6 . . . . .

Present Address 2 Sutton Lane

Name & Address of Contractor... Dan Ballentine Well Drilling, Inc. P.O. Box 178  
Port Murray, Rd. Port Murray, N.J. 07865 Telephone... 609 7666

Number of Realty Improvements to be Served .....

Type of Water System to be Constructed \_\_\_\_\_

1. Non-public water system (individual dwelling).....
2. Public, non-community water system (restaurants, office buildings, businesses, etc.).....

Type of Well or Source.....Rotary Drilled.....

Estimate Depth of Casing.....50.....

Method of Sealing ..... Cement graft

Pumping Equipment ..... Submersible

Purification Facilities (if required) .....

Proposed Use of Water Supply.....domestic.....

Estimated Water Demands and Basis of Estimates..... 57

Describe Type of Alteration Proposed.... New.... well, ... replace... well.... Point... under... House

Contractor (signed)  ..... Owner (signed) .....

Signed Judith Hancock / M.M.C. APPLICATION FEE \$25.00  
HEALTH OFFICER/SANITARIAN

DATE APPROVED Dec 8, 1950 By John F. [illegible]

APPLICATION FEE \$25.00

PERMIT FEE.....100.00

**RETURN ORIGINAL APPLICATION**

FRANCIS J. SCHINDELAR  
P. E. & LAND SURVEYOR, L.C. #4062  
MAIN ST., STANHOPE, NEW JERSEY

ATTACHMENT K3



The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

WEEK ADVANCE NOTICE  
WELL DRILLING REQUESTED

**APPROVED**

BYRAM TOWNSHIP HEALTH DEPT.

BY *Gudeth Hancock*

ONE WEEK  
OF WELL

REQUESTED

DATE 12-14-88

N 6-36° E 313.85'

One Week  
24 HOUR NOTICE OF WELL  
DRILLING REQUIRED

WELL TO BE 100 FEET  
COMPONENT OF THE


WELL CASING TO BE 12"

ALL PUMP AND WELL LINE  
SHALL BE MADE WITH THE USE  
OF PITLESS ADAPTER

3.70

WELL WATER SHOULD BE TESTED AT LEAST  
ONCE A YEAR FOR OWNERS PROTECTION

N 67-54° W 158.5'  
N 74-37° W 201.5'  
N 39-48° W 118.1'



565-00E

No Septics  
within 150'  
of well

DEC 8 1988

Byram Township Health Dept.

PROPERTY OF

EX. 6

BYRAM TWP. SUSSEX CO. N.J.

SCALE 1"=100'

MAY 1, 1971

ATTACHMENT

K4

FRANCIS J. SCHINDLER

**RECEIVED DEC 30 1988 WELL RECORD**

The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

Well Permit No. 22 - 28398  
Atlas Sheet Coordinates 22 : 41 : 493**OWNER IDENTIFICATION - Owner** Ex. 6Address 2 Sutton Lane  
City NEEDHAM State MA Zip Code 01821**WELL LOCATION** - If not the same owner please give address.Address 2 Sutton Lane Owner's Well No. \_\_\_\_\_  
County SUSSEX Municipality NEEDHAM TWP. Lot No. 13 Block No. 366**WELL USE** Withdrew - For Water Supply Status in use**WATER USE** Domestic Average \_\_\_\_\_ gals. daily Maximum \_\_\_\_\_ gals. daily**WELL CONSTRUCTION**Date well completed 12 / 15 / 88**BOREHOLE DIMENSIONS**Depths: Total 124 ft. Finished \_\_\_\_\_ ft.Diameter: Top 10 in. Bottom 5 7/8 in.Land Surface Elevation at well 800 ft. Elevation was determined using Topographic Map #22Casing Height (stick-up) above land surface 1.25 ft.

	DEPTH TO TOP (FT.)	LENGTH (FT.)	DIAMETER (IN.)	TYPE AND MATERIAL Screens: Note Slot Size(s)
Casing 1		<u>106</u>	<u>6</u>	<u>1.250 Well Steel</u>
Casing 2				
Casing 3				
Screen 1				
Screen 2				
Tail Piece				
Gravel Pack				
Grout				
Grouting Method			<u>Drill + Drive</u>	

**WELL FLOWS NATURALLY** \_\_\_\_\_ gals. per min. at \_\_\_\_\_ ft. above the land surface.

Water rises to \_\_\_\_\_ ft. above the land surface.

**RECORD OF TEST**Test Date 12 / 15 / 88Static water-level before pumping 15 ft. below land surface. Water level \_\_\_\_\_ ft. below land surface after \_\_\_\_\_ hrs. of pumping.Water level was measured using gate Drawdown \_\_\_\_\_ ft.Discharge rate measured using estimated Discharge Rate 15 gals. per min.Well was pumped using oil Specific Capacity \_\_\_\_\_ gals. per min. per ft. of drawdown

Observed effects on nearby wells \_\_\_\_\_

Water Quality (taste, odor, color, etc.) \_\_\_\_\_

**PERMANENT PUMPING EQUIPMENT**Installed by Not Installing Pump Type \_\_\_\_\_

Pfrs. Name \_\_\_\_\_ Model \_\_\_\_\_

CAPACITY: Pump delivers \_\_\_\_\_ GPM at \_\_\_\_\_ PSI pressure.

POWER: \_\_\_\_\_ HP at \_\_\_\_\_ RPM Power Source \_\_\_\_\_

DEPTHS: Pump \_\_\_\_\_ ft. Footpiece \_\_\_\_\_ ft. Airline \_\_\_\_\_ ft.

FLOW METER: Model \_\_\_\_\_ installed on \_\_\_\_\_ in. diameter pipe.

**CONTRACTOR** - Name of Drilling ContractorDAN BALLENTINEAddress P.O. Box 178, P.O. Murray Rd.City P.O. Murray State N.J. Zip Code 07865Name of Driller Carl T. Kierby License No. 1752Signature of Contractor [Signature] Date 12 / 23 / 88

COPIES: White - DEP Canary - Driller Pink - Owner

Goldenrod - Health Dept.

ATTACHMENT K5

PAGE 2 OF 2

## Well Permit No.

Type of Rig

Aquifer/Geo. Fm.:

0-7' Clay + Gravel

7'-67' Pen. Sand.

67-74. Gray clay - silt & sand.

74. 99 low ~~grey~~ clay + gravel

3-124 Weathered granite

W.S. 108 - 117

## Storet Hydrogeo Code

USGS Hydrogeo Code

Depth to Bedrock \_\_\_\_\_ ft.

Bedrock Lith. Code

Bedrock Fm. Code

Completed by

Date        /        /       

**Thick.**

Lith.

Fm.

GWP1 No.

NJPDES No.

Latitude

### Lat-Long Accuracy

USGS Quadrangle

Drainage Basin Code

OTHER FILES:

☐ Lithologic Log☐ Geophysical Logs

 **Samples Available**

☐ Water Chemistry

County/Municipality Code

☐ **Aquifer Test**

### ☐ Pollution Case

☐ Water Level Data

Checked by

Date \_\_\_\_\_

RECORDED

JAN 9 1989

ATTACHMENT K6

PERMIT TO DRILL WELL

VALID ONLY AFTER APPROVAL BY THE D.E.P.

COORD #: 22.41.4 93

RECEIVED DEC 09 1988

Mail to  
Water Allocation  
CN 029  
Trenton, N.J. 08625

Owner Ex. 6  
Address 2 Sutton Lane,  
Andover, N. J. 07821  
Name of Facility same  
Address 2 Sutton Lane,  
Byram Township, N. J.

Driller Dan Ballentine Well Drilling, Inc.  
Address P. O. Box 178, Port Murray Road,  
Port Murray, N. J. 07865-0178

Diameter of Well	6	Inches	Proposed Depth of Well	200	Feet
Proposed Capacity of Pump	less than 20	GPM	Method of Drilling (cable-tool, rotary, etc.)	rotary	
Use of Well (See Reverse)	Domestic - replacement point				
Drinking Water Supply?	a	yes (see #6 on reverse)	now		



LOCATION OF WELL

Lot #	Block #	Municipality	County
13	366	Byram Twsp.	Sussex

Draw sketch showing distance and relations of well site to nearest public roads, streets, septic systems, etc.

State Atlas Map No. 22

3.70 Acres



The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

REVERSE SIDE FOR IMPORTANT PROVISIONS AND REGULATIONS PERTAINING TO THIS PERMIT. APPROVAL OF THIS PERMIT IS SUBJECT TO ACCEPTANCE OF AND COMPLIANCE WITH THE FOLLOWING ADDITIONAL CONDITIONS.

- ☐ DOMESTIC/PUBLIC NON-COMMUNITY Water Supply Wells shall comply with N.J.A.C. 7:10-12.1 et. seq.
- ☐ PUBLIC COMMUNITY Water Supply Wells shall obtain construction and operation permits from the Bureau of Safe Drinking Water in accordance with N.J.A.C. 7:10-11.2 and be constructed in compliance with N.J.A.C. 7:10-11.3.
- ☐ DOMESTIC IRRIGATION SUPPLY - No piping from the well for which the permit applies shall enter any building.
- ☐ HEAT PUMP WELLS - Wells must be a minimum of 50 feet apart and the water must be returned to the same aquifer as the production well. A two hour pump test must be performed on the return well at a rate of 1½ times the estimated return flow of water.
- ☐ INDUSTRIAL SUPPLY - A physical connection control permit shall be obtained pursuant to the provisions of N.J.A.C. 7:10-10-1 et. seq.
- ☐ REPLACEMENT WELL - Existing well must be sealed by a certified New Jersey licensed well driller.
- ☐ MONITORING PURPOSES ONLY ☐ IRRIGATION PURPOSES ONLY ☐ TEST PURPOSES ONLY
- ☐ PINELANDS - Well must be drilled over 100' deep or a clay layer at least 4' in thickness must be encountered.
- ☐ GEOPHYSICAL LOGS of this well must be made. Permanent pumping equipment SHALL NOT be installed until such logs are made.
- ☐ SAMPLES of cuttings required every \_\_\_\_\_ feet or change in material.
- ☐ RESULTS of a volatile organic scan must be obtained prior to using the water and submitted to \_\_\_\_\_
- ☐ MINIMUM distance requirements as per N.J.A.C. 7:10-12.13 have not been met - see attached additional condition(s).

This Space for Approval Stamp

WELL PERMIT APPROVED  
Dept. of Environmental Protection  
Water Resources / Water Allocation

DEC 02 1988

DEC 15 1988

compliance with N.J.S.A. 58:4A-14, application is made for a permit to drill a well at

November 28, 1988

Signature of Driller

Signature of Owner

Ex. 6

COPIES:

Water Allocation — White

Health Dept. — Yellow

Owner — Blue

ATTACHMENT K7

Dave — well is 150'  
casing 50'  
more information attached.

Copy

The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

June 7, 1994

Byram Township Environmental Commission  
10 Mansfield Drive  
Stanhope, N.J. 07874

Ex. 6

116 Route 206  
Stanhope, N.J. 07874

Ex. 6

} one is home +  
one is the bait-fishing  
store they own; you  
will find them at  
the store, both at  
the same location.

Dear

Ex. 6

This is to remind you that David Dibblee and David Triggs of the New Jersey Department of Environmental Protection and Energy (NJDEPE) will come to your store on June 16 to gather water samples for testing.

The store  
is called  
Lee + Sons.

They will be working in the area all day and so may be at your place any-time from about 9 a.m. to 4 p.m. I've asked them to try to get there in the morning and that seems likely.

Thank you again for agreeing to participate and help Byram Township find out whether the old dumpsite on Cat Swamp Hill presents a hazard. If you have any questions, please call me at 347-2358.

Yours truly,

Margaret McGarrity, Chairwoman  
Byram Township Environmental Commission

## WELL RECORD

Well Permit No. 22 26953  
Atlas Sheet Coordinates 25 43 575

Ex. 6

## OWNER IDENTIFICATION - Owner

Address P.O. BOX 147  
City STAN HILL State NC Zip Code \_\_\_\_\_

## WELL LOCATION - If not the same owner please give address.

Owner's Well No. \_\_\_\_\_

Address \_\_\_\_\_  
County \_\_\_\_\_ Municipality BYRAM TWP. Lot No. 10 Block No. 20WELL USE W. the owner Status \_\_\_\_\_WATER USE Domestic Average \_\_\_\_\_ gals. daily Maximum \_\_\_\_\_ gals. daily

## WELL CONSTRUCTION

Date well completed 11/1/85

## BOREHOLE DIMENSIONS

Depths: Total 15.7 ft. Finished 15.7 ft.Diameter: Top 10 in. Bottom 6 in.

Land Surface Elevation at well \_\_\_\_\_ ft.

Elevation was determined using \_\_\_\_\_

Casing Height (stick-up) above land surface 12 ft.

The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

DEPTH TO TOP  
(FT.)LENGTH  
(FT.)DIAMETER  
(IN.)TYPE AND MATERIAL  
Screens: Note Slot Size(s)

Casing 1	<u>5.0</u>	<u>6</u>	<u>Steel</u>
Casing 2			
Casing 3			
Screen 1			
Screen 2			
Tail Piece			
Gravel Pack			
Grout			
Grouting Method			

WELL FLOWS NATURALLY \_\_\_\_\_ gals. per min. at \_\_\_\_\_ ft. above the land surface.

Water rises to \_\_\_\_\_ ft. above the land surface.

## RECORD OF TEST

Test Date 1/1/86Static water-level before pumping 25 ft. below land surface. Water level \_\_\_\_\_ ft. below land surface after \_\_\_\_\_ hrs. of pumping.

Water level was measured using \_\_\_\_\_ Drawdown \_\_\_\_\_ ft.

Discharge rate measured using \_\_\_\_\_ Discharge Rate 25 gals. per min.

Well was pumped using \_\_\_\_\_ Specific Capacity \_\_\_\_\_ gals. per min. per ft. of drawdown

Observed effects on nearby wells \_\_\_\_\_

Water Quality (taste, odor, color, etc.) \_\_\_\_\_

## PERMANENT PUMPING EQUIPMENT

Installed by \_\_\_\_\_ Pump Type \_\_\_\_\_

Mfrs. Name \_\_\_\_\_ Model \_\_\_\_\_

CAPACITY: Pump delivers \_\_\_\_\_ GPM at \_\_\_\_\_ PSI pressure.

POWER: 1 HP at \_\_\_\_\_ RPM Power Source \_\_\_\_\_

DEPTHS: Pump \_\_\_\_\_ ft. Footpiece \_\_\_\_\_ ft. Airline \_\_\_\_\_ ft.

FLOW METER: Model \_\_\_\_\_ installed on \_\_\_\_\_ in. diameter pipe.

## CONTRACTOR - Name of Drilling Contractor

Address 124 S. 4th St.City Charlotte State NC Zip Code 28205Name of Driller D. F. Well Drilling Co. License No. 1236Signature of Contractor D. F. Well Drilling Co. Inc.Date 11/1/85

COPIES:

White - DEP

Canary - Driller

Pink - Owner

Goldenrod - Health Dept.

ATTACHMENT K9

STATE OF NEW JERSEY  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
TRENTON, N.J.

RECEIVED NOV 30 1987  
PERMIT TO DRILL WELL

Permit No.

2226953

08625

VALID ONLY AFTER APPROVAL BY THE D.E.P.

COORD #: 22:415:76

Ex. 6

Owner

Driller

Address

Address

Name of Facility

Address

Diameter of Well

6

Inches

Proposed Depth of Well

UNKNOWING FEET

Proposed Capacity of Pump

7

GPM

Method of Drilling

(cable-tool, rotary, etc.) Rotary

Use of Well (See Reverse)

DOMESTIC (POTABLE WATER)

LOCATION OF WELL

Lot #


Block #

Municipality

County

State Atlas Map No.

40° 58'



Draw sketch showing distance and relations of well site to nearest public roads, streets, septic systems, etc.

North

The redacted information consists of names and/or phone numbers of private individuals. Disclosure of this information would constitute a clearly unwarranted invasion of personal privacy and thus is exempt from mandatory disclosure by virtue of Exemption 6 of the FOIA, 5 U.S.C. § 552(b)(6).

East

South

SEE REVERSE SIDE for IMPORTANT PROVISIONS AND REGULATIONS pertaining to this permit. APPROVAL of this permit is made SUBJECT TO acceptance of and compliance with the following ADDITIONAL CONDITIONS.

- ☐ Pinelands - Well must be drilled over 100' deep or a clay layer at least 4' in thickness must be encountered.
- ☐ It is necessary that Geophysical Logs of this well be made. Permanent pumping equipment SHALL NOT be installed until such logs are made.
- ☐ Authorization by rule under N.J.A.C. 7:14A-1 et seq.
- ☐ Samples of cuttings required every \_\_\_\_\_ feet or change in material.
- ☐ The results of a volatile organic scan must be obtained prior to using the water and submitted to \_\_\_\_\_
- ☐ Domestic Potable Water Supply - The service line for water from the public community water supply system shall be turned off at the curb cock, and the meter shall be removed by the water purveyor.
- ☐ Domestic Irrigation Supply - No piping from the well for which the permit applies shall enter any building.
- ☐ Industrial/Commercial Supply - A physical connection permit shall be obtained pursuant to the provisions of N.J.A.C. 7:10-10.1 et seq., and a vigorous cross connections control program shall be instituted and maintained within the premises.
- ☐ Heat Pump Wells - Wells must be 50 feet apart and the water must be returned to the same aquifer as the production well.
- ☐ \_\_\_\_\_

This Space for Approval Stamp

WELL PERMIT APPROVED  
Dept. of Environmental Protection  
Water Resources/Water Allocation

NOV 19 1987

In compliance with R.S. 58:4A-14, application is made for a permit to drill a well as described above.

Date

Nov. 2, 1987

Signature of Owner

SI LEWIS PIZZYBYSZEWSKI

COPIES:

Water Allocation - White

Health Dept. - Yellow

Owner - Blue

Driller - White

# 355

A CERTIFICATE OF COMPLIANCE  
CANNOT BE ISSUED UNTIL WELL  
DRILLER SUBMITS BOARD OF HEALTH COPY  
OF STATE WELL WATER RECORD

WATER SYSTEM DESIGN APPROVED BY:  
SUSSEX CO. HEALTH DEPT.

SIGNED

DATE

11/14/87

TO A/E

U.S.

ROUTE  
MINIMUM OF 50' OF  
CASING REQUIRED

ATTACHMENT K10

Well Permit No. 22-26733

22.41.576

**DEP USE ONLY**

Aquifer/Geo. Fm. \_\_\_\_\_

Bedrock Fm. Code \_\_\_\_\_

Date \_\_\_\_\_ / \_\_\_\_\_ / \_\_\_\_\_

Thick.                      Lith.                      Fm.

0-3'-Machado

3' - 150' - Limestone

NJPDES No. \_\_\_\_\_

Longitude                      °            '            "

USGS Quadrangle \_\_\_\_\_

County/Municipality Code \_\_\_\_\_

☐ Aquifer Test                      ☐ Water Level Data  
☐ Pollution Case

Date \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_

ATTACHMENT K11



Dave = We have no information on this well.  
We'll try again if you can't get  
it from Mr. Kapsos on the 16th.

June 7, 1994

Byram Township Environmental Commission  
10 Mansfield Drive  
Stanhope, N.J. 07874

Konstantine Kapsos  
Mountainside Restaurant → 347-8787  
198 Route 206  
Andover, N.J. 07821

Dear Mr. Kapsos:

This is to remind you that David Dibblee and David Triggs of the New Jersey Department of Environmental Protection and Energy (NJDEPE) will come to your restaurant on June 16 to gather water samples for testing.

They will be working in the area all day and so may be at your place any-time from about 9 a.m. to 4 p.m. I've asked them to try to get there in the morning and that seems likely.

Thank you again for agreeing to participate and help Byram Township find out whether the old dumpsite on Cat Swamp Hill presents a hazard. If you have any questions, please call me at 347-2358.

Yours truly,

Margaret McGarrity, Chairwoman  
Byram Township Environmental Commission

Dave = well is 150  
casing 50  
more information attached. COPY

RECEIVED

JUN 8 1994

June 7, 1994

Byram Township Environmental Commission  
10 Mansfield Drive  
Stanhope, N.J. 07874

The Stone House (76rs Restaurant) → phone 347-9780  
c/o Mazzei  
54 Richmond Road  
Stanhope, N.J. 07874

Dear Mr. Mazzei:

This is to remind you that David Dibblee and David Triggs of the New Jersey Department of Environmental Protection and Energy (NJDEPE) will come to your restaurant on June 16 to gather water samples for testing.

They will be working in the area all day and so may be at your place any-time from about 9 a.m. to 4 p.m. I've asked them to try to get there in the morning and that seems likely.

Thank you again for agreeing to participate and help Byram Township find out whether the old dumpsite on Cat Swamp Hill presents a hazard. If you have any questions, please call me at 347-2358.

Yours truly,

Margaret McGarrity, Chairwoman  
Byram Township Environmental Commission

He may  
not be there  
but there is  
a spigot in  
front + back  
you can use.  
He says  
the  
dunny  
was  
operating  
as early  
as 1941.

ATTACHMENT K13

APPLICATION FOR WELL PERMIT

Individual and Semipublic Water Supply Code of New Jersey

Installation: New WELL Date SEPT. 30 - 1982

Address of Building ROUTE 206

Map Name, if any - (STATE PERMIT # 22-2174)

Municipality BYRAM Block 70 Lot 9

Owner's Name (Print) STONE HOUSE INC 76 ER RESTAURANT

Name and Address of Well Driller D.F. WELL DRILLING CO INC  
Box 8 NETCONG. N.J.

Type of Building to be Served Garage MINIMUM OF 50' OF

TYPE OF WELL

- (1) Drilled 200 (5) Estimated Depth 200  
(2) Driven CEMENT GROUT (6) Method of Sealing  
(3) Spring SUBMERSIBLE (7) Pumping Equipment  
(4) Surface 80 GALLON TANK (8) Storage Facilities  
(9) Purification Facilities HTH

Make an accurate sketch on a separate sheet and attach to this application showing: Lot dimensions, location of house, location of proposed water supply system, and all buildings. Include distance from house, side and rear lot lines, auxiliary buildings, large trees and sewage systems within 100 feet.

The undersigned agrees to locate, construct or alter the above described individual water supply system in accordance with the standards of the New Jersey State Department of Health and the ordinances of the Municipality of BYRAM and in particular in accordance with the individual and Semipublic water supply code of New Jersey, adopted by the Board of Health of Byram and to accurately follow the layout set forth herein.

OCT 6 1982

WATER SYSTEM DESIGN APPROVED BY  
SUSSEX CO. HEALTH DEPT.

SIGNED SLS

DATE 10-6-82

Willard J. Shelly

Owner or Well Driller

FOR D.F. WELL DRILLING

BYRAM TOWNSHIP  
BOARD OF HEALTH

10-5-82

Recd. 550 Chd # 5425

J. Ebs

(3/77) orig

ATTACHMENT L



# Water Resources Data New Jersey Water Year 1992

Volume 1. Surface-Water Data



U.S. GEOLOGICAL SURVEY WATER-DATA REPORT NJ-92-1  
Prepared in cooperation with the New Jersey Department  
of Environmental Protection and Energy and with other agencies

01455801 MUSCONETCONG RIVER AT LOCKWOOD, NJ

LOCATION.--Lat 40°55'10", long 74°44'07", Sussex County, Hydrologic Unit 02040105, at bridge in Lockwood, at boundary between Sussex County and Morris County, 0.2 mi southeast of Cage Hill, 0.4 mi south of Jefferson Lake, and 0.9 mi downstream from Lubbers Run.

DRAINAGE AREA.--60.1 mi<sup>2</sup>.

PERIOD OF RECORD.--Water years 1976 to October 1991 (discontinued).

COOPERATION.--Field data and samples for laboratory analyses provided by New Jersey Department of Environmental Protection and Energy. Analyses of fecal coliform by the MPN method, enterococcus bacteria by the membrane filtration method, water-phase nutrients, and BOD were performed by the New Jersey Department of Health, Division of Laboratories and Epidemiology.

## WATER QUALITY DATA, WATER YEAR OCTOBER 1991 TO SEPTEMBER 1992

DATE	TIME	DIS-CHARGE, INST. CUBIC FEET PER SECOND	SPE-CIFIC CON-DUCT-ANCE (US/CM)	PH WATER WHOLE FIELD (STAND-ARD UNITS)	TEMPER-ATURE WATER (DEG C)	OXYGEN, DIS-SOLVED (MG/L)	OXYGEN, DIS-SOLVED (PER-CENT SATUR-ATION)	OXYGEN DEMAND, BIO-CHEM-ICAL, 5 DAY (MG/L)	COLI-FORM, FECAL, EC BROTH (MPN)	ENTERO-COCCI, ME, MF WATER TOTAL (COL / 100 ML)
OCT 1991 17...	1230	50	346	7.6	10.0	10.6	95	2.8	5400	>2400
DATE		HARD-NESS TOTAL (MG/L AS CaCO3)	CALCIUM DIS-SOLVED (MG/L AS Ca)	MAGNE-SIUM, DIS-SOLVED (MG/L AS Mg)	SODIUM, DIS-SOLVED (MG/L AS Na)	POTAS-SIUM, DIS-SOLVED (MG/L AS K)	ALKA-LINITY LAB (MG/L AS CaCO3)	SULFATE DIS-SOLVED (MG/L AS SO4)	CHLO-RIDE, DIS-SOLVED (MG/L AS Cl)	FLUO-RIDE, DIS-SOLVED (MG/L AS F)
OCT 1991 17...		110	28	10	24	2.4	78	21	52	0.1
DATE		SILICA, DIS-SOLVED (MG/L AS SiO2)	SOLIDS, SUM OF CONSTI-TUENTS, DIS-SOLVED (MG/L)	NITRO-GEN, NITRITE TOTAL (MG/L AS N)	NITRO-GEN, NITRITE DIS-SOLVED (MG/L AS N)	NITRO-GEN, NO2+NO3 TOTAL (MG/L AS N)	NITRO-GEN, NO2+NO3 DIS-SOLVED (MG/L AS N)	NITRO-GEN, AMMONIA TOTAL (MG/L AS N)	NITRO-GEN, AMMONIA DIS-SOLVED (MG/L AS N)	NITRO-GEN, AM-MONIA + ORGANIC TOTAL (MG/L AS N)
OCT 1991 17...		8.7	197	0.053	0.047	0.76	0.78	0.28	0.28	1.2
DATE		NITRO-GEN, AM-MONIA + ORGANIC DIS. (MG/L AS N)	NITRO-GEN, TOTAL (MG/L AS N)	NITRO-GEN, DIS-SOLVED (MG/L AS N)	PHOS-PHORUS TOTAL (MG/L AS P)	PHOS-PHORUS DIS-SOLVED (MG/L AS P)	CARBON, ORGANIC DIS-SOLVED (MG/L AS C)	CARBON, ORGANIC SUS-PENDED TOTAL (MG/L AS C)	SEDI-MENT, SUS-PENDED (MG/L)	SEDI-MENT, DIS-CHARGE, SUS-PENDED (T/DAY)
OCT 1991 17...		1.1	2.0	1.8	0.04	<0.02	7.1	1.1	3	0.41

## DELAWARE RIVER BASIN

01456200 MUSCONETCONG RIVER AT BEATTYSTOWN, NJ

LOCATION.--Lat 40°48'48", long 74°50'32", Warren County, Hydrologic Unit 02040105, at bridge at Beattystown, 1.6 mi upstream of Hanes Brook, 2.1 mi northeast of Stephensburg, and 3.5 mi northeast of Scrappy Corner.

DRAINAGE AREA.--90.3 mi<sup>2</sup>.

PERIOD OF RECORD.--Water years 1976 to current year.

COOPERATION.--Field data and samples for laboratory analyses provided by New Jersey Department of Environmental Protection and Energy. Analyses of fecal coliform by the MPN method, enterococcus bacteria by the membrane filtration method, water-phase nutrients, and BOD were performed by the New Jersey Department of Health, Division of Laboratories and Epidemiology.

## WATER QUALITY DATA, WATER OCTOBER 1991 TO SEPTEMBER 1992

DATE	TIME	DIS-CHARGE, INST. CUBIC FEET PER SECOND	SPE-CIFIC CON-DUCT-ANCE (US/CM)	PH WATER WHOLE FIELD (STAND-ARD UNITS)	TEMPER-ATURE WATER (DEG. C)	OXYGEN, DIS-SOLVED (MG/L)	OXYGEN, DIS-SOLVED (PER-CENT SATUR-ATION)	OXYGEN DEMAND, BIO-CHEM-ICAL, 5 DAY (MG/L)	COLI-FORM, FECAL, EC BROTH (MPN)	ENTERO-COCCI ME, MF WATER TOTAL (COL / 100 ML)
JAN 1992										
29...	1100	120	336	8.6	2.0	13.7	99	6.1	<20	<10
APR 01...	1300	180	267	8.7	8.0	13.1	114	E1.8	20	<10
JUN 17...	1030	100	342	8.1	21.0	9.1	102	<1.0	3500	150
AUG 12...	1100	53	392	8.4	21.5	9.4	108	E1.7	2400	770


DATE	HARD-NESS, TOTAL (MG/L AS CaCO3)	CALCIUM DIS-SOLVED (MG/L AS Ca)	MAGNE-SIUM, DIS-SOLVED (MG/L AS Mg)	SODIUM, DIS-SOLVED (MG/L AS Na)	POTAS-SIUM, DIS-SOLVED (MG/L AS K)	ALKA-LINITY LAB (MG/L AS CaCO3)	SULFATE DIS-SOLVED (MG/L AS SO4)	CHLO-RIDE, DIS-SOLVED (MG/L AS Cl)	FLUO-RIDE, DIS-SOLVED (MG/L AS F)
JAN 1992									
29...	100	26	8.7	22	1.1	64	22	48	0.1
APR 01...	85	21	8.0	18	1.0	58	18	37	0.2
JUN 17...	100	25	10	24	1.4	75	20	49	0.1
AUG 12...	140	31	14	25	1.9	107	18	50	0.4

DATE	SILICA, DIS-SOLVED (MG/L AS SiO2)	SOLIDS, SUM OF CONSTI-TUENTS, DIS-SOLVED (MG/L)	NITRO-GEN, NITRITE TOTAL (MG/L AS N)	NITRO-GEN, NITRITE DIS-SOLVED (MG/L AS N)	NITRO-GEN, NO2+NO3 TOTAL (MG/L AS N)	NITRO-GEN, NO2+NO3 DIS-SOLVED (MG/L AS N)	NITRO-GEN, AMMONIA TOTAL (MG/L AS N)	NITRO-GEN, AMMONIA DIS-SOLVED (MG/L AS N)	NITRO-GEN, AM-MONIA + ORGANIC TOTAL (MG/L AS N)
JAN 1992									
29...	5.1	174	0.017	0.018	0.63	0.61	0.23	0.21	0.60
APR 01...	5.6	147	0.019	0.019	0.72	0.75	0.18	0.11	0.47
JUN 17...	5.4	184	0.044	0.042	0.85	0.88	0.18	0.11	0.64
AUG 12...	6.1	215	0.087	0.081	0.92	0.87	0.21	0.16	0.85

DATE	NITRO-GEN, AM-MONIA + ORGANIC DIS. (MG/L AS N)	NITRO-GEN, TOTAL (MG/L AS N)	NITRO-GEN DIS-SOLVED (MG/L AS N)	PHOS-PHORUS TOTAL (MG/L AS P)	PHOS-PHORUS DIS-SOLVED (MG/L AS P)	CARBON, ORGANIC DIS-SOLVED (MG/L AS C)	CARBON, ORGANIC SUS-PENDED TOTAL (MG/L AS C)	SEDI-MENT, SUS-PENDED (MG/L)	SEDI-MENT, DIS-CHARGE, SUS-PENDED (T/DAY)
JAN 1992									
29...	0.75	1.2	1.4	0.07	0.04	3.3	0.5	4	1.3
APR 01...	0.38	1.2	1.1	0.03	0.04	3.0	0.5	6	2.9
JUN 17...	0.52	1.5	1.4	0.05	0.02	3.6	0.3	6	1.6
AUG 12...	0.39	1.8	1.3	0.33	0.03	3.4	1.6	56	8.0


ATTACHMENT M











ATTACHMENT N

NEW JERSEY DIVISION OF FISH, GAME AND WILDLIFE  
1995 SPRING TROUT STOCKING SCHEDULE

WATERBODY	PRESEASON	WEEK 1	WEEK 2	WEEK 3	WEEK 4	WEEK 5	WEEK 6	WEEK 7	TOTAL
Mohawk Pond	180	0	140	140	140	140	0	0	740
Monksville Reservoir	1000	0	1000	0	1000	0	1000	0	4000
Mountain Lake	440	0	330	330	330	0	0	0	1430
Mt. Hope Pond	410	0	310	310	310	0	0	0	1340
Mulhockaway Creek	370	0	150	150	150	150	100	0	1070
Mullica Hill Pond	410	0	310	310	310	0	0	0	1340
Musconetcong River - Lower	9920	4330	3850	3970	3850	3850	2410	2480	34660
Musconetcong River - Upper	2890	1300	1160	1160	1160	1160	720	720	10270
Neldon Brook	190	0	190	0	190	0	0	0	570
Neshanic River	280	0	110	0	110	0	0	0	500
Oldham Pond	440	0	330	330	330	0	0	0	1430
Papakating Creek	700	0	280	0	280	0	0	0	1260
Papakating Creek W/B	240	0	240	240	0	0	0	0	720
Pascack Creek	610	0	250	250	250	250	0	0	1610
Passaic River	1540	0	620	620	620	620	0	0	4020
Paulins Kill - Lower	6480	2910	2590	2590	2590	2590	1620	1620	22990
Paulins Kill - Middle	770	350	310	310	310	310	190	190	2740
Paulins Kill - Upper	1350	400	360	540	360	360	220	340	3930
Peapack Brook	500	0	200	200	200	200	120	0	1420
Pequannock River	2060	0	830	830	830	830	520	520	6420
Pequest River - Lower	5560	2500	2220	2220	2220	2220	1390	1390	19720
Pequest River - Middle	1710	770	680	680	680	680	430	430	6060
Pequest River - Upper	650	290	260	260	260	260	160	160	2300
Pine Brook	150	0	150	0	150	0	0	0	450
Pohatcong Creek - Lower	3550	1600	1420	1420	1420	1420	890	890	12610
Pohatcong Creek - Upper	600	0	240	0	240	0	0	0	1080
Pompton Lake	440	0	330	330	330	0	0	0	1430
Pompton River	1890	0	760	760	760	760	0	0	4930
Pond Brook	110	0	100	100	100	100	100	0	610
Popandusing Creek	220	0	220	0	220	0	0	0	660
Prospertown Lake	360	0	270	270	270	0	0	0	1170
Rahway River	2390	0	960	960	960	960	0	0	6230
Ramapo River	4300	1930	1720	1720	1720	1720	1070	1070	15250
Rancocas Creek SW/B	430	0	170	170	170	170	0	0	1110
Raritan River	1260	0	500	500	500	500	0	0	3260
Raritan River N/B	4590	2060	1830	1830	1830	1830	1150	1150	16270
Raritan River S/B - Lower	2890	1300	1160	1160	1160	1160	720	720	10270
Raritan River S/B - Middle	8880	4000	3550	3550	3550	3550	2220	2220	31520
Raritan River S/B - Upper	1310	480	430	520	430	430	270	330	4200
Ringwood Brook	250	0	100	100	100	100	100	0	750
Roaring Rock Brook	350	0	350	0	350	0	0	0	1050
Rock Brook	370	0	0	370	0	0	0	0	740
Rockaway Creek	230	0	100	100	100	100	0	0	630
Rockaway Creek S/B	230	0	100	100	100	100	100	0	730
Rockaway River	5940	2670	2380	2380	2380	2380	1480	1480	21090
Roosevelt Park Pond	450	0	340	340	340	0	0	0	1470
Rosedale Lake	510	0	390	390	390	0	0	0	1680
Round Valley Reservoir	0	0	3870	0	2580	0	5160	0	11610
Roy Spring Brook	160	0	0	160	0	0	0	0	320

ATTACHMENT O

RECEIVED

OCT 4 1994



State of New Jersey

DEPARTMENT OF ENVIRONMENTAL  
PROTECTION

CHRISTINE TODD WHITMAN  
Governor

ROBERT C. SHINN, JR.  
Commissioner

SEP 29 1994

MEMORANDUM

TO: Frank Sorce  
Site Assessment Section

THROUGH: Greg Toffoli *20 11/24/94*  
Joseph Sanguiliano *89/29/94*  
Quality Assurance Section  
Bureau of Environmental Measurements and Quality Assurance

FROM: Linda M. Appel *LA 9/29/94*  
Quality Assurance Section  
Bureau of Environmental Measurements and Quality Assurance

SUBJECT: Analytical data validation of the June 16, 1994 sampling event conducted at  
Cat Swamp Hill Dump, Byram Township. Analyses for TCL by NYTEST  
Environmental, Inc.

Samples Reviewed

<u>Field ID</u>	<u>Lab ID</u>	<u>Matrix</u>	<u>Collection Date</u>
459	2108601	Soil	06/16/94
460	2108604	Soil	06/16/94
461	2108605	Soil	06/16/94
462	2108606	Soil	06/16/94
463	2108607	Soil	06/16/94
464	2108608	Soil	06/16/94
465	2108609	Soil	06/16/94
466	2108610	Soil	06/16/94
467	2108611	Soil	06/16/94
468	2108612	Soil	06/16/94
469	2108613	Soil	06/16/94
470	2108614	Soil	06/16/94
471	2108615	Soil	06/16/94
472	2108616	Soil	06/16/94
473	2108617	Soil	06/16/94
474	2108618	Soil	06/16/94

476	2108619	Soil	06/16/94
477	2108620	Soil	06/16/94
478	2108621	Soil	06/16/94
480	2108622	Soil	06/16/94
481	2108623	Soil	06/16/94
482	2108624	Soil	06/16/94
484	2108625	Soil	06/16/94
485	2108626	Soil	06/16/94
486	2108627	Soil	06/16/94
487	2108628	Soil	06/16/94
488	2108629	Water	06/16/94
489	2108632	Water	06/16/94
490	2108633	Water	06/16/94
491	2108634	Water	06/16/94
493	2108635	Water	06/16/94
496	2108636	Water	06/16/94
497	2108637	Water	06/16/94

The Quality Assurance Section, Bureau of Environmental Measurements and Quality Assurance, Division of Publicly Funded Site Remediation has reviewed the above mentioned samples for Volatile Organics, Semivolatile Organics, Pesticides and PCBs. Please refer to the detailed data validation report and the target and non-target analyte data summary for additional information. Specific comments are provided below.

#### GENERAL COMMENTS

The analytical data package was well organized and all data deliverables were present.

#### VOLATILE ORGANICS

The Volatile Organics analyses were performed according to the CLP Statement of Work (Document No. OLM01.8) and the data are acceptable. Minor qualifications are noted on the target and non-target analyte data summary.

#### SEMIVOLATILE ORGANICS

The Semivolatile Organics analyses were performed according to the CLP Statement of Work (Document No. OLM01.8). Please note the following rejections or qualifications due to analytical deficiencies:

1. The initial analysis of sample 466 was performed at low level with one unacceptable internal standard area and three unacceptable base-neutral surrogate percent recoveries. The laboratory performed a re-extraction/re-analysis at medium level. All internal standard areas and surrogate percent recoveries were acceptable; however, the re-extraction exceeded the holding time by 25 days. Therefore, the base-neutral fraction data in the original analysis are rejected and the data from the medium level re-extraction/re-analysis are rejected. The data from the original analysis for the acid-extractable fraction are acceptable.



2. Sample 481 was chosen as one of the samples for the Matrix Spike/Matrix Spike Duplicate (MS/MSD) analysis. In the original extraction, the laboratory inadvertently added the matrix spiking solution to samples 480 and 485 instead of 481MS and 481MSD. The laboratory performed a re-extraction/re-analysis of samples 480, 481, 481MS, 481MSD and 485. However, the re-extraction exceeded the holding time by 25 days. Therefore, all data for samples 480RE, 481RE, 481MSRE, 481MSDRE and 485RE are rejected. The data from the initial analysis of sample 481 are acceptable. Except for the matrix spiking compounds, the data from the original analysis of samples 480 and 485 are acceptable. The data for the following analytes used as matrix spiking compounds are rejected in samples 480 and 485: Phenol, 2-Chlorophenol, 1,4-Dichlorobenzene, N-Nitroso-di-n-propylamine, 1,2,4-Trichlorobenzene, 4-Chloro-3-methylphenol, Acenaphthene, 4-Nitrophenol, 2,4-Dinitrotoluene, Pentachlorophenol and Pyrene.

3. The following samples had one or more unacceptable internal standard areas in the initial analysis: 470, 473, 476, 477, 478 and 480. Samples 470, 473, 476, 477 and 478 were re-analyzed and a matrix effect was exhibited. Therefore, the data from the original analysis are acceptable with qualifications as noted on the target and non-target analyte data summary. Sample 480 was re-extracted and re-analyzed but the re-extraction exceeded the holding time by 25 days. The data from the original analysis are acceptable with qualifications as noted on the target and non-target analyte data summary (except for those analytes specifically mentioned above in #2). All non-detects (NDs) associated with Internal Standards whose area is less than 50% of the area of the daily standard, are considered estimated and qualified "UJ". For a list of the Internal Standards and the associated analytes, please refer to Attachment A.

4. Sample 466 was analyzed at a 1:10 dilution only and samples 467, 468, 469, 470, 470RE, 471, 472, 474, 476, 476RE and 480 were analyzed at 1:2 dilutions only. In the case narrative, the laboratory states that this was due to the viscous nature of the sample extracts. The end user is alerted that contamination may exist below the elevated detection limits for these samples.

5. Several of the percent recoveries and/or %RPDs were outside the acceptable QC limits in the MS/MSD analyses of samples 459, 481 and 488. No action is required.

6. Several samples have non-target peaks (which appear to be greater than 10% of the nearest eluting Internal Standard) for which a library search was not performed. These peaks elute either with or near a target analyte and when the automated library search is performed, these peaks are excluded from the library search as are the Internal Standards and surrogates. An example of this oversight may be found in sample 478. The chromatogram displays two significant non-target peaks at approximate retention times 21.0 and 23.0 minutes. However, neither of these peaks are listed on Form 1F. If the end user is concerned with tentative identification of the non-target analytes, the laboratory should be contacted, the chromatograms re-reviewed and a manual library search for those overlooked non-target peaks performed.

## PESTICIDES and PCBs

The Pesticide and PCB analyses were performed according to the CLP Statement of Work (Document No. OLM01.8) and the data are acceptable. Please note the following:

1. Several samples had surrogate percent recoveries which were outside the advisory QC limits. This may be due to matrix interference and no action is required. Some surrogate compounds were not recovered in the diluted samples. Again, no action is required. Sample 482 had no surrogate recovery, possibly due to a laboratory error. The laboratory stated in the case narrative that a re-extraction and re-analysis would be performed and the data would be submitted at a later date. Until the data for the re-extraction/re-analysis is received, the Pesticide and PCB data for sample 482 is conditionally rejected.
2. On the Pesticide forms, the laboratory entered %D values in all the fields where %RPD was requested. The data is not affected since all %RPD values would be acceptable.
3. The laboratory analyzed the GPC Pesticide Check Mixture and the Aroclor Check Mixture on an instrument (HP2) different from the instrument (HP3) on which the samples were analyzed. Although this issue is not addressed in the Statement of Work, it is a sound laboratory practice to analyze field samples and associated QC samples on the same instrument.
4. Sample 468 was analyzed at 1:3 and 1:50 dilutions and sample 472 was analyzed at 1:8 and 1:100 dilutions. The end user is alerted that contamination may exist below the elevated detection limits for these two samples.

If you have any questions regarding this review, please do not hesitate to contact this office at 633-0752.

Attachment

c. William Lowry, BEMQA

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 1 of 18

THE NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
459	VOA	Methylene Chloride	U	5 J	5 J	qualify	6
		No TICs were reported.					
	SVOA	Bis(2-ethylhexyl)phthalate	64 J	560 B	560 JB	qualify	3
		21 TICs were reported.					
		RT 4.95	15000 J	23000 JB	23000 JB	negate	1
		RT 27.76	350 J	400 JB	400 JB	negate	1
		The remaining 19 TICs are acceptable.				qualify	9
	PEST/PCB	4,4'-DDE	U	6.1	6.1		
		4,4'-DDD	U	4.3	4.3		
		4,4'-DDT	U	15	15		
		Aroclor 1260	U	58	58		
460	VOA	Methylene Chloride	1 J	2 JB	2 JB	negate	1
		1 TIC was reported.					
		RT 21.31	U	31 J	31 J	negate	3
	SVOA	Phenol	U	150 J	150 J	qualify	6
		Diethylphthalate	U	510	510		
		Pentachlorophenol	U	480 J	480 J	qualify	6
		Butylbenzylphthalate	U	470	470		
		21 TICs were reported.					
		RT 4.90	15000 J	13000 JB	13000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	Endrin	U	18 J	18 J	qualify	11
		Aroclor 1242 (1/50 dilution)	U	24000 D	24000 D		10

ATTACHMENT L5

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 2 of 18.

E NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

AB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
461	VOA	Methylene Chloride	U	3 J	3 J	qualify	6
		2 TICs were reported.					
		RT 17.18	U	30 J	30 J	negate	3
		RT 21.32	U	82 J	82 J	negate	3
	SVOA	No target analytes were detected.					
		4 TICs were reported.					
		RT 4.90	15000 J	19000 JB	19000 JB	negate	1
		The remaining 3 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					
462	VOA	Methylene Chloride	U	4 J	4 J	qualify	6
		2 TICs were reported.					
		RT 17.19	U	6 J	6 J	negate	3
		RT 21.30	U	14 J	14 J	negate	3
	SVOA	No target analytes were detected.					
		8 TICs were reported.					
		RT 4.89	15000 J	16000 JB	16000 JB	negate	1
		The remaining 7 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 3 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
463	VOA	Methylene Chloride	1 J	2 JB	2 JB	negate	1
		2 TICs were reported.					
		RT 17.17	U	7 J	7 J	negate	3
		RT 21.31	U	8 J	8 J	negate	3
	SVOA	No target analytes were detected.					
		8 TICs were reported.					
		RT 4.89	15000 J	17000 JB	17000 JB	negate	1
		The remaining 7 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					
464	VOA	Methylene Chloride	1 J	2 JB	2 JB	negate	1
		2 TICs were reported.					
		RT 17.18	U	9 J	9 J	negate	3
		RT 21.31	U	8 J	8 J	negate	3
	SVOA	No target analytes were detected.					
		6 TICs were reported.					
		RT 4.90	15000 J	17000 JB	17000 JB	negate	1
		The remaining 5 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					

ATTACHMENT 17

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 4 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
465	VOA	Methylene Chloride	1 J	2 JB	2 JB	negate	1
		0 TICs were reported.					
	SVOA	No target analytes were detected.					
		8 TICs were reported.					
		RT 4.89	15000 J	18000 JB	18000 JB	negate	1
		The remaining 7 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					
466	VOA	Methylene Chloride	1 J	4 JB	4 JB	negate	4
		1 TIC was reported.					
		RT 21.32	U	13 J	13 J	negate	3
	SVOA (1/10)	The BN fraction is rejected.				reject	12
		Acid extractables were not detected.					
		15 TICs were reported.					
		RT 4.81	15000 J	43000 JB	43000 JB	negate	1
		The remaining 14 TICs are acceptable.				qualify	9
	PEST/PCB	delta-BHC	U	2.7 J	2.7 J	qualify	11
		Heptachlor	U	2.2 J	2.2 J	qualify	6,11
		Aroclor 1254 (1/3 dilution)	U	1500 D	1500 D		10
		Aroclor 1260 (1/3 dilution)	U	2000 D	2000 D		10

ATTACHMENT L8

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 5 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

SAMPLE MATRIX: Soil

AB NAME: NYTEST

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
467	VOA	Methylene Chloride	1 J	4 JB	4 JB	qualify	2,6
		2 TICs were reported.					
		RT 17.17	U	52 J	52 J	negate	3
		RT 21.32	U	43 J	43 J	negate	3
	SVOA (1/2)	Hexachlorobenzene	U	92 J	92 J	qualify	6
		Di-n-butylphthalate	U	290 J	290 J	qualify	6
		Bis(2-ethylhexyl)phthalate	64 J	890 B	890 JB	qualify	2
		21 TICs were reported.					
		RT 4.90	15000 J	23000 JB	23000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1254	U	660	660		
		Aroclor 1260 (1/10 dilution)	U	4200 D	4200 D		10
468	VOA	Methylene Chloride	1 J	3 JB	3 JB	negate	1
		2 TICs were reported.					
		RT 17.17	U	11 J	11 J	negate	3
		RT 21.31	U	7 J	7 J	negate	3
	SVOA (1/2)	Diethyl phthalate	U	99 J	99 J	qualify	6
		Di-n-butylphthalate	U	130 J	130 J	qualify	6
		Butylbenzylphthalate	U	110 J	110 J	qualify	6
		Bis(2-ethylhexyl)phthalate	64 J	1200 B	1200 JB	qualify	2
		15 TICs were reported.					
		RT 4.86	15000 J	27000 JB	27000 JB	negate	1
		The remaining 14 TICs are acceptable.				qualify	9
	PEST/PCB	Methoxychlor (1/50 dilution)	U	5300 D	5300 D		10
		Aroclor 1248 (1/3 dilution)	U	1300	1300		
		Aroclor 1260 (1/3 dilution)	U	1500	1500		

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 6 of 18

SITE NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
469	VOA	Methylene Chloride	1 J	3 JB	3 JB	negate	1
		1 TICs was reported.					
		RT 21.31	U	8 J	8 J	negate	3
	SVOA (1/2)	Bis(2-ethylhexyl)phthalate	64 J	280 B	280 JB	negate	4
		21 TICs were reported.					
		RT 4.87	15000 J	23000 JB	23000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	beta-BHC	U	6.2 J	6.2 J	qualify	11
		Aroclor 1254	U	190 J	190 J	qualify	11
		Aroclor 1260	U	510	510		
470	VOA	Methylene Chloride	1 J	3 JB	3 JB	negate	1
		2 TICs were reported.					
		RT 17.18	U	10 J	10 J	negate	3
		RT 21.31	U	9 J	9 J	negate	3
	SVOA (1/2)	Diethyl phthalate	U	280 J	280 J	qualify	6
		Di-n-butylphthalate	U	130 J	130 J	qualify	6
		Butylbenzylphthalate	U	210 J	210 J	qualify	6,8
		Bis(2-ethylhexyl)phthalate	64 J	1500 B	1500 JB	qualify	2,8
		NDs associated with Chrysene-d12				qualify	8
		21 TICs were reported.					
		RT 4.86	15000 J	28000 JB	28000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1248 (1/2 dilution)	U	1200 D	1200 D		10
		Aroclor 1260 (1/2 dilution)	U	1000 D	1000 D		10

ATTACHMENT L10



# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 7 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
471	VOA	Methylene Chloride	1 J	18 JB	18 JB	qualify	2,6
		Acetone	U	7 J	7 J	qualify	6
		2 TICs were reported.					
		RT 17.17	U	82 J	82 J	negate	3
		RT 21.31	U	120 J	120 J	negate	3
	SVOA (1/2)	Bis(2-ethylhexyl)phthalate	64 J	1000 JB	1000 JB	qualify	2
		13 TICs were reported.					
		RT 4.86	15000 J	29000 JB	29000 JB	negate	1
		The remaining 12 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1260 (1/5 dilution)	U	1600 D	1600 D		10
472	VOA	Methylene Chloride	1 J	13 JB	13 JB	qualify	2,6
		3 TICs were reported.					
		RT 17.17	U	58 J	58 J	negate	3
		RT 21.31	U	34 J	34 J	negate	3
		The remaining 1 TIC is acceptable.				qualify	9
	SVOA (1/2)	Phenol	U	210 J	210 J	qualify	6
		Pentachlorophenol	U	250 J	250 J	qualify	6
		Pyrene	U	110 J	110 J	qualify	6
		21 TICs were reported.					
		RT 4.85	15000 J	19000 JB	19000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1260 (1/1000 dilution)	U	430000 D	430000 D		10

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 8 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
473	VOA	Methylene Chloride	1 J	10 JB	10 JB	qualify	2,6
		1 TICs was reported at RT 21.31	U	11 J	11 J	negate	3
	SVOA	Phenanthrene	U	200 J	200 J	qualify	6
		Fluoranthene	U	280 J	280 J	qualify	6
		Pyrene	U	280 J	280 J	qualify	6,8
		Benzo(a)anthracene	U	160 J	160 J	qualify	6,8
		Chrysene	U	220 J	220 J	qualify	6,8
		Bis(2-ethylhexyl)phthalate	64 J	260 JB	260 JB	negate	4
		NDs associated with Chrysene-d12				qualify	8
		Benzo(b)fluoranthene	U	180 J	180 J	qualify	6
		Benzo(k)fluoranthene	U	150 J	150 J	qualify	6
		Benzo(a)pyrene	U	160 J	160 J	qualify	6
		16 TICs were reported.					
		RT 4.89	15000 J	21000 JB	21000 JB	negate	1
		The remaining 15 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1248	U	150	150		
		Aroclor 1260	U	120	110		13
474	VOA	Methylene Chloride	1 J	7 JB	7 JB	qualify	2,6
		2 TICs were reported.					
		RT 17.17	U	260 J	260 J	negate	4
		RT 21.31	U	300 J	300 J	qualify	5
	SVOA (1/2)	Bis(2-ethylhexyl)phthalate	64 J	84 JB	84 JB	negate	1
		16 TICs were reported.					
		RT 4.86	15000 J	21000 JB	21000 JB	negate	1
		The remaining 15 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1260	U	290	290		

ATTACHMENT L12

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 9 of 18

TE NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

AB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
476	VOA	Methylene Chloride	1 J	10 JB	10 JB	qualify	2,6
		0 TICs were reported.					
	SVOA (1/2)	Pentachlorophenol	U	730 J	730 J	qualify	6
		Di-n-butylphthalate	U	120 J	120 J	qualify	6
		Bis(2-ethylhexyl)phthalate	64 J	230 JB	230 JB	negate	1
		NDs associated with Chrysene-d12				qualify	8
		21 TICs were reported.					
		RT 4.86	15000 J	21000 JB	21000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1254	U	680	680		
		Aroclor 1260	U	400 J	400 J	qualify	11
477	VOA	Methylene Chloride	2 J	4 JB	4 JB	negate	1
		Acetone	3 J	2 JB	2 JB	negate	1
		2 TICs were reported.					
		RT 17.17	U	15 J	15 J	negate	3
		RT 21.31	U	7 J	7 J	negate	3
	SVOA	4-Methylphenol	U	53 J	53 J	qualify	6
		Pentachlorophenol	U	160 J	160 J	qualify	6,8
		Pyrene	U	140 J	140 J	qualify	6,8
		Butylbenzylphthalate	U	100 J	100 J	qualify	6,8
		NDs associated with Phenanthrene-d10, Chrysene-d12 and Perylene-12				qualify	8
		21 TICs were reported.					
		RT 4.89	15000 J	16000 JB	16000 JB	negate	1
		The remaining 20 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1248	U	210	210		
		Aroclor 1260	U	57 J	57 J	qualify	11

ATTACHMENT L13

## Page 10 of 18

SAMPLING DATE: June 16, 1994

SAMPLE MATRIX: Soil

ATTACHMENT L14

### TARGET & NON-TARGET ANALYTE DATA SUMMARY

THE NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

[illegible]

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 12 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

B NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
481	VOA	Methylene Chloride	2 J	3 JB	3 JB	negate	1
		2 TICs were reported.					
		RT 17.17	U	34 J	34 J	negate	3
		RT 21.29	U	20 J	20 J	negate	3
	SVOA	Target analytes were not detected.					
		11 TICs were reported.					
		RT 4.89	19000 J	25000 JB	25000 JB	negate	1
		RT 16.95	83 J	180 J	180 JB	negate	1
		The remaining 9 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1258	U	180	180		
		Aroclor 1260	U	100 J	110		13
482	VOA	Methylene Chloride	1 J	8 JB	8 JB	qualify	2,6
		Tetrachloroethene	U	5 J	5 J	qualify	6
		3 TICs were reported.					
		RT 17.18	U	71 J	71 J	negate	3
		RT 21.31	U	22 J	22 J	negate	3
		The remaining 1 TIC is acceptable.				qualify	6
	SVOA	Bis(2-ethylhexyl)phthalate	52 J	110 JB	110 JB	negate	1
		18 TICs were reported.					
		RT 4.86	19000 J	18000 JB	18000 JB	negate	1
		The remaining 17 TICs are acceptable.					
	PEST/PCB	Pesticides or PCBs were not detected.				reject	7

ATTACHMENT L116

## Page 13 of 18

SAMPLE MATRIX: Soil

NAME: Cat Swamp Hill Dump

NAME: NYTEST

ATTACHMENT L17

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 14 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
485	VOA	Methylene Chloride	2 J	16 JB	16 JB	negate	4
		Acetone	3 J	23 JB	23 JB	negate	4
		2-Butanone	U	32 J	32 J	qualify	6
		4-Methyl-2-Pentanone	U	10 J	10 J	qualify	6
		0 TICs were reported.					
							7
	SVOA	Phenol	U	7700	—	reject	7
		2-Chlorophenol	U	8600	—	reject	7
		1,4-Dichlorobenzene	U	4500	—	reject	7
		N-nitroso-di-n-propylamine	U	5400	—	reject	7
		1,2,4-Trichlorobenzene	U	5800	—	reject	7
		4-Chloro-3-Methylphenol	U	8400	—	reject	7
		Acenaphthene	U	7000	—	reject	7
		4-Nitrophenol	U	8800 J	—	reject	7
		2,4-Dinitrotoluene	U	5500	—	reject	7
		Pentachlorophenol	U	3600 J	—	reject	7
		Pyrene	U	4400	—	reject	7
		Bis(2-ethylhexyl)phthalate	52 J	680 JB	680 JB	negate	4
		21 TICs were reported.					
		RT 4.90	19000 J	36000 JB	36000 JB	negate	1
		RT 16.97	83 J	1000 J	1000 JB	negate	4
		The remaining 19 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1260	U	57 J	57 J	qualify	6

ATTACHMENT L18



# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 15 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Soil

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/Kg	LAB REPORT CONC ug/Kg	QA REPORT CONC ug/Kg	QA DECISIONS	FOOTNOTE
486	VOA	Methylene Chloride	2 J	4 JB	4 JB	negate	1
		4-Methyl-2-Pentanone	U	1 J	1 J	qualify	6
		0 TICs were reported.					
	SVOA	Fluoranthene	U	120 J	120 J	qualify	6
		Pyrene	U	84 J	84 J	qualify	6
		Benzo(a)anthracene	U	60 J	60 J	qualify	6
		Chrysene	U	80 J	80 J	qualify	6
		Bis(2-ethylhexyl)phthalate	52 J	80 JB	80 JB	negate	1
		14 TICs were reported.					
		RT 4.84	19000 J	21000 JB	21000 JB	negate	1
		RT 16.93	83 J	240 J	240 JB	negate	1
		The remaining 12 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					
487	VOA	Methylene Chloride	2 J	3 JB	3 JB	negate	1
		2 TICs were reported.					
		RT 17.17	U	25 J	25 J	negate	3
		RT 21.31	U	22 J	22 J	negate	3
	SVOA	Bis(2-ethylhexyl)phthalate	52 J	160 JB	160 JB	negate	4
		18 TICs were reported					
		RT 4.36	79 J	88 JB	88 JB	negate	1
		RT 4.85	19000 J	23000 JB	23000 JB	negate	1
		RT 6.13	120 J	96 JB	96 JB	negate	1
		RT 16.94	83 J	290 J	290 JB	negate	4
		The remaining 14 TICs are acceptable.				qualify	9
	PEST/PCB	Aroclor 1260	U	15 J	15 J	qualify	6

ATTACHMENT L19

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 16 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

NAME: NYTEST

SAMPLE MATRIX: Water

TELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/L	LAB REPORT CONC ug/L	QA REPORT CONC ug/L	QA DECISIONS	FOOTNOTE
488	VOA	Methylene Chloride	6 J	14 B	14 JB	negate	1
		Trichloroethene	U	4 J	4 J	qualify	6
		1 TIC reported at RT 18.04.	U	9 J	9 J	negate	3
	SVOA	No target analytes were detected. 4 TICs were reported.					
		RT 4.85	12 J	3 JB	3 JB	negate	1
		RT 6.97	7 J	3 JB	3 JB	negate	1
		RT 7.11	11 J	5 JB	5 JB	negate	1
		The remaining 1 TIC is acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					
489	VOA	Methylene Chloride	6 J	14 B	14 JB	negate	1
		3 TICs were reported.					
		RT 18.04	U	20 J	20 J	negate	3
		RT 22.17	U	9 J	9 J	negate	3
		The remaining 1 TIC is acceptable.				qualify	9
	SVOA	No target analytes were detected. 2 TICs were reported.					
		RT 4.85	12 J	4 JB	4 JB	negate	1
		RT 7.12	11 J	2 JB	2 JB	negate	1
	PEST/PCB	Pesticides or PCBs were not detected.					

ATTACHMENT L20

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 17 of 18

NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

B NAME: NYTEST

SAMPLE MATRIX: Water

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/L	LAB REPORT CONC ug/L	QA REPORT CONC ug/L	QA DECISIONS	FOOTNOTE
490	VOA	Methylene Chloride	6 J	14 B	14 JB	negate	1
		0 TICs were reported.					
	SVOA	No target analytes were detected.					
		2 TICs were reported.					
		RT 4.84	12 J	6 JB	6 JB	negate	1
	PEST/PCB	The remaining 1 TIC is acceptable.				qualify	9
		Pesticides or PCBs were not detected.					
	VOA						
491	VOA	Methylene Chloride	6 J	13 B	13 JB	negate	1
		0 TICs were reported.					
	SVOA	No target analytes were detected.					
		3 TICs were reported.					
		RT 4.85	12 J	5 JB	5 JB	negate	1
	PEST/PCB	RT 6.98	7 J	8 JB	8 JB	negate	1
		RT 7.10	11 J	12 JB	12 JB	negate	1
	PEST/PCB						

ATTACHMENT L21

# TARGET & NON-TARGET ANALYTE DATA SUMMARY

Page 18 of 18

TE NAME: Cat Swamp Hill Dump

SAMPLING DATE: June 16, 1994

LAB NAME: NYTEST

SAMPLE MATRIX: Water

FIELD ID	FRACTION	ANALYTE	METHOD BLANK CONC ug/L	LAB REPORT CONC ug/L	QA REPORT CONC ug/L	QA DECISIONS	FOOTNOTE
493	VOA	Methylene Chloride	6 J	14 B	14 JB	negate	1
		Trichloroethene	U	4 J	4 J	qualify	6
		2 TICs were reported.					
		RT 18.04	U	10 J	10 J	negate	3
		RT 22.17	U	6 J	6 J	negate	3
	SVOA	No target analytes were detected.					
		7 TICs were reported.					
		RT 4.80	12 J	7 JB	7 JB	negate	1
		RT 6.93	7 J	13 JB	13 JB	negate	1
		RT 7.07	11 J	18 JB	18 JB	negate	1
		The remaining 4 TICs are acceptable.				qualify	9
	PEST/PCB	Pesticides or PCBs were not detected.					
496	VOA	Methylene Chloride	6 J	15 B	15 JB	negate	1
		3 TICs were reported.					
		The non-target data is acceptable.				qualify	9
497	VOA	Methylene Chloride	6 J	17 B	17 B	negate	1
		1 TIC was reported.					
		The non-target data is acceptable.				qualify	9

#### FOOTNOTES:

1. The value reported in the sample is less than or equal to three (3) times the value in the method blank. It is the policy of NJDEP-DPFSR to negate the reported value due to probable contamination unrelated to the actual sample.
2. The value reported is greater than three (3) times the value in the method blank and is considered "real". However, the reported value must be quantitatively qualified "J" due to the method blank contamination. The "B" qualifier alerts the end-user to the presence of this analyte in the method blank.
3. The value reported is less than or equal to three (3) times the value in the trip/field blank. It is the policy of NJDEP-DPFSR to negate the reported value as due to probable contamination unrelated to the actual sample. The end-user, however, is alerted that a reportable quantity of the analyte was detected.
4. This sample concentration was corrected for the moisture content. The value reported prior to the % moisture correction is less than or equal to three (3) times the value in the method blank, trip blank or field blank. It is the policy of NJDEP-DPFSR to negate the reported value due to probable laboratory contamination unrelated to the actual sample. The end-user is alerted that a reportable quantity of the analyte was detected.
5. This sample concentration was corrected for moisture content. The value reported prior to the % moisture correction is greater than three (3) times the value in the method blank, trip blank or field blank. The reported value must be quantitatively qualified "J" due to the blank contamination.
6. The reported concentration is quantitatively qualified because the concentration is below the CRQL.
7. Please refer to the cover memo for specific details.
8. The internal standard area did not meet the QC criteria. Therefore, all results using this internal standard for quantitation are quantitatively qualified.
9. The non-target compound is qualified "J" and considered quantitatively to be an estimated value because relative response factors are not calculated for non-target compounds.
10. The laboratory was required to dilute the samples to bring the peaks onto scale. The CLP program requires dilutions to be indicated with the "D" qualifier.
11. The reported analyte is qualified because the calculated concentrations on two different columns had a %D greater than 25%.
12. The fraction is rejected because three of the base-neutral surrogate percent recoveries are unacceptable.
13. The laboratory reported the incorrect concentration. The concentration reported by QAS is the correct value.

## FOOTNOTES:

1. The value reported in the sample is less than or equal to three (3) times the value in the method blank. It is the policy of NJDEP-DPFSR to negate the reported value due to probable contamination unrelated to the actual sample.
2. The value reported is greater than three (3) times the value in the method blank and is considered "real". However, the reported value must be quantitatively qualified "J" due to the method blank contamination. The "B" qualifier alerts the end-user to the presence of this analyte in the method blank.
3. The value reported is less than or equal to three (3) times the value in the trip/field blank. It is the policy of NJDEP-DPFSR to negate the reported value as due to probable contamination unrelated to the actual sample. The end-user, however, is alerted that a reportable quantity of the analyte was detected.
4. This sample concentration was corrected for the moisture content. The value reported prior to the % moisture correction is less than or equal to three (3) times the value in the method blank, trip blank or field blank. It is the policy of NJDEP-DPFSR to negate the reported value due to probable laboratory contamination unrelated to the actual sample. The end-user is alerted that a reportable quantity of the analyte was detected.
5. This sample concentration was corrected for moisture content. The value reported prior to the % moisture correction is greater than three (3) times the value in the method blank, trip blank or field blank. The reported value must be quantitatively qualified "J" due to the blank contamination.
6. The reported concentration is quantitatively qualified because the concentration is below the CRQL.
7. Please refer to the cover memo for specific details.
8. The internal standard area did not meet the QC criteria. Therefore, all results using this internal standard for quantitation are quantitatively qualified.
9. The non-target compound is qualified "J" and considered quantitatively to be an estimated value because relative response factors are not calculated for non-target compounds.
10. The laboratory was required to dilute the samples to bring the peaks onto scale. The CLP program requires dilutions to be indicated with the "D" qualifier.
11. The reported analyte is qualified because the calculated concentrations on two different columns had a %D greater than 25%.
12. The fraction is rejected because three of the base-neutral surrogate percent recoveries are unacceptable.
13. The laboratory reported the incorrect concentration. The concentration reported by QAS is the correct value.



# State of New Jersey

## DEPARTMENT OF ENVIRONMENTAL PROTECTION

CHRISTINE TODD WHITMAN  
Governor

ROBERT C. SHINN, JR.  
Commissioner

### MEMORANDUM

TO: Frank Sorce  
Site Assessment Section

FROM: Joseph Sanguiliano 8 11/16/94  
Quality Assurance Section  
Bureau of Environmental Measurements and Quality Assurance

SUBJECT: Analytical Data Validation of the June 17, 1994 sampling  
event conducted at Cat Swamp Hill Dump. Analysis by NyTest  
Environmental Inc. Port Washington, N.Y.

NOV 16 1994

#### SAMPLES REVIEWED

<u>FIELD ID</u>	<u>LAB ID</u>	<u>COLLECTION DATE</u>	<u>MATRIX</u>
459	108601	6/17/94	SOIL
460	108604	6/17/94	SOIL
461	108605	6/17/94	SOIL
462	108606	6/17/94	SOIL
463	108607	6/17/94	SOIL
464	108608	6/17/94	SOIL
465	108609	6/17/94	SOIL
466	108610	6/17/94	SOIL
467	108611	6/17/94	SOIL
468	108612	6/17/94	SOIL
469	108613	6/17/94	SOIL
470	108614	6/17/94	SOIL
471	108615	6/17/94	SOIL
472	108616	6/17/94	SOIL
473	108617	6/17/94	SOIL
474	108618	6/17/94	SOIL
476	108619	6/17/94	SOIL
477	108620	6/17/94	SOIL
478	108621	6/17/94	SOIL
480	108622	6/17/94	SOIL
481	108623	6/17/94	SOIL
482	108624	6/17/94	SOIL
484	108625	6/17/94	SOIL
485	108626	6/17/94	SOIL
486	108627	6/17/94	SOIL
487	108628	6/17/94	SOIL
488	108629	6/17/94	AQUEOUS
489	108632	6/17/94	AQUEOUS
490	108633	6/17/94	AQUEOUS
491	108634	6/17/94	AQUEOUS
493	108635	6/17/94	AQUEOUS

The Quality Assurance Section, Bureau of Environmental Measurements and Quality Assurance, Division of Publicly Funded Site Remediation, has reviewed the above mentioned samples for Inorganics. Please refer to the detailed data validation report and the Target Analyte summary for additional information. Specific comments are provided below.

Inorganics

The Inorganics analysis was performed according to the CLP Statement of Work (Document ILM03.0) and the data are acceptable. Please note the following minor deficiencies:

Certain analytes were qualified because of the following QA/QC outliers: CRDL, sample spike, duplicate, serial dilution, and Graphite Furnace AA post spike analyses. Please refer to the Target Analyte Summary for the affected analytes.

If you have any questions concerning this review, please contact this office at 633-0752.

c. William Lowry, BEMQA



# Target Analyte Summary List

Site Name: CAT SWAMP

Sampling Date: 6/17/94

Page 1 of 12

Sample	Analyte	Method Blank Conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
<b>Sample 459</b>						
INORGANICS (mg/kg):						
	Aluminum	U	1800	1800		
	Antimony	7.398 J	8.2 JB	8.2 JB	negate	6
	Arsenic	U	7.7	7.7		
	Barium	U	93.2	93.2		
	Beryllium	U	1.0 J	1.0 J	qualify	1
	Cadmium	U	0.45 UJ	0.45 UJ	qualify	2
	Calcium	U	4570 J	4570 J	qualify	3
	Chromium	U	36.4	36.4		
	Cobalt	U	18.1	18.1		
	Copper	U	22.7 J	22.7 J	qualify	2
	Iron	U	36900	36900		
	Lead	U	25.9	25.9		
	Magnesium	U	5170	5170		
	Manganese	U	741 J	741 J	qualify	2
	Mercury	U	0.21	0.21		
	Nickel	U	56.0 J	56.0 J	qualify	2
	Potassium	U	870 J	870 J	qualify	1
	Selenium	U	1.2 UJ	1.2 UJ	qualify	9
	Vanadium	U	59.7	59.7		
	Zinc	U	610 J	610 J	qualify	2

## Sample 460

### INORGANICS (mg/kg):

	Aluminum	U	1800	1800		
	Antimony	7.398 J	9.2 JB	9.2 JB	negate	6
	Arsenic	U	2.7 J	2.7 J	qualify	1
	Barium	U	348	348		
	Beryllium	U	4.4	4.4		
	Cadmium	U	3.3 J	3.3 J	qualify	2
	Calcium	U	102000 J	102000 J	qualify	3
	Chromium	U	35.3	35.3		
	Cobalt	U	12.0	12.0		
	Copper	U	1930 J	1930 J	qualify	2
	Iron	U	43200	43200		
	Lead	U	350 J	359 J	qualify	2
	Magnesium	U	15500	15500		
	Manganese	U	1680 J	1680 J	qualify	2
	Nickel	U	56.0 J	56.0 J	qualify	2
	Potassium	U	5040	5040		
	Selenium	U	1.9 J	1.9 J	qualify	4, 5
	Silver	U	3.4	3.4		
	Sodium	U	824 J	824 J	qualify	1
	Vanadium	U	37.1	37.1		
	Zinc	U	12700 J	12700 J	qualify	2

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
<b>Sample 461</b>						
<b>INORGANICS (mg/kg) :</b>						
Aluminum		U	17500	17500		
Antimony	7.398 J		7.0 UJ	7.0 UJ	qualify	2, 8
Arsenic		U	3.0	3.0		
Barium		U	80.9	80.9		
Beryllium		U	1.6	1.6		
Cadmium		U	1.1 J	1.1 J	qualify	1, 2
Calcium		U	2940 J	2940 J	qualify	3
Chromium		U	17.2 J	17.2 J	qualify	11
Cobalt		U	16.1	16.1		
Copper		U	28.9 J	28.9 J	qualify	2
Iron		U	31000	31000		
Lead		U	7.6	7.6		
Magnesium		U	3050	3050		
Manganese		U	654 J	654 J	qualify	2
Nickel		U	9.9 J	9.9 J	qualify	2
Potassium		U	1340	1340		
Selenium		U	1.1 UJ	1.1 UJ	qualify	9
Silver		U	1.9 J	1.9 J	qualify	1
Vanadium		U	46.3	46.3		
Zinc		U	205 J	205 J	qualify	2

**Sample 462****INORGANICS (mg/kg) :**

Aluminum		U	14000	14000		
Antimony	7.398 J		7.1 UJ	7.1 UJ	qualify	2, 8
Arsenic		U	1.9 J	1.9 J	qualify	1
Barium		U	109	109		
Cadmium		U	0.46 U	0.46 UJ	qualify	2
Calcium		U	3490 J	3490 J	qualify	3
Chromium		U	13.3 J	13.3 J	qualify	11
Cobalt		U	11.0 J	11.0 J	qualify	1
Copper		U	10.8 J	10.8 J	qualify	2
Iron		U	27500	27500		
Lead		U	4.0	4.0		
Magnesium		U	3470	3470		
Manganese		U	672 J	672 J	qualify	2
Nickel		U	10.9 J	10.9 J	qualify	2
Potassium		U	1340	1340		
Selenium		U	1.2 UJ	1.2 UJ	qualify	9
Silver		U	4.1 J	4.1 J	qualify	1
Vanadium		U	29.9	29.9		
Zinc		U	99.4 J	99.4 J	qualify	2

**Sample 463****INORGANICS (mg/kg) :**

Aluminum		U	40400	40400		
Antimony	7.398 J		7.3 UJ	7.3 UJ	qualify	2, 8
Arsenic		U	2.4 UJ	2.4 UJ	qualify	7
Barium		U	110	110		
Cadmium		U	0.47 UJ	0.47 UJ	qualify	2
Calcium		U	14500 J	14500 J	qualify	3
Chromium		U	52.9	52.9		
Cobalt		U	23.8	23.8		
Copper		U	2.4 UJ	2.4 UJ	qualify	2
Iron		U	33900	33900		

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
	Lead	U	2.9 J	2.9 J	qualify	2
	Magnesium	U	8810	8810		
	Manganese	U	713 J	713 J	qualify	2
	Nickel	U	36.1 J	36.1 J	qualify	2
	Potassium	U	1950	1950		
	Selenium	U	1.2 UJ	1.2 UJ	qualify	7, 9
	Silver	U	2.9	2.9		
	Sodium	U	1880	1880		
	Vanadium	U	84.7	84.7		
	Zinc	U	143 J	143 J	qualify	2

**Sample 464**

INORGANICS (mg/kg):

	Aluminum	U	15200	15200		
	Antimony	7.398 J	7.0 UJ	7.0 UJ	qualify	2, 8
	Arsenic	U	2.2 J	2.2 J	qualify	1
	Barium	U	64.8	64.8		
	Cadmium	U	0.45 UJ	0.45 UJ	qualify	2
	Calcium	U	1850 J	1850 J	qualify	3
	Chromium	U	16.5 J	16.5 J	qualify	11
	Cobalt	U	12.5	12.5		
	Copper	U	11.4 J	11.4 J	qualify	2
	Iron	U	29600	29600		
	Lead	U	10.3 J	10.3 J	qualify	2
	Magnesium	U	2800	2800		
	Manganese	U	519 J	519 J	qualify	2
	Nickel	U	14.3 J	14.3 J	qualify	2
	Potassium	U	1230	1230		
	Selenium	U	1.1 UJ	1.1 UJ	qualify	7, 9
	Silver	U	5.1	5.1		
	Vanadium	U	40.8	40.8		
	Zinc	U	104 J	104 J	qualify	2

**Sample 465**

INORGANICS (mg/kg):

	Aluminum	U	16800	16800		
	Antimony	7.398 J	6.8 UJ	6.8 UJ	qualify	2, 8
	Arsenic	U	1.4 J	1.4 J	qualify	1
	Barium	U	76.6	76.6		
	Beryllium	U	1.1	1.1		
	Cadmium	U	0.44 UJ	0.44 UJ	qualify	2
	Calcium	U	3200 J	3200 J	qualify	3
	Chromium	U	23.5	23.5		
	Cobalt	U	11.8	11.8		
	Copper	U	13.3 J	13.3 J	qualify	2
	Iron	U	31400	31400		
	Lead	U	7.2 J	7.2 J	qualify	2
	Magnesium	U	3600	3600		
	Manganese	U	617 J	617 J	qualify	2
	Nickel	U	16.7 J	16.7 J	qualify	2
	Potassium	U	1460	1460		
	Selenium	U	1.1 UJ	1.1 UJ	qualify	9
	Silver	U	4.9	4.9		
	Vanadium	U	44.9	44.9		
	Zinc	U	230 J	230 J	qualify	2

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
<b>Sample 466</b>						
INORGANICS (mg/kg) :						
Aluminum		U	31600	31600		
Antimony	7.398 J	U	9.5 JB	9.5 JB	negate	6
Arsenic		U	1.5 UJ	1.5 UJ	qualify	7
Barium		U	336	336		
Beryllium		U	3.8	3.8		
Cadmium		U	0.58 UJ	0.58 UJ	qualify	2
Calcium		U	111000 J	111000 J	qualify	3
Chromium		U	39.5	39.5		
Cobalt		U	11.7 J	11.7 J	qualify	1
Copper		U	81.8 J	81.8 J	qualify	2
Iron		U	49600	49600		
Lead		U	262 J	262 J	qualify	2
Magnesium		U	25600	25600		
Manganese		U	1960 J	1960 J	qualify	2
Mercury		U	0.81	0.81		
Nickel		U	23.9 J	23.9 J	qualify	2
Potassium		U	5870	5870		
Selenium		U	1.5 UJ	1.5 UJ	qualify	7, 9
Silver		U	5.7	5.7		
Sodium		U	840 J	840 J	qualify	1
Vanadium		U	40.8	40.8		
Zinc		U	735 J	735 J	qualify	2
Cyanide		U	0.86	0.86		
<b>Sample 467</b>						
INORGANICS (mg/kg) :						
Aluminum		U	36400	36400		
Antimony	7.398 J	U	15.1 JB	15.1 JB	negate	6
Arsenic		U	14.9	14.9		
Barium		U	488	488		
Beryllium		U	4.6	4.6		
Cadmium		U	0.53 UJ	0.53 UJ	qualify	2
Calcium		U	136000 J	136000 J	qualify	3
Chromium		U	43.9	43.9		
Cobalt		U	14.9	14.9		
Copper		U	139 J	139 J	qualify	2
Iron		U	72900	72900		
Lead		U	190 J	190 J	qualify	2
Magnesium		U	28300	28300		
Manganese		U	1890 J	1890 J	qualify	2
Mercury		U	0.42	0.42		
Nickel		U	30.5 J	30.5 J	qualify	2
Potassium		U	5870	5870		
Selenium		U	2.4 J	2.4 J	qualify	4
Silver		U	2.8	2.8		
Sodium		U	1100 J	1100 J	qualify	1
Vanadium		U	31.5	31.5		
Zinc		U	486 J	486 J	qualify	2
Cyanide		U	0.91	0.91		
<b>Sample 468</b>						
INORGANICS (mg/kg) :						
Aluminum		U	31400	31400		
Antimony	7.398 J	U	8.7 UJ	8.7 UJ	qualify	2, 8
Barium		U	273	273		

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
	Beryllium	U	2.5	2.5		
	Cadmium	U	3.9 J	3.9 J	qualify	2
	Calcium	U	46900 J	46900 J	qualify	3
	Chromium	U	51.9	51.9		
	Cobalt	U	15.5	15.5		
	Copper	U	123 J	123 J	qualify	2
	Iron	U	64000	64000		
	Lead	U	359 J	359 J	qualify	2
	Magnesium	U	9940	9940		
	Manganese	U	1440 J	1440 J	qualify	2
	Mercury	U	1.1	1.1		
	Nickel	U	38.5 J	38.5 J	qualify	2
	Potassium	U	2420	2420		
	Selenium	U	1.4 UJ	1.4 UJ	qualify	9
	Silver	U	7.7	7.7		
	Vanadium	U	62.9	62.9		
	Zinc	U	657 J	657 J	qualify	2
<b>Sample 469</b>						
INORGANICS (mg/kg):						
	Aluminum	U	18200	18200		
	Antimony	7.398 J	8.6 UJ	8.6 UJ	qualify	2, 8
	Arsenic	U	6.5	6.5		
	Barium	U	122	122		
	Cadmium	U	1.1 J	1.1 J	qualify	2
	Calcium	U	9860 J	9860 J	qualify	3
	Chromium	U	30.0	30.0		
	Cobalt	U	14.1	14.1		
	Copper	U	40.0 J	40.0 J	qualify	2
	Iron	U	38000	38000		
	Lead	U	55.3 J	55.3 J	qualify	2
	Magnesium	U	4900	4900		
	Manganese	U	2010 J	2010 J	qualify	2
	Mercury	U	0.22	0.22		
	Nickel	U	20.6 J	20.6 J	qualify	2
	Potassium	U	1020	1020		
	Selenium	U	1.4 UJ	1.4 UJ	qualify	7, 9
	Silver	U	2.9	2.9		
	Vanadium	U	50.7	50.7		
	Zinc	U	537 J	537 J	qualify	2
<b>Sample 470</b>						
INORGANICS (mg/kg):						
	Aluminum	U	23300	23300		
	Antimony	7.398 J	43.8 JB	43.8 JB	qualify	2, 10, 12
	Arsenic	U	9.3	9.3		
	Barium	U	342	342		
	Beryllium	U	2.5	2.5		
	Cadmium	U	13.4 J	13.4 J	qualify	2
	Calcium	U	63200 J	63200 J	qualify	3
	Chromium	U	68.9	68.9		
	Cobalt	U	23.5	23.5		
	Copper	U	212 J	212 J	qualify	2
	Iron	U	148000	148000		
	Lead	U	5400 J	5400J	qualify	2
	Magnesium	U	13300	13300		
	Manganese	U	1790 J	1790 J	qualify	2

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
	Mercury	U	1.3	1.3		
	Nickel	U	52.9 J	52.9 J	qualify	2
	Potassium	U	3390	3390		
	Selenium	U	1.4 UJ	1.4 UJ	qualify	7, 9
	Silver	U	11.9	11.9		
	Vanadium	U	46.9	46.9		
	Zinc	U	2270 J	2270 J	qualify	2
	Cyanide	U	2.1	2.1		
<b>Sample 471</b>						
<b>INORGANICS (mg/kg) :</b>						
	Aluminum	U	25600	25600		
	Antimony	7.398 J	32.5 JB	32.5 JB	qualify	2, 10, 12
	Arsenic	U	8.3	8.3		
	Barium	U	986	986		
	Beryllium	U	2.5	2.5		
	Cadmium	U	2.5 J	2.5 J	qualify	2
	Calcium	U	74300 J	74300 J	qualify	3
	Chromium	U	90.7	90.7		
	Cobalt	U	20.2	20.2		
	Copper	U	246 J	246 J	qualify	2
	Iron	U	104000	104000		
	Lead	U	703 J	703 J	qualify	2
	Magnesium	U	14300	14300		
	Manganese	U	1710 J	1710 J	qualify	2
	Mercury	U	1.8	1.8		
	Nickel	U	37.2 J	37.2 J	qualify	2
	Potassium	U	3400	3400		
	Selenium	U	2.5 J	2.5 J	qualify	4
	Silver	U	6.3	6.3		
	Vanadium	U	35.3	35.3		
	Zinc	U	1300 J	1300 J	qualify	2
<b>Sample 472</b>						
<b>INORGANICS (mg/kg) :</b>						
	Aluminum	U	50700	50700		
	Antimony	7.398 J	9.1 UJ	9.1 UJ	qualify	2, 8
	Barium	U	387	387		
	Beryllium	U	7.3	7.3		
	Cadmium	U	0.59 UJ	0.59 UJ	qualify	2
	Calcium	U	202000 J	202000 J	qualify	3
	Chromium	U	28.7	28.7		
	Copper	U	35.9 J	35.9 J	qualify	2
	Iron	U	8820	8820		
	Lead	U	91.3 J	91.3 J	qualify	2
	Magnesium	U	62700	62700		
	Manganese	U	1800 J	1800 J	qualify	2
	Mercury	U	0.24	0.24		
	Nickel	U	37.8 J	37.8 J	qualify	2
	Potassium	U	9530	9530		
	Selenium	U	2.2 J	2.2 J	qualify	4
	Silver	U	2.8	2.8		
	Sodium	U	1540 J	1540 J	qualify	1
	Thallium	U	1.5 UJ	1.5 UJ	qualify	7
	Vanadium	U	28.7	28.7		
	Zinc	U	342 J	342 J	qualify	2
	Cyanide	U	0.77	0.77		

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
<b>Sample 473</b>						
INORGANICS (mg/kg):						
Aluminum		U	24900	24900		
Antimony		7.398 J	21.6 JB	21.6 JB	negate	6
Arsenic		U	8.7	8.7		
Barium		U	137	137		
Beryllium		U	1.2 J	1.2 J	qualify	1
Cadmium		U	0.59 UJ	0.59 UJ	qualify	2
Calcium		U	10800 J	10800 J	qualify	3
Chromium		U	34.1	34.1		
Cobalt		U	16.0	16.0		
Copper		U	40.7 J	40.7 J	qualify	2
Iron		U	40500	40500		
Lead		U	84.0 J	84.0 J	qualify	2
Magnesium		U	5960	5960		
Manganese		U	1590 J	1590 J	qualify	2
Mercury		U	0.28	0.28		
Nickel		U	30.5 J	30.5 J	qualify	2
Potassium		U	1430	1430		
Selenium		U	1.5 UJ	1.5 UJ	qualify	7, 9
Vanadium		U	45.4	45.4		
Zinc		U	718 J	718 J	qualify	2

<b>Sample 474</b>						
INORGANICS (mg/kg):						
Aluminum		U	31700	31700		
Antimony		7.398 J	22.6 JB	22.6 JB	negate	6
Arsenic		U	6.3	6.3		
Barium		U	196	196		
Beryllium		U	2.9	2.9		
Cadmium		U	2.0 J	2.0 J	qualify	2
Calcium		U	58500 J	58500 J	qualify	3
Chromium		U	121	121		
Cobalt		U	17.5	17.5		
Copper		U	41.1 J	41.1 J	qualify	2
Iron		U	44800	44800		
Lead		U	95.7 J	95.7 J	qualify	2
Magnesium		U	12900	12900		
Manganese		U	1360 J	1360 J	qualify	2
Mercury		U	0.60	0.60		
Nickel		U	35.4 J	35.4 J	qualify	2
Potassium		U	2980	2980		
Selenium		U	1.1 UJ	1.1 UJ	qualify	9
Vanadium		U	53.8	53.8		
Zinc		U	825 J	825 J	qualify	2

<b>Sample 476</b>						
INORGANICS (mg/kg):						
Aluminum		U	25900	25900		
Antimony		7.398 J	10.6 JB	10.6 JB	negate	6
Arsenic		U	7.7	7.7		
Barium		U	274	274		
Beryllium		U	3.5	3.5		
Cadmium		U	0.55 UJ	0.55 UJ	qualify	2
Calcium		U	79400 J	79400 J	qualify	3
Chromium		U	105	105		

Sample	Analyte	Method Blank/ conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
	Cobalt	U	15.5	15.5		
	Copper	U	290 J	290 J	qualify	2
	Iron	U	54600	54600		
	Lead	U	526 J	526 J	qualify	2
	Magnesium	U	16800	16800		
	Manganese	U	1020 J	1020 J	qualify	2
	Mercury	U	0.57	0.57		
	Nickel	U	1180 J	1180 J	qualify	2
	Potassium	U	3600	3600		
	Selenium	U	1.4 UJ	1.4 UJ	qualify	7, 9
	Vanadium	U	28.3	28.3		
	Zinc	U	404 J	404 J	qualify	2

## Sample 477

INORGANICS (mg/kg):

	Aluminum	U	19200	19200		
	Antimony	7.398 J	8.0 UJ	8.0 UJ	qualify	2, 8
	Arsenic	U	1.5 J	1.5 J	qualify	1
	Barium	U	97.8	97.8		
	Beryllium	U	2.6	2.6		
	Cadmium	U	0.52 UJ	0.52 UJ	qualify	2
	Calcium	U	11500 J	11500 J	qualify	3
	Chromium	U	26.4	26.4		
	Cobalt	U	25.3J	25.3J	qualify	1
	Copper	U	42.8 J	42.8 J	qualify	2
	Iron	U	38900	38900		
	Lead	U	60.8 J	60.8 J	qualify	2
	Magnesium	U	5770	5770		
	Manganese	U	453 J	453 J	qualify	2
	Mercury	U	0.21	0.21		
	Nickel	U	2990 J	2990 J	qualify	2
	Potassium	U	4100 J	4100 J	qualify	1
	Selenium	U	1.3 UJ	1.3 UJ	qualify	9
	Vanadium	U	68.5	68.5		
	Zinc	U	191 J	191 J	qualify	2

## Sample 478

INORGANICS (mg/kg):

	Aluminum	U	5130	5130		
	Antimony	7.398 J	6.8 UJ	6.8 UJ	qualify	2, 8
	Arsenic	U	1.8 J	1.8 J	qualify	1
	Barium	U	15.8 J	15.8 J	qualify	1
	Beryllium	U	1.2	1.2		
	Cadmium	U	0.44 UJ	0.44 UJ	qualify	2
	Calcium	U	3420 J	3420 J	qualify	3
	Chromium	U	47.4	47.4		
	Cobalt	U	7.1 J	7.1 J	qualify	1
	Copper	U	235 J	235 J	qualify	2
	Iron	U	17300	17300		
	Lead	U	55.2 J	55.2 J	qualify	2
	Magnesium	U	1780	1780		
	Manganese	U	77.7 J	77.7 J	qualify	2
	Nickel	U	22.4 J	22.4 J	qualify	2
	Potassium	U	767 J	767 J	qualify	1
	Selenium	U	1.1 UJ	1.1 UJ	qualify	9
	Vanadium	U	41.6	41.6		
	Zinc	U	62.9 J	62.9 J	qualify	2



Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
<b>Sample 480</b>						
INORGANICS (mg/kg) :						
	Aluminum	U	15700	15700		
	Antimony	7.398 J	19.3 JB	19.3 JB	negate	6
	Arsenic	U	32.2	32.2		
	Barium	U	512	512		
	Beryllium	U	3.0	3.0		
	Cadmium	U	0.46 UJ	0.46 UJ	qualify	2
	Calcium	U	51200 J	51200 J	qualify	3
	Chromium	U	19.1 J	19.1 J	qualify	11
	Cobalt	U	31.4	31.4		
	Copper	U	539 J	539 J	qualify	2
	Iron	U	28900	28900		
	Lead	U	172 J	172 J	qualify	2
	Magnesium	U	22800	22800		
	Manganese	U	797 J	797 J	qualify	2
	Nickel	U	60.8 J	60.8 J	qualify	2
	Potassium	U	5110	5110		
	Selenium	U	2.3 J	2.3 J	qualify	4
	Sodium	u	1360	1360		
	Vanadium	U	29.8	29.8		
	Zinc	U	586 J	586 J	qualify	2

<b>Sample 481</b>						
INORGANICS (mg/kg) :						
	Aluminum	U	43600	43600		
	Antimony	7.398 J	8.3 UJ	8.3 UJ	qualify	2, 8
	Arsenic	U	4.3 J	4.3 J	qualify	1
	Barium	U	409	409		
	Beryllium	U	7.0	7.0		
	Cadmium	U	3.4 J	3.4 J	qualify	2
	Calcium	U	170000 J	170000 J	qualify	3
	Chromium	U	24.5	24.5		
	Cobalt	U	9.1 J	9.1 J	qualify	1
	Copper	U	48.9 J	48.9 J	qualify	2
	Iron	U	31400	31400		
	Lead	U	85.8 J	85.8 J	qualify	2
	Magnesium	U	32700	32700		
	Manganese	U	3540 J	3540 J	qualify	2
	Mercury	U	0.30	0.30		
	Nickel	U	23.3 J	23.3 J	qualify	2
	Potassium	U	7120	7120		
	Selenium	U	3.6 J	3.6 J	qualify	4
	Sodium	u	1780	1780		
	Vanadium	U	21.8	21.8		
	Zinc	U	2020 J	2020 J	qualify	2

<b>Sample 482</b>						
INORGANICS (mg/kg) :						
	Aluminum	U	50400	50400		
	Antimony	7.398 J	10.6 JB	10.6 JB	negate	6
	Arsenic	U	3.3 J	3.3 J	qualify	1, 7
	Barium	U	493	493		
	Beryllium	U	8.8	8.8		
	Cadmium	U	4.3 J	4.3 J	qualify	2
	Calcium	U	18400 J	18400 J	qualify	3

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
	Chromium	U	89.8	89.8		
	Cobalt	U	11.8	11.8		
	Copper	U	139 J	139 J	qualify	2
	Iron	U	14600	14600		
	Lead	U	391 J	391 J	qualify	2
	Magnesium	U	4270	4270		
	Manganese	U	2430 J	2430 J	qualify	2
	Mercury	U	0.18	0.18		
	Nickel	U	48.6 J	48.6 J	qualify	2
	Potassium	U	9880	9880		
	Selenium	U	3.2 J	3.2 J	qualify	4
	Silver	U	44.9	44.9		
	Sodium	U	1690	1690		
	Thallium	U	1.1 UJ	1.1 UJ	qualify	7
	Vanadium	U	40.2	40.2		
	Zinc	U	393 J	393 J	qualify	2
	Cyanide	U	1.3	1.3		

**Sample 484****INORGANICS (mg/kg):**

	Aluminum	U	16000	16000		
	Antimony	7.398 J	66.5 JB	66.5 JB	negate	6
	Arsenic	U	5.6 UJ	5.6 UJ	qualify	7
	Barium	U	124 J	124 J	qualify	1
	Cadmium	U	9.6 J	9.6 J	qualify	2
	Calcium	U	17600 J	17600 J	qualify	3
	Chromium	U	25.0	25.0		
	Copper	U	19.4 J	19.4 J	qualify	1, 2
	Iron	U	11800	11800		
	Lead	U	76.9	76.9		
	Magnesium	U	3315 J	3315 J	qualify	1
	Manganese	U	1550 J	1550 J	qualify	2
	Selenium	U	12.7 J	12.7 J	qualify	4
	Vanadium	U	31.2 J	31.2 J	qualify	1
	Zinc	U	607 J	607 J	qualify	2

**Sample 485****INORGANICS (mg/kg):**

	Aluminum	U	34700	34700		
	Antimony	7.398 J	33.8 JB	33.8 JB	negate	6
	Arsenic	U	5.4 J	5.4 J	qualify	1
	Barium	U	276	276		
	Cadmium	U	5.3 J	5.3 J	qualify	2
	Calcium	U	18700 J	18700 J	qualify	3
	Chromium	U	44.6	44.6		
	Copper	U	27.3 J	27.3 J	qualify	2
	Iron	U	18100	18100		
	Lead	U	97.1	97.1		
	Magnesium	U	3970 J	3970 J	qualify	1
	Manganese	U	1820 J	1820 J	qualify	2
	Mercury	U	0.52	0.52		
	Selenium	U	8.1 J	8.1 J	qualify	4
	Thallium	U	21.7	21.7		
	Vanadium	U	51.1	51.1		
	Zinc	U	985 J	985 J	qualify	2

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
--------	---------	--------------------------	------------------------	------------------------	-----------------	-----------

**Sample 486****INORGANICS (mg/kg) :**

Aluminum	U	21200	21200			
Antimony	7.398 J	9.5 JB	9.5 JB	negate		6
Arsenic	U	5.3	5.3			
Barium	U	138	138			
Beryllium	U	1.1 J	1.1 J	qualify		1
Cadmium	U	0.50 UJ	0.50 UJ	qualify		2
Calcium	U	7450 J	7450 J	qualify		3
Chromium	U	43.7	43.7			
Cobalt	U	16.9	16.9			
Copper	U	33.5 J	33.5 J	qualify		2
Iron	U	47000	47000			
Lead	U	29.7	29.7			
Magnesium	U	4490	4490			
Manganese	U	1570 J	1570 J	qualify		2
Mercury	U	0.21	0.21			
Nickel	U	32.4 J	32.4 J	qualify		2
Potassium	U	894 J	894 J	qualify		1
Selenium	U	1.3 UJ	1.3 UJ	qualify		7, 9
Silver	U	2.4 J	2.4 J	qualify		1
Thallium	U	1.3 UJ	1.3 UJ	qualify		7
Vanadium	U	33.6	33.6			
Zinc	U	591 J	591 J	qualify		2

**Sample 487****INORGANICS (mg/kg) :**

Aluminum	U	41600	41600			
Antimony	7.398 J	13.9 JB	13.9 JB	negate		6
Barium	U	461	461			
Beryllium	U	6.3	6.3			
Cadmium	U	0.48 UJ	0.48 UJ	qualify		2
Calcium	U	166000 J	166000 J	qualify		3
Chromium	U	22.0	22.0			
Cobalt	U	8.1 J	8.1 J	qualify		1
Copper	U	213 J	213 J	qualify		2
Iron	U	12800	12800			
Lead	U	230 J	230 J	qualify		2
Magnesium	U	34400	34400			
Manganese	U	2350 J	2350 J	qualify		2
Mercury	U	0.20	0.20			
Nickel	U	14.1 J	14.1 J	qualify		2
Potassium	U	8730	8730			
Selenium	U	3.1 J	3.1 J	qualify		4
Sodium	U	1530	1530			
Thallium	U	1.2 UJ	1.2 UJ	qualify		7
Vanadium	U	19.8	19.8			
Zinc	U	256 J	256 J	qualify		2

**Sample 488****INORGANICS (ug/L) :**

Barium	U	55.0 U	55.0 UJ	qualify		8
Calcium	U	22500 J	22500 J	qualify		3
Iron	U	90.4 J	90.4 J	qualify		1
Lead	U	3.0 U	3.0 UJ	qualify		8
Magnesium	U	7850	7850			

Sample	Analyte	Method Blank conc.	Lab Report Conc.	QAS Report Conc.	QAS Decision	Footnotes
	Sodium	U	3690 J	3690 J	qualify	1
<b>Sample 489</b>						
INORGANICS(ug/L ):						
	Barium	U	55.0 U	55.0 UJ	qualify	8
	Calcium	U	5300 J	5300 J	qualify	3
	Copper	U	795 J	795 J	qualify	2
	Lead	U	3.0 U	3.0 UJ	qualify	8
<b>Sample 490</b>						
INORGANICS(ug/L ):						
	Barium	U	55.0 U	55.0 UJ	qualify	8
	Calcium	U	30100 J	30100 J	qualify	3
	Lead	U	3.0 U	3.0 UJ	qualify	8
	Magnesium	U	9590	9590		
	Potassium	U	1890 J	1890 J	qualify	1
	Sodium	U	16200	16200		
	Zinc	U	29.2 J	29.2 J	qualify	2
<b>Sample 491</b>						
INORGANICS(ug/L ):						
	Barium	U	55.0 U	55.0 UJ	qualify	8
	Calcium	U	21900 J	21900 J	qualify	3
	Copper	U	159 J	159 J	qualify	2
	Lead	U	5.2 J	5.2 J	qualify	12
	Magnesium	U	7210	7210		
	Manganese	U	8.0 J	8.0 J	qualify	1
	Sodium	U	21900	21900		
<b>Sample 493</b>						
INORGANICS(ug/L ):						
	Barium	U	55.0 U	55.0 UJ	qualify	8
	Calcium	U	21500 J	21500 J	qualify	3
	Iron	U	87.6 J	87.6 J	qualify	1
	Lead	U	3.0 U	3.0 UJ	qualify	8
	Magnesium	U	7630	7630		
	Sodium	U	3550 J	3550 J	qualify	1

## FOOTNOTES

1. The reported concentration was quantitatively qualified because the concentration was below the CRDL but greater than the IDL. The concentration is considered estimated since the value obtained is at the low end of the instrument performance.
2. In the duplicate sample analysis for metals, the analyte fell outside the control limits of 20 percent RPD or  $\pm$  CRDL. Therefore, the result for the metal is qualified.
3. The reported metal value is qualified because the Serial Dilution is not within ten percent (10%) of sample concentration.
4. The reported metal value is qualified because the spike recovery was between 30 and 74 percent. The result may be biased low.
5. The result for this analyte is qualified because the correlation coefficient is less than 0.995 for the initial and reanalysis for method of standard addition.
6. The value reported is less than or equal to three (3) times the value in the preparation blank. It is the policy of NJDEP-DPFSR to negate the reported value as due to probable contamination unrelated to the actual sample. The end-user, however, is alerted that a reportable quantity of the analyte was detected.
7. The reported non-detect is qualified because the analytical spike of this analyte during the GFAA analysis was below the recovery range of 85-115%. The reported detection limit may be biased low.
8. This non-detected metal detection limit is qualified (UJ) because the CRDL standard was below the recovery range (80-120 %).
9. The non-detected metal detection limit is qualified (UJ) because the spike recovery is between 30 and 74 percent. The detection limit for this metal could be elevated because of spike recovery.
10. The value reported is greater than three (3) times the value in the preparation blank and is considered "real". However, the reported value must be quantitatively qualified "J" due to the method preparation blank contamination. The "B" qualifier alerts the end-user to the presence of this analyte in the method blank/prep blank.
11. This metal value is qualified because the associated CRDL is above the recovery range of 80% - 120%. The reported concentration may be biased high.
12. This metal value is qualified because the associated CRDL is below the recovery range of 80% - 120%. The reported concentration may be biased low.